

KC CONSTRUCTION CO.

1737 Stout Drive, Ivyland, PA 18974 | 215-443-5553

MARQUETTE LAKE DAM REHABILITATION

Project No. DGS C-0960-0086 Phase 1

TECHNICAL SUBMITTAL

CUSTOMER:



PENNSYLVANIA FISH & BOAT COMMISSION Susan Stanisic, Proposal Coordinator 3rd Floor Arsenal Building 18th & Herr Street, Harrisburg, PA 17103

ENGINEER:



D'APPOLONIA 701 Lodi Road – Floor 2 Pittsburgh, PA 15235





PROPOSAL SUBMITTED BY:

KC CONSTRUCTION CO.

1737 Stout Drive, Ivyland, PA 18974 **Proposal Contact:** Joel Baker (267) 961-0949 joelb@kcconstruct.com



Marguette Lake Dam Rehabilitation

Project No. DGS C-0960-0086 Phase 1

TABLE OF CONTENTS

SECTION 1. TEAM QUALIFICATIONS, EXPERIENCE, AND PAST PERFORMANCE

Section T-1A	Introduction to Project Team	4
Section T-1B	Prime Contractor (Appendix F - Qualifications Statement)	10
Section T-1C Designated Critical Work (Appendix G – Qualifications Statement)		
	- CIP Concrete (Spillways with Watertight/Waterstop Joints)	32
	- Graded Aggregate Filterdrain Construction	51
	- Earthwork (Compaction of Earthen Dam Embankment)	51
Section T-1C	 Designated Critical Work (Appendix G – Qualifications Statement) CIP Concrete (Spillways with Watertight/Waterstop Joints) Graded Aggregate Filterdrain Construction Earthwork (Compaction of Earthen Dam Embankment) 	32 51 51

SECTION 2. PROJECT MANAGEMENT PLAN

•	Section T-2A	Project Management Team	72
•	Section T-2B	Work Plan & Schedule	
		- T-2B.a Overall Project Work Plan & Schedule	
		- T-2B.b Critical Item Work Plans	98
•	Section T-2C	Safety Plan	106
•	Section T-2D	Quality Control Plan	112
•	Section T-2D	Quality Control Plan	112

SECTION 3. STAFFING PLAN

•	Section T-3A	Staffing Resources	128
•	Section T-3B	Skill Training	131
•	Section T-3C	Workforce Sfaety	133

SECTION 4. SUPPORTING DOCUMENTS

•	Section T-4A	Proposal Signature Page (COPY)	136
•	Section T-4B	Non-Collusion Affidavit (COPY)	141



Marquette Lake Dam - Rehabilitation

Project No. DGS C-0960-0086 Phase 1

SECTION 1.

Project Team Qualifications, Experience,

and Past Performance

Marquette Lake Dam Rehabilitation

Project No. DGS C-0960-0086 Phase 1

TECHNICAL SUBMITTAL

Section 1. Project Team Qualifications, Experience and Past Performance

T-1A Introduction to Project Team

4

MARQUETTE LAKE DAM REHABILITATION PROJECT NO. DGS C-0960-0086 PHASE 1

TECHNICAL SUBMITTAL

T-1A Introduction to Project Team

Incorporated in 1983 as a family-owned small business serving as a general contractor, KC Construction Co. has focused on technically challenging heavy civil works projects in both the public and private markets. Growing a reputation as a "can do it" contractor, we utilize in house civil and geotechnical engineering solutions for our projects. In 2000, KC began to focus on Dam Rehabilitation and Flood Protection projects, developing a hand-picked group of project managers and skilled tradesman who take great pride in quality work. Now having worked on over **60** specialty dam, levee, and flood control projects in our region, we offer unmatched experience and expertise with an army of seasoned suppliers, subcontractors and consulting partners in tow. When it comes down to Dam Construction, KC has done it all - Crest Raising, Slope Armoring, Blanket and Toe Drains, Diversion and Control of Water, Seepage Control, Outlet Drains, Conduit Rehabilitation, Labyrinth Spillways, Fusegates, Roller Compacted Concrete (RCC), Shotcrete Repairs, Rip Rap Armoring, and Articulating Concrete Block (ACB) Armoring.

KC Construction – Prime Contractor

KC Construction shall be the Prime Contractor for the project acting as the responsible contact for PA DGS, D'Appolonia, PA DMVA, and any other oversight parties. KC will coordinate, schedule, and monitor the work of our subcontractors for compliance with the project schedule and the contract documents. All our subcontractors are well known in the industry and have previously worked on or are currently working with KC on other dam or flood control projects. The proposed team has no first-time partners.

KC will commit the following personnel to this project:

- John V. Lima, PE | President
- Gino Yannuzzelli | Vice President
- Tim Wintermute | Sr. Project Manager
- Bobby Machiesky, PLS | General Superintendent
- Dan Samoni | Site Foreman

Performance Construction Company – Subcontractor (Spillway CIP Concrete & Water stop)

As a subcontractor on this project, it is not only critical that their tasks be well coordinated and executed, but they must fit within the overall project plan. For critical infrastructure projects, such as this project, it is necessary to assemble a veteran team of professionals with a proven history of success.

Started in 1995, Performance Construction Company serves as a General Contractor, Structural Concrete Contractor and General Trades Contractor. Performance regularly self-performs all cast-in-place concrete for heavy civil type projects including:

- Dam and spillway construction.
- WWTP projects including all concrete, piping, and equipment installation.
- Parking garages and other elevated structural concrete.
- Large industrial projects.
- Installation of specialty items on various projects by utilizing our own skilled, union workforce.

Performance will serve as the Subcontractor for cast in place concrete. The Project Management Team selected for the Marquette Lake Dam project has extensive experience providing project management and inspection services for complex dam projects. Another characteristic that uniquely qualifies the team is the inclusion of licensed plant operatives on the field staff. Performance commits to using the following Project Team personnel for your project:

Eric Eichenberg | Vice President

- Tracks staffing, budget, and expenses
- o Coordinates team efforts and support staff
- Primary reporting to DGS
- Contract administration, including submittals, RFI's, meeting minutes, change order management, monthly reports, and schedule updates.

Brian Mickatavage | General Superintendent

- Monitors job site safety programs
- Ensures a safe working environment
- Runs timely and efficient projects.

Leah Eichenberg | Project Manager

- Attention to detail and quality work make him a valuable member
- Experience in all facets of construction, especially environmental, highway, municipal and commercial construction

Andy Studlack | Project Forman

- Over 25 years in the construction industry
- Has served as a carpenter and carpenter foreman
- o Runs timely and efficient projects
- o Exemplary safety record

GEI Consultants - Professional Consultant (Control of Water/Dewatering)

Founded as a geotechnical engineering firm in 1970, GEI has been an industry leader in the application of geotechnical principles to achieve safe, economical and practical projects. We are highly experienced in investigating, evaluating and navigating the risk and uncertainty of the underground to overcome challenges presented to both routine and complex projects by variable soil, rock, and groundwater conditions; fast-track schedules; and sensitive adjacent buildings and infrastructure.

GEI has a team of specialists located across the U.S. with expertise in surface and subsurface drainage, as well as flood hydrology and flood control facilities. Our team applies advanced hydrologic and hydraulic models that take into account historic rainfall and runoff events, maximum probable event predictions and multiple reservoir operational considerations. These considerations include flood control, recreation, power generation, endangered species, water supply and wild and scenic river issues. We provide our clients with solutions that integrate yesterday's history with today's technology. Specialties include: Dams; Levees; Dikes; Seawalls; and Dam Safety.

GEI commits to using the following Project Team personnel for your project:

- Andy Baxter, PE | Project Principal
- Marat Mardenov PE | Sr. Engineer

History of Working Relationships

KC and Performance have teamed up on multiple dam projects over the last several years, Toby Creek back in 2008 as well as completing work on Pikes Creek Dam (2017), and Lake Scranton Dam (2018) for PA American Water. All included control of water measures, water stop and cast-in-place concrete for watertight hydraulic structures. Additionally, KC and Performance recently partnered up on five more dam rehab projects (Minsi Lake Dam, Pecks Pond Dam, Meadow Grounds Lake Dam, Sheppard-Myers Dam, Stony Garden Dam). Point being, this team has a solid performance record of successful dam rehabilitation projects, many of which have been built for PA DGS.

KC will be partnering with GEI Consultants to provide cofferdam and dewatering designs for rehabilitation of the primary spillway and dam embankment. The KC-GEI Consultants relationship dates back over 10 years. GEI Consultants was one of KC's first consulting partners upon entering the dam construction world. They have evolved to be one of our most trusted resources, especially when the is a complex project to tackle or we need an outside the box approach. We have an excellent working relationship which will help progress this project successfully.

Concrete Simplicity Consulting & Supply, LLC has been a partner to KC in the truest sense of the term. Karen Reese is an excellent technical resource and has consistently met our needs. As a registered SDB stocking supplier, she has regularly participated with us on State projects allowing us to meet and exceed the SDB participation goals.

Lastly, but most importantly, KC Construction Co. has now completed **6** "Best Value" dam rehabilitation jobs for the State (PA DGS – DCNR/Fish & Boat) while developing excellent working relationships with staff of every department and instilling a confidence that every contract will be completed to the highest standards on time and on budget.

Services and Materials to be Provided

- Survey Layout & Utility Notification
- Erosion and Sediment Control Measures
- Clearing, Grubbing and Stripping of Identified Areas
- Control & Diversion of Water (Cofferdam Installation and Removal, Temporary Stream Diversion)
- Temporary Lay Down Areas, Temporary Parking, and Temporary Access Roads
- Excavation Dewatering
- Demolition and Removal of Existing Structures
- Subgrade Prep (Rock Foundation) and Drainage System for Concrete Structures
- New Cast-in-Place Concrete Labyrinth Spillway (Auxiliary Structure)
- Improvements to the Spillway Channel downstream (RipRap Lining)
- Embankment Excavation, Subgrade Preparation, Zoned Fill Placement (Flattening Dam)
- Installation of Internal Drain System (Chimney and Toe Drains) and Seepage Monitoring System
- Installation of Dam Instrumentation
- Install Dry-Hydrant (Base Bid 2)
- Supplemental Stream Channel Improvements (Base Bid 2)
- Replacement of 17th Street Bridge Structure (Base Bid 3)
- Fine Grade Embankment Slopes, Install Riprap Scour Protection
- Maintenance/Removal of Erosion Control Measures
- Permanent Restoration of Grass, Stone Paved areas
- Demobilize

Team's Experience with Project Features

- Spillway Construction (Large Spillway Construction, Cast-in-Place Concrete for Watertight Structures) KC/Performance have worked together on several dam projects and many other water conveyance projects. We understand the critical need for quality construction methods and materials. We understand the need for the dam to behave as designed, and that construction means and methods have a significant outcome on that behavior. Their installers have received certifications from factory manufacturers of water stop products. Project after project has been completed in compliance with the contract documents with no rework required. Their experience in water-tight structures makes them a leader in the industry.
- Water Control & Dewatering All of the dam projects we work on require control of water. KC Construction is proficient in the installation of various forms of temporary earthen, sheet pile, and portadam cofferdams in addition to bypass pumping systems. KC Construction maintains superb working relationships with multiple geotechnical and structural engineering firms for design collaboration. Additionally, Performance has built and repaired numerous projects requiring control of water in partnership with KC. They too understand that the control of water includes all parts of the infrastructure, and that infrastructure must be fully understood to assure that the entire system acts together to function correctly.
- Embankment Construction, Drainage & Seepage Collection Systems KC Construction has satisfactorily completed 32 earthen dam and levee rehabs or upgrades in the last five (5) years, including multiple projects for PA DGS. It should be noted that these drainage systems have been designed by several different engineers, all of which have slightly different variations and specifications. We understand the overall intent of these systems and how Dam Safety expects them to perform.
- Piezometer Installation in Embankments whether it's protecting, extending, or installing completely new, KC has experience with Piezometers. Dam instrumentation is obviously a critical component of dam monitoring for both construction and long-term monitoring for performance of the embankment. Our drilling and engineering partners are all regulars in the dam construction industry.
- Demolition of Concrete Structures More and more we are seeing dam rehab projects require surgical demolition of existing structures. The reasons can vary from minimizing cost, salvaging historic structures, or maybe it's necessary to manage water and mitigate risk during construction. No matter the reason, KC has routinely completed total and partial demolition services and successfully married the new construction to remaining dam facilities.
- Excavated Material Handling and Screening Whenever a contractor excavates into an existing dam embankment, there is an element of risk that needs to be understood and addressed. Our experience provides us with a unique insight as to what we are essentially "getting into". Our operators have dug into numerous dam embankments some good, some bad. Understanding the geotechnical requirements of these soils helps us identify and handle the materials in the appropriate manner. Many times our dam rehabilitation projects have required soils processing. We own and partner with several equipment suppliers (screens and crushers) that we rely on to service the project with the best tools to get the job done.

Marquette Lake Dam Rehabilitation

Project No. DGS C-0960-0086 Phase 1

PROJECT TEAM ORGANIZATION CHART



Marquette Lake Dam Rehabilitation

Project No. DGS C-0960-0086 Phase 1

TECHNICAL SUBMITTAL

Section 1. Project Team Qualifications, Experience and Past Performance

T-1B Prime Contractor

(Appendix F)

APPENDIX F

PRIME CONTRACTOR QUALIFICATION STATEMENT

APPENDIX F PRIME CONTRACTOR QUALIFICATION STATEMENT

COVER SHEET

DGS Project Name	Marquette Lake Dam - Rehabilitation	
DGS Project Number	C-0960-0086.1	
<u>Check One</u> :		
XCorporation,		
Partnership,		
Individual,		
Joint Venture,		
Other		
Name of Firm	KC Construction Co.	· · · · · · · · · · · · · · · · · · ·
Address	1737 Stout Drive, Ivyland, PA 18974	
Principal Office	Same	
Owner or Authorized Representative Gino Yannuzzelli		

SECTION 1 - INFORMATION ON FIRM

1.1 Background Information

a) How many years has the firm been in business? 40 Years

b) How many years has the firm been doing business in proposed contract field? <u>36 Years</u>

Under what former names has the firm conducted business? KC Engineering and Construction Company

- c) Provide an <u>Attachment 1</u> to this Qualifications Statement identifying all jurisdictions in which the firm is licensed or otherwise qualified to do business. List and provide copies of any business or trade licenses, certificates or registrations (to the extent that they apply to the Contract Work) held by the firm.
- d) If the firm is a corporation, provide the following information:

Date of incorporation	October 17, 1983
State of incorporation	Pennsylvania
President's name	John V. Lima
Vice President's name(s)	Gino Yannuzzelli
Secretary's name	Gino Yannuzzelli
Treasurer's name	John V. Lima

e) If the firm is a partnership, provide the following information:

Date of formation	
Type of partnership_	
Names of partners	

f) If the firm is individually owned, provide the following information:

Date of formation_	۱	<u> </u>
Name of owner		

g) If the form of the firm is other than those listed above, describe it and name the principals:

SECTION 2 - EXPERIENCE AND PERFORMANCE

2.1 General

a) Provide the annual construction volume in dollars completed by the firm in the past three years:

Year 2023 \$12,790,741

Year 2022 \$ 16,618,240

Year <u>2021</u> <u>\$ 15,339,475</u>

- b) Identify the percentage of work on similar projects the firm typically performs with its own work force <u>65%</u>
- c) List the categories of work that the firm normally performs with its own forces on similar projects.

Earthwork, demolition, clearing & grubbing, cofferdams, dewatering, underground utilities, cast-in-place concrete, roller compacted concrete (RCC), articulated concrete block (ACB), mechanical gate valves and sluice gates.

2.2 Project Experience and References

Submit as **<u>Attachment 2</u>** to this Qualifications Statement:

- a) Suggested number of Sheets/Pages:
 - 3 sheets/(6 pages)

Three (3) detailed project descriptions for relevant projects that are similar in size and scope to the Contract Work. The project descriptions shall include, at a minimum, the following information presented in the order listed below:

- i. Name of project, type of project and location
- ii. Description of the project and relevance of work to the Contract Work
- iii. Contact information for an owner representative familiar with the firm's work performed on this project. Include name, address, telephone number(s) and email address.
- iv. The original bid/proposal price and the final contract price. If the project is ongoing, project the final price and relation to proposal price. Contract value for which the firm was/is responsible.
- v. The original date for project completion and the actual completion date. If the project is ongoing, project the completion date and relation to original schedule.
- vi. As available, performance ratings of the work evaluated by owner or owner's representative.

2.3 Contractor Safety Record

Submit as <u>Attachment 3</u> to this Qualifications Statement the information specified herein and verify this information by providing copies of OSHA 300/200 Forms or appropriate documentation from insurance carriers, as applicable. The firm may submit written explanations to comment on or clarify its safety record.

a) Provide the firm's Workers Compensation Experience Modification Rating for the past three years, beginning with the most recent year available:

Year 1:	2024	0.987
Year 2:	2023	1.025

Year 3: 2022 0.968

b) Provide the firm's Total Lost Workday Incidence Rate (LWDIR) for the past three years, beginning with the most recent year available:

Year 1:	2023	0
Year 2:	2022	0
Year 3:	2021	0

*LWDIR Rate = Number of Lost Time Injuries & Illnesses x 200,000 ÷ Total Hours Worked

c) Provide the firm's Recordable Incidence Rate (RIR) for the past three years:

Year 1:	2023	0
Year 2:	2022	0
Year 3:	2021	0

*RIR Rate = Number of Injuries x 200,000 ÷ Total Hours Worked

d) Provide in an <u>Attachment 4</u> to this Qualifications Statement a list of any health or safety citations issued by federal or state agencies for serious or willful violations issued in the past 3 years. Include a separate statement for any such violations and include the citation number, a brief description of the violation and the amount of penalty, if any, for each violation and current status of violation. N/A

SECTION 3 - REQUIRED DISCLOSURES

The firm shall answer the following questions with regard to the past three (3) years. If any question is answered in the affirmative, the firm shall submit in an <u>Attachment 5</u> to this Qualifications Statement, for each affirmative answer, a written explanation which shall provide details concerning the matter in question, including applicable dates, locations, names of projects/project owners and current status of any such matter.

3.1 Has the firm ever been debarred or suspended from doing business with any federal, state or local government agency or private entity?

Yes No X

3.2 Is the firm currently or has the firm been otherwise prohibited from doing business with any federal, state or local government agency or private entity?

Yes No X

3.3 Has the firm been denied prequalification (not including short listing), declared nonresponsible, or otherwise declared ineligible to submit bids or proposals for work by any federal, state or local government agency or private entity?

Yes <u>No X</u>

3.4 Has the firm defaulted, been terminated for cause or otherwise failed to complete any project that it was awarded?

Yes <u>No X</u>

3.5 Has the firm been assessed or required to pay liquidated damages in connection with work performed on any project?

Yes No X

3.6 Has the firm had any business or professional license, registration, certificate or certification suspended or revoked?

Yes No X

3.7 Have any liens been filed against the firm as a result of its failure to pay subcontractors, suppliers, or workers?

Yes No X

3.8 Has the firm been denied bonding or insurance coverage or been discontinued by a surety or insurance company?

Yes ____ No _X

3.9 Has the firm been found in violation of any laws, including but not limited to contracting or antitrust laws, tax or licensing laws, labor or employment laws or environmental laws by a final decision of a court or government agency?

Yes No X

*Note: information regarding health and safety violations is addressed in a previous section.

3.10 Has the firm or its owners, officers, directors or managers been the subject of any criminal indictment or criminal investigation concerning any aspect of the firm's business?

Yes <u>No X</u>

3.11 Has the firm been the subject to any bankruptcy proceeding?

Yes No X

SECTION 4 - REQUIRED REPRESENTATIONS

In submitting this Qualifications Statement, along with the representations and authorizations listed on the Proposal Signature page and in the RFP, the firm also makes the following representations, which it understands are required as a condition of performing the Contract Work and receiving payment for same.

- 4.1 The firm will possess all applicable professional, business and trade licenses required for performing the Contract Work.
- 4.2 The firm satisfies all bonding and insurance requirements as stipulated in the solicitation for the Contract Work.
- 4.3 The firm and all subcontractors it employs in execution of the Contract Work shall be in full compliance with the Commonwealth's requirements for workers' compensation insurance according to all applicable laws, and unemployment insurance according to all applicable laws.
- 4.4 The firm and all subcontractors it employs in execution of the Contract Work shall be in full compliance with all requirements of the Commonwealth's prevailing wage law and Public Works Employment Verification Act.
- 4.5 If awarded the Contract Work, the firm represents that it will not exceed its current bonding limitations when the Contract Work is combined with the total aggregate amount of all unfinished work for which the Contractor is responsible.

- 4.6 The firm represents that it has no conflicts of interests with the Commonwealth of Pennsylvania and, if awarded the Contract Work, any potential conflicts of interest that may arise in the future will be disclosed immediately to the Department of General Services.
- 4.7 The firm represents the price offered in connection with its proposal for the Contract Work was arrived at independently without consultation, communication or agreement with any other Proposer or competitor.
- 4.8 The firm will ensure that employees and applicants for employment are not discriminated against because of their race, color, religion, sex or national origin.





1737 Stout Drive, Ivyland, PA 18974 | 215-443-5553

Appendix F

Attachment 1

List Of All Jurisdictions in where KC Construction Co. is Qualified to do Business.

- 1. Pennsylvania
 - a. Pennsylvania Business License
 - b. City of Philadelphia Contractors License
 - c. Pennsylvania Department of General Services Small Business Certification
 - d. PennDOT Pre-Qualification
- 2. New Jersey
 - a. New Jersey Business Registration
 - b. New Jersey Public Works Contractor Registration
 - c. New Jersey Division of Property Management and Construction Certificate
- 3. Delaware
 - a. State of Delaware Business License
- 4. Maryland
 - a. State of Maryland Contractor's Business License
- 5. Virginia
 - a. Commonwealth of Virginia Business License
- 6. Massachusetts
 - a. Commonwealth of Massachusetts Foreign Corporation Certificate of Registration

Pennsylvania Department of State

Bureau of Corporations and Charitable Organizations PO Box 8722 | Harrisburg, PA 17105-8722 T:717-787-1057 dos.pa.gov/BusinessCharities

Regarding:	KC CONSTRUCTION CO.
Request Type:	Subsistence Certificate
Request No.:	011569625
Receipt No.:	000421968
Filing Type:	Domestic Business Corporation
Filing Subtype:	Business
Initial Filing Date:	October 17, 1983
Status:	Active

 Issuance Date:
 March 16, 2023

 File No.:
 0000785505

TO ALL WHOM THESE PRESENTS SHALL COME, GREETING:

I DO HEREBY CERTIFY THAT

KC CONSTRUCTION CO.

is currently subsisting on the records of the Department of State as of the issuance date herein.

I DO FURTHER CERTIFY THAT this Subsistence Certificate shall not imply that all fees, taxes and penalties owed to the Commonwealth of Pennsylvania are paid.



IN TESTIMONY WHEREOF, I have hereunto set my hand and caused the seal of my office to be affixed, the day and year above written

Alan Schow

Albert Schmidt Acting Secretary of the Commonwealth

Verify this certificate online at <u>www.file.dos.pa.gov</u>

SHEPPARD-MYERS DAM REHABILITATION

Hanover, York County, PA



OWNER: THE BOROUGH OF HANOVER HANOVER, PA Eric Mains (717) 797-4210 | emains@hanoverboroughpa.gov



ENGINEER: Gannett Fleming Camp Hill, PA Craig Snyder (717) 886-5475 <u>csnyder@gfnet.com</u>



ORIGINAL CONTRACT PRICE \$10,846,975 FINAL CONTRACT PRICE \$10,484,164 CONTRACT COMPLETION DATE August 2023 ACTUAL COMPLETION DATE July 2023



<u>PROJECT</u> :	Sheppard-Myers Dam Rehabilitation
LOCATION:	Hanover, York County, PA
<u>PROJECT TYPE</u> :	Dam Rehabilitation
PROJECT ROLE:	Prime Contractor

DESCRIPTION OF PROJECT:

The Sheppard-Myers Dam is a 38 ft high, 760 LF wide, high hazard classified earth embankment dam located in West Manheim Township, Pennsylvania. The Project consists of the rehabilitation of the existing Dam generally including:

- Installation and maintenance of control of water cofferdams and dewatering sumps and wells necessary to protect the work.
- Permanent storm drainage bypass.
- Regrading of the upstream reservoir approach channel
- Demolition, removal, and protection of existing concrete structures, masonry structures and other features designated for demolition.
- New reinforced watertight cast-in-place concrete auxiliary spillway structure.
- Modifications and repairs to the existing principal spillway intake tower including the removal of existing flap valve, removal of existing and installation of new gate valves, slide gates, and related appurtenances, installation of new trash racks, instrumentation, and controls.
- Concrete repairs and modifications to the existing principal spillway intake tower, pedestrian bridge, outlet conduit, outlet structure, and outlet channel.
- Removal of existing outlet structure and discharge channel.
- Masonry and concrete repairs.
- New reinforced concrete outlet conduit extension, outlet structure and outlet channel slab.
- Dam embankment modifications including toe drains, blanket drains, drainage filters and seepage collection systems.
- Installation and raising of Piezometers.
- Construction of abutment berm, parking lot, realigned site access road.
- Associated storm water management facilities and,
- Electrical improvements and monitoring instrumentation and associated controls.

PROJECT TEAM:

John Lima, PE | President

Gino Yannuzzelli | VP/Operations

Bobby Machiesky | Project Manager & Surveyor

Steve Sickler | Site Superintendent





MEADOW GROUNDS LAKE DAM REHABILITATION

FULTON COUNTY, PA



FISH & BOAT COMMISSION

Harrisburg, PA Gerald Woomer, PE (814) 359-5170 gwoomer@pa.gov

D'APPOLONIA <u>ENGINEER:</u> D'APPLONIA DIVISION OF GROUND TECHNOLOGY, INC. Pittsburgh, PA Aaron Antell (412) 229-1596

AJAntell@dappolonia.com

ORIGINAL CONTRACT PRICE \$5,090,000 FINAL CONTRACT PRICE \$ 5,172,623 CONTRACT COMPLETION DATE April 2021 ACTUAL COMPLETION DATE April 2021



PROJECT:	Meadow Grounds Lake Dam Rehabilitation
LOCATION:	Fulton County, PA
PROJECT TYPE:	Rehabilitation of Existing Earthen Dam Appurtenant Structures
PROJECT ROLE :	Prime Contractor

DESCRIPTION OF PROJECT:

The Meadow Grounds Lake Dam is a 40 ft high, 950 LF wide, high hazard classified earth embankment dam located in Ayer Township, Fulton County, Pennsylvania. The Meadow Grounds Dam Rehabilitation Project comprises modifying the dam and appurtenant structures to meet current dam safety criteria and design standards. Construction activities generally include removal of the existing concrete spillway structure, construction of a cast-in-place concrete replacement spillway and stilling basin, slip-lining the existing cast-in-place principal spillway conduit with pipe, modifications and improvements to the existing control tower, installing a seepage collection/toe drain and conveyance system consisting of a sand and stone filter with PVC pipe and a sand chimney/blanket drain, flattening the downstream slope, and raising dam crest approximately 3.6 feet. Work activities include:

- Clearing, grubbing and stripping of topsoil in earthwork areas.
- Demolition and removal of the existing cast-in-place concrete spillway.
- Control of water cofferdams and dewatering to complete all construction activities.
- Excavation, subgrade preparation, placement of general and embankment fill.
- Construction of seepage collection and conveyance system that includes an aggregate chimney drain, aggregate blanket drain, aggregate abutment trench drain, and piping system for collection and controlled discharge of water.
- Construction of watertight concrete spillway, concrete spillway channel, and concrete stilling basin.
- Construction of permanent erosion protection ancillary to concrete spillway.
- Slip-lining and extension of existing concrete principal spillway conduit.
- Improvements to control tower including installing sluice gate and assemblies ancillary to the operation of the sluice gate.
- Installation and maintenance of all Erosion and Sedimentation Control features necessary for completion of the project.
- Installation of standpipe piezometers in dam embankment.
- Site restoration and revegetation.

PROJECT TEAM:

John Lima, PE President	Gino Yannuzzelli VP/Operations
Derek Fuller, PE Project Manager	Schnabel Engineering Consulting Engineer
Chris Knash Onsite Superintendent	Darren Rascher Site Foreman



REHABILITATION OF PIKES CREEK DAM LUZERNE COUNTY, PA



OWNER: PENNSYLVANIA AMERICAN WATER 852 Wesley Drive Mechanicsburg, PA 17055

Anthony Nokovich, P.E. (717) 691-2138







ORIGINAL CONTRACT PRICE \$14,464,941 FINAL CONTRACT PRICE \$14,434,413

ORIGINAL COMPLETION DATE December 2018 ACTUAL COMPLETION DATE December 2017





KC Construction Company 1737 Stout Drive, Ivyland, PA 18974 215-443-5553 **PROJECT:** Rehabilitation of Pikes Creek Dam

PROJECT TYPE: Rehabilitation of Existing Dam

LOCATION: Luzerne County, PA

DESCRIPTION OF PROJECT:

Rehab of an existing earth filled dam with a 2,155' long crest, maximum embankment height of 65' and a storage capacity of 9,026-acre feet. Work activities include:

- Clearing and Grubbing
- Design, installation and operation of a temporary dewatering wells
- Design, installation and removal of earthen and porta-dam cofferdams
- 40,000 cy of rock excavation for new auxiliary spillway and channel
- Demolition of the existing concrete auxiliary spillway
- Rock anchors for new auxiliary spillway
- Installation of a new 2,500 CY cast in place auxiliary spillway sill
- Install pre-cast Fusegate Control Structures at auxiliary spillway
- Installation of downstream embankment toe filters and foundation drainage system
- Screen Process and Placement of 42,000 cy of select fill at embankment
- 5,200 cy of rip rap protection at upstream embankment
- DIP Outlet conduit modifications
- Concrete restoration of main spillway
- Abandon existing piezometers
- Furnish and install new piezometers
- Demo existing upstream underwater closure valves and aeration system
- Furnish and install new underwater closure valves and aeration system

PROJECT TEAM:

John Lima, PE | Vice President Operations

Gino Yannuzzelli | Project Manager

Robert Machiesky, Jr. | Site Superintendent





INSURANCE BROKERS AND CONSULTANTS

April 25, 2024

KC Construction Company Attn: Wayne Randall 1737 Stout Drive Ivyland, PA 18974

Re: PA Workers Compensation Experience Modification Ratings Policy Terms: 2024, 2023, 2022, 2021, 2020 Bureau file Number: 2663455

Dear Wayne:

This is to confirm that the 4 year history of Pennsylvania Experience Modification Rates are as follows:

Effective Date	Expiration Date	Experience Rating Modification
06/01/2024	06/01/2025	0.987
06/01/2023	06/01/2024	1.025
06/01/2022	06/01/2023	0.968
06/01/2021	06/01/2022	0.774
07/01/2020	06/01/2021	0.760
07/01/2019	07/01/2020	0.754

Should you have any questions or require additional information, please contact me.

Sincerely,

Lauren Anderson

Lauren Anderson Account Assistant

100 Granite Drive – Suite 205 – Media, PA 19063 OFFICE 610-892-7688 – FAX 610-892-7695 www.safegardgroup.com

OSHA's Form 300 (Rev. 01/2004) Log of Work-Related Injuries and Illnesses

Attention: This form contains information relating to employee health and must be used in a manner that protects the confidentiality of employees to the extent possible while the information is being used for occupational safety and health purposes.

You must record information about every work-related injury or illness that involves loss of consciousness, restricted work activity or job transfer, days away from work, or medical treatment beyond first aid. You must also record significant work-related injuries and illnesses that are diagnosed by a physician or licensed health care professional. You must also record work-related injuries and illnesses that meet any of the specific recording criteria listed in 29 CFR 1904.8 through 1904.12. Feel free to use two lines for a single case if you need to. You must complete an

Ectablichmont name

injury ar	njury and illness incident report (OSHA Form 301) or equivalent form for each injury or illness recorded on this form. If you're not sure whether a case is recordable, call your local OSHA office																					
tor neip.								City	lvyland			State			PA							
	Identify the person			Describe the	case	Class	ify the case	9														
(A) (B) Case Employee's Name No.	(C) (D) (E) (F) Job Title (e.g., Welder) Date of injury or illness, parts of body or onset of Loading dock north end) Loading dock north end) Describe injury or illness, parts of body and object/substance that directly injury			(F) Describe injury or illness, parts of body affected, and object/substance that directly injured or made person ill (e.g. Second degree burns on right	CHECK the mos	CONLY ONE st serious outo	box for each ca come for that ca	ase based on ase:	Enter the number of days the injured or ill worker was:		Enter the number of days the injured or ill worker was:		Enter the number of days the injured or ill worker was:		Enter the number of days the injured or ill worker was:		Check th	າe "injur	y" colun illn	nn or cho ess:	oose one	e type of
			(mo./day)		forearm from acetylene torch)	Death	Days away from work	Remain	ed at work	Away From	On job transfer or restriction		isorder	atory ion	ing	g Loss	her illness					
								Job transfer or restriction	Other record- able cases	(days)	(days)	lnjury	Skin D	Respir Condit	Poisor	Hearin	All of					
	N I					(G)	(H)	(I)	(J)	(K)	(L)	(1)	(2)	(3)	(4)	(5)	(6)					
	None													<u> </u> '	┝──┤							
													+	'	┝──┦							
		_											<u> </u>	 '								
														 '	┝───┦							
													+	 '	┝──┤							
					Deve totale								+		\square							
					Page totals	0	0	0	0	0	0	0	0	0	0	0	0					
Public review the are not the are and office of the office of the are and the are and office of the are are are are are are are are are ar	eporting burden for this collection o he instruction, search and gather th required to respond to the collection y comments about these estimates f Statistics, Room N-3644, 200 Cor	f information is estima ne data needed, and c n of information unless or any aspects of this stitution Ave. NW. Wa	ted to average 14 omplete and revie s it displays a curr data collection, o ashington, DC 202	minutes per response, including time to w the collection of information. Persons ently valid OMB control number. If you contact: US Department of Labor, OSHA 210. Do not send the completed forms to	Be sure to transfer these totals	to the	Summary p	bage (Form	300A) befor	e you post	it.	Injury	Skin Disorder	Respiratory Condition	Poisoning	Hearing Loss	All other illnesses					

this office.

Page 1 of 1

Appendix F -Attachment 3



Year 2023

U.S. Department of Labor

Occupational Safety and Health Administration

Form approved OMB no. 1218-0176

(1) (2) (3) (4) (5) (6)

KC Construction Co

OSHA's Form 300A (Rev. 01/2004) Summary of Work-Related Injuries and Illnesses

All establishments covered by Part 1904 must complete this Summary page, even if no injuries or illnesses occurred during the year. Remember to review the Log to verify that the entries are complete

Using the Log, count the individual entries you made for each category. Then write the totals below, making sure you've added the entries from every page of the log. If you had no cases write "0."

Employees former employees, and their representatives have the right to review the OSHA Form 300 in its entirety. They also have limited access to the OSHA Form 301 or its equivalent. See 29 CFR 1904.35, in OSHA's Recordkeeping rule, for further details on the access provisions for these forms.

Number of Cases



Number of Days

Total number of days away from work	Total number of days of job transfer or restriction
0	0
(K)	(L)

Injury and Illness Types

Total number of… (M)			
(1) Injury	0	(4) Poisoning	0
(2) Skin Disorder	0	(5) Hearing Loss	0
(3) Respiratory			
Condition	0	(6) All Other Illnesses	0

Post this Summary page from February 1 to April 30 of the year following the year covered by the form

Public reporting burden for this collection of information is estimated to average 58 minutes per response, including time to review the instruction, search and gather the data needed, and complete and review the collection of information. Persons are not required to respond to the collection of information unless it displays a currently valid OMB control number. If you have any comments about these estimates or any aspects of this data collection, contact: US Department of Labor, OSHA Office of Statistics, Room N-3644, 200 Constitution Ave, NW, Washington, DC 20210. Do not send the completed forms to this office.



U.S. Department of Labor Occupational Safety and Health Administration

Form approved OMB no. 1218-0176

Esta	ablishi	ment informatio	n					
	Your e	stablishment name	KC Constructior	ו Co.				
	Street	1737 Stout Drive						
	City	lvyland		State	PA		Zip	18974
	Industr	y description (e.g., Construction	Manufacture of mo	otor truck trailers)				
	Standa	rd Industrial Classif	ication (SIC), if kn	own (e.g., SIC 371	5)			
OR	North A	American Industrial	Classification (NAI	CS), if known (e.g. 0	, 336212)			
Emp	oloyme	ent information						
	Annua	average number o	femployees	28				
	Total h year	ours worked by all e	employees last	54,913				
Sigr	n here							
	Knowi	ngly falsifying this	document may re	esult in a fine.				
	I certify comple	o that I have examin te.	ed this document :	and that to the bes	t of my knowledge the e	entries are true	, accurate	e, and
		Company	ecutive			-	T	itle
	215-44	3-5553 Pho	ne			-	D	1/3/2024 ate

OSHA's Form 300A (Rev. 01/2004) Summary of Work-Related Injuries and Illnesses

All establishments covered by Part 1904 must complete this Summary page, even if no injuries or illnesses occurred during the year. Remember to review the Log to verify that the entries are complete

Using the Log, count the individual entries you made for each category. Then write the totals below, making sure you've added the entries from every page of the log. If you had no cases write "0."

Employees former employees, and their representatives have the right to review the OSHA Form 300 in its entirety. They also have limited access to the OSHA Form 301 or its equivalent. See 29 CFR 1904.35, in OSHA's Recordkeeping rule, for further details on the access provisions for these forms.

Number of Cases



Number of Days

Total number of days away from work	Total number of days of job transfer or restriction
0	0
(K)	(L)

Injury and Illness Types



Post this Summary page from February 1 to April 30 of the year following the year covered by the form

Public reporting burden for this collection of information is estimated to average 58 minutes per response, including time to review the instruction, search and gather the data needed, and complete and review the collection of information. Persons are not required to respond to the collection of information unless it displays a currently valid OMB control number. If you have any comments about these estimates or any aspects of this data collection, contact: US Department of Labor, OSHA Office of Statistics, Room N-3644, 200 Constitution Ave, NW, Washington, DC 20210. Do not send the completed forms to this office.



U.S. Department of Labor Occupational Safety and Health Administration

Form approved OMB no. 1218-0176

	Your es	stablishment name KC Construction	on Co.		
	Street	1737 Stout Drive			
	City	lvyland	State	PA	Zip 18974
	Industr	y description (e.g., Manufacture of m Construction	otor truck trailers)		
	Standa	ard Industrial Classification (SIC), if kr	nown (e.g., SIC 3715)		
R	North A	American Industrial Classification (NA	AICS), if known (e.g., 33	6212)	
mp	loyme	ent information			
	Annual	average number of employees	33		
	Total h year	ours worked by all employees last	63,214		
ign	here				
	Knowii	ngly falsifying this document may	result in a fine.		
	l certify comple	that I have examined this document te.	t and that to the best of	my knowledge the entries	are true, accurate, and
-	/	Company executive			Vice President Title
	215-44	3-5553			1/31/2023

Appendix F -Attachment 3

OSHA's Form 300A (Rev. 01/2004) Summary of Work-Related Injuries and Illnesses

All establishments covered by Part 1904 must complete this Summary page, even it no injuries or illnesses occurred during the year. Remember to review the Log to verify that the entries are complete

Using the Log, count the individual entries you made for each category. Then write the totals below, making sure you've added the entries from every page of the log. If you had no cases write "0."

Employees former employees, and their representatives have the right to review the OSHA Form 300 in its entirety. They also have limited access to the OSHA Form 301 or its equivalent. See 29 CFR 1904.35, in OSHA's Recordkeeping rule, for further details on the access provisions for these forms.



Post this Summary page from February 1 to April 30 of the year following the year covered by the form

Public reporting burden for this collection of information is estimated to average 58 minutes per response, including time to review the instruction, search and gather the data needed, and complete and review the collection of information. Persons are not required to respond to the collection of information unless it displays a currently valid OMB control number. If you have any comments about these estimates or any aspects of this data collection, contact. US Department of Labor, OSHA Office of Statistics, Room N-3644, 200 Constitution Ave. NW. Washington, DC 20210. Do not send the completed forms to this office.



U.S. Department of Labor Occupational Safety and Health Administration

Form approved OMB no. 1218-0176

Your establishment name KC Cons	struction Co.		
Street 1737 Stout Drive			
City Ivyland	State	PA	Zip 18974
Industry description (e.g., Manufactur Construction	e of motor truck trailers)		
Standard Industrial Classification (SIC	c), if known (e.g., SIC 3715)		
OR North American Industrial Classification	on (NAICS), if known (e.g., 3	36212)	
<u>2 3 7 1</u>	0		
Employment information			
Annual average number of employees	36		
Total hours worked by all employees I year	ast68,229		
Sign here			
Knowingly falsifying this document	may result in a fine.		
I certify that I have examined this docu complete.	ument and that to the best of	my knowledge the entrie:	s are true, accurate, and
Company executive	Ul		Vice President
Company executive			itte
215-443-5553			1/7/2022

OSHA's Form 300 (Rev. 01/2004) Log of Work-Related Injuries and Illnesses

Attention: This form contains information relating to employee health and must be used in a manner that protects the confidentiality of employees to the extent possible while the information is being used for occupational safety and health purposes.

City

Establishment name

lvyland



Form approved OMB no. 1218-0176

PA

KC Construction Co.

State

You must record information about every work-related injury or illness that involves loss of consciousness, restricted work activity or job transfer, days away from work, or medical treatment beyond first aid. You must also record significant work-related injuries and illnesses that are diagnosed by a physician or licensed health care professional. You must also record significant work-related injuries and illnesses that are diagnosed by a physician or licensed health care professional. You must also record significant work-related injuries and illnesses that meet any of the specific recording criteria listed in 29 CFR 1904.8 through 1904.12. Feel free to use two lines for a single case if you need to. You must complete an injury and illness incident report (OSHA Form 301) or equivalent form for each injury or illness recorded on this form. If you're not sure whether a case is recordable, call your local OSHA office for help.

ld	entify the person	STREEMSTD M		Describe the o	case	Class	ify the case	9		and the second		San all all				1 3.er	
(A) (B) Case Employee's Name No.	(C) Job Title (e.g., Welded	C) (D) (E) (F) le (e.g., Date of injury Where the event occurred (e.g. Describe injury or illness, parts of body affected				CONLY ONE at serious out	box for each c come for that c	ase based on ase:	Enter the ni days the inj worker was	umber of ured or ill :	Check the "injury" column or choose one type of illness:						
NU.	illness (mo./day) (mo./day) (mo./day) (mo./day)	and object/substance that directly injured or mad person ill (e.g. Second degree burns on right forearm from acetylene torch)	Death	Days away from work	Remain	ed at work	Away	On job transfer or	(M)	order	λīε.	5	Loss	r illnesses			
						(G)	(H)	Job transfer or restriction	Other record- able cases	Work (days)	(days)	() Injury	Skin Dise	Condition	Poisonin	G Hearing	All other
_									(0)	(ry	(5/		(2)	(3)	(4)	(3)	
_																	
-																	
														_		-	
					Page totals	0	0	0	0	0	0	0	0	0	0	0	0
ublic repor	ting burden for this collection of	Information is estimat	ed to average 14 r	ninutes per response, including time to	Be sure to transfer these totals	to the s	Summary p	bage (Form	300A) before	e you post	it.	Injury	Disorder	espiratory Condition	Poisoning	aring Loss	r illnesses
re not requ ave any co	ired to respond to the collection mments about these estimates	of information unless or any aspects of this	it displays a current data collection, co	ntly valid OMB control number. If you ntact: US Department of Labor, OSHA									Skir	£	19864	Her	All other
ffice of Statistics of Statist	tistics, Room N-3644, 200 Con	stitution Ave, NW, Was	shington, DC 2021	0. Do not send the completed forms to					Page	1 of 1		(1)	(2)	(2)	(4)	(5)	(6)

Marquette Lake Dam Rehabilitation

Project No. DGS C-0960-0086 Phase 1

TECHNICAL SUBMITTAL

Section 1. Project Team Qualifications, Experience and Past Performance

T-1C Critical Work

(Appendix G)

APPENDIX G

DESIGNATED CRITICAL WORK QUALIFICATIONS STATEMENT

APPENDIX G DESIGNATED CRITICAL WORK QUALIFICATIONS STATEMENT

COVER SHEET

DGS Project Name Marquette Lake Dam Rehabilitation and Improvements

DGS Project Number C-0960-0086 Phase 1

DESIGNATED CRITICAL WORK: For proper evaluation, the Proposer MUST submit at least one "Designated Critical Work Qualification Statement" for each Work item listed in T-1C for the respective contract. NOTE: The selected Proposer shall enter subcontracts with each listed subcontractor in T-1C.

Check One Work item for which this Qualification Statement is being submitted:

General Construction (.1 contract)

- X Cast-in-place Concrete spillways with watertight waterstop joints
- _____ Graded aggregate filterdrain construction
- Earthwork including placement and compaction of fill material for earthen dam embankments

Name of Firm Performance Construction Company

Address 25 South Centre Street, Pottsville PA 17901

Principal Office ___Quandel Enterprises, LLC

Owner or Authorized Representative Eric Eichenberg

SECTION 1 – FIRM INFORMATION

- 1.1 Background Information
 - a) How many years has the firm been in business? ______28 years
 - b) How many years has the firm been doing business in proposed contract field? 28 years

Under what former names has the firm conducted business?

Quandel Construction Services, Corp	
Performance Labor Services, Inc.	
Performance Construction Services, Inc.	
Susquehanna Supply Company	

c) Identify all jurisdictions in which the firm is licensed or otherwise qualified to do business.

Pennsylvania	Ohio	
New York		

d) If the firm is a corporation, provide the following information:

Date of incorporation 05-04-1995
State of incorporation Pennsylvania
President's name Vance Martin
Vice President's name(s) Eric Eichenberg
Secretary's name Kelyn Eichenberg
Treasurer's name Don Deegan

e) If the firm is a partnership, provide the following information:

ate of formation	
/pe of partnership	
ames of partners	

f) If the firm is individually owned, provide the following information:

Date of formation_____

Name of owner_____

g) If the form of the firm is other than those listed above, describe it and name the principals:

SECTION 2 - EXPERIENCE AND PERFORMANCE

2.1 General

a) Provide the annual construction volume in dollars completed by the firm in the past three years:

 Year
 2023
 \$ 49,925,086.00

 Year
 2022
 \$ 24,932,685.00

 Year
 2021
 \$ 24,998,528.00

- b) Identify the percentage of work on similar projects the firm typically performs with its own work force _80%_
- c) List the categories of work that the firm normally performs with its own forces on similar projects. Cast in Place Concrete General Trades Structural Concrete Project Experience and Perforences

2.2 Project Experience and References

Submit as Attachment 1 to this Qualifications Statement:

- a) Suggested number of Sheets/Pages:
 - 3 sheets/(6 pages)

Three (3) detailed project descriptions for relevant projects similar in size and scope to the Contract Work. The project descriptions shall include, at a minimum, the following information presented in the order listed below:

- vii. Name of project, type of project and location
- viii. Description of the project and relevance of work to the Contract Work
- ix. Contact information for an owner representative familiar with the firm's work performed on this project. Include name, address, telephone number(s) and e-mail address.
- x. The original bid/proposal price and the final contract price. If the project is ongoing, project the final price and relation to proposal price. Contract value for which the firm was/is responsible.
- xi. The original date for project completion and the actual completion date. If the project is ongoing, project the completion date and relation to original schedule.
- xii. As available, performance ratings of the work evaluated by owner or owner's representative.

2.3 Contractor Safety Record

Submit as <u>Attachment 2</u> to this Qualifications Statement the information specified herein and verify this information by providing copies of OSHA 300/200 Forms or appropriate documentation from insurance carriers, as applicable. The firm may submit written explanations to comment on or clarify its safety record.

a) Provide the firm's Workers Compensation Experience Modification Rating for the past three years, beginning with the most recent year available:

Year 1:	2023	.848
Year 2:	2022	.744
Year 3: 2021 .680

b) Provide the firm's Total Lost Workday Incidence Rate (LWDIR) for the past three years, beginning with the most recent year available:

Year 1:	2023	1.78
Year 2:	2022	1.62
Year 3:	2021	11.18

*LWDIR Rate = Number of Lost Time Injuries & Illnesses x 200,000 ÷ Total Hours Worked

c) Provide the firm's Recordable Incidence Rate (RIR) for the past three years:

Year 1:	2023	1.78
Year 2:	2022	4.86
Year 3:	2021	3.73

*RIR Rate = Number of Injuries x 200,000 ÷ Total Hours Worked

d) Provide in an <u>Attachment 3</u> to this Qualifications Statement a list of any health or safety citations issued by federal or state agencies for serious or willful violations issued in the past 3 years. Include a separate statement for any such violations and include the citation number, a brief description of the violation and the amount of penalty, if any, for each violation and current status of violation.

SECTION 3 - REQUIRED DISCLOSURES

The firm shall answer the following questions with regard to the past three (3) years. If any question is answered in the affirmative, the firm shall submit in an <u>Attachment 5</u> to this Qualifications Statement, for each affirmative answer, a written explanation which shall provide details concerning the matter in question, including applicable dates, locations, names of projects/project owners and current status of any such matter.

3.1 Is the firm currently debarred or suspended from doing business with any federal, state or local government agency or private entity?

Yes No x

3.2 Has the firm ever been debarred or suspended from doing business with any federal, state or local government agency or private entity?

Yes No x

3.3 Is the firm currently or has the firm been otherwise prohibited from doing business with any federal, state or local government agency or private entity?

Yes No X

3.4 Has the firm been denied prequalification (not including short listing), declared nonresponsible, or otherwise declared ineligible to submit bids or proposals for work by any federal, state or local government agency or private entity?

Yes No X

3.5 Has the firm defaulted, been terminated for cause or otherwise failed to complete any project that it was awarded?

Yes No X

3.6 Has the firm been assessed or required to pay liquidated damages in connection with work performed on any project?

Yes No x

3.7 Has the firm had any business or professional license, registration, certificate or certification suspended or revoked?

Yes No x

3.8 Have any liens been filed against the firm as a result of its failure to pay subcontractors, suppliers, or workers?

Yes No x

3.9 Has the firm been denied bonding or insurance coverage or been discontinued by a surety or insurance company?

Yes No x

3.10 Has the firm been found in violation of any laws, including but not limited to contracting or antitrust laws, tax or licensing laws, labor or employment laws or environmental laws by a final decision of a court or government agency?

Yes No X

*Note: information regarding health and safety violations is addressed in a previous section.

3.11 Has the firm or its owners, officers, directors or managers been the subject of any criminal indictment or criminal investigation concerning any aspect of the firm's business?

Yes No x

3.12 Has the firm been the subject to any bankruptcy proceeding?

Yes No x

SECTION 4 - REQUIRED REPRESENTATIONS

In submitting this Qualifications Statement, along with the other representations and authorizations listed in the RFP, the firm also makes the following representations, which it understands are required as a condition of performing the Contract Work and receiving payment for same.

- 4.1 The firm will possess all applicable professional, business and trade licenses required for performing the Contract Work.
- 4.2 The firm satisfies all bonding and insurance requirements as stipulated in the solicitation for the Contract Work.
- 4.3 The firm and all subcontractors it employs in execution of the Contract Work shall be in full compliance with the Commonwealth's requirements for workers' compensation insurance according to all applicable laws, and unemployment insurance according to all applicable laws.
- 4.4 The firm and all subcontractors it employs in execution of the Contract Work shall be in full compliance with all requirements of the Commonwealth's prevailing wage law and Public Works Employment Verification Act.

- 4.5 If awarded the Contract Work, the firm represents that it will not exceed its current bonding limitations when the Contract Work is combined with the total aggregate amount of all unfinished work for which the Contractor is responsible.
- 4.6 The firm represents that it has no conflicts of interests with the Commonwealth of Pennsylvania and, if awarded the Contract Work, any potential conflicts of interest that may arise in the future will be disclosed immediately to the Department of General Services.
- 4.7 The firm represents the price offered in connection with its proposal for the Contract Work was arrived at independently without consultation, communication or agreement with any other Proposer or competitor.
- 4.8 The firm will ensure that employees and applicants for employment are not discriminated against because of their race, color, religion, sex or national origin.



BOROUGH OF HANOVER SHEPPARD MEYERS DAM





OWNER CONTACT INFO

Ms. Dorothy C Felix Borough Secretary Borough of Hanover 44 Frederick Street Hanover, PA 17331 717-797-4213 dfelix@hanoverboroughpa.gov LOCATION | Hanover, PA SIZE | 4,080 Cubic Yards PROJECT TYPE | Rehabilation CONST. BUDGET | \$3.2 Million CONST. COST | \$3.2 Million CONST. START | July 2021 CONST. COMPLETION | December 2022 DELIVERY METHOD | Subcontractor ARCHITECT | Gannett Fleming

Our firm was hired to complete the auxiliary spillway slabs, auxiliary spillway battered training wall footers and outlet structure slabs.

Also included in our scope of work was the removal existing intake tower beam, shear studs for intake tower beam, embedded plates with welded threaded rod and drilling botoom beam flanges for intake tower walkway column replacement, weir walls and training walls, and contract joint treatment at top of labyrinth weir and joint materials.

3,920 LF of PVC Waterstop was installed. We installed 110 LF ofSurface-Applied Waterstop at joints between new concrete and rock/existing concrete and any previously placed concrete.



quandel.com



PENNSYLVANIA DEPARTMENT OF GENERAL SERVICES MEADOWS GROUNDS LAKE DAM





OWNER CONTACT INFO

Mr. Reggie McNeil Secretary Department of General Services 401 North Street Harrisburg, PA 17120 717.787.5996 LOCATION | Fulton County, PA SIZE | 204 acre reservoir PROJECT TYPE | Rehabilitation CONST. COST | \$1.1 Million CONST. START | July 2020 CONST. COMPLETION | October 2020 DELIVERY METHOD | Subcontractor ARCHITECT | D'Appolonia

Performance Construction Services was hired to construct a new spillway, control tower bulkhead, and cast-in-place box culvert and outlet structure. The project included:

- Placement of approximately 460 cubic yards of PennDOT Class C concrete backfill over excavated top of rock surfaces
- Installation of a one-sided cut-off wall, formed cut-off wall to be placed monolithically with the uppermost 15' of spillway slabs
- Spillway slabs, sloped slabs, and stilling basin
- Concrete bulkhead at Control Tower



quandel.com



PENNSYLVANIA DEPARTMENT OF GENERAL SERVICES MINSI LAKE DAM REPAIR/SPILLWAY





OWNER CONTACT INFO

Mr. Reggie McNeil Secretary Department of General Services 401 North Street Harrisburg, PA 17120 717.787.5996 LOCATION | Bangor, PA SIZE | 29 foot wide spillway PROJECT TYPE | Rehabilitation CONST. BUDGET | \$1.3 Million CONST. COST | \$1.3 Million CONST. START | May 2019 CONST. COMPLETION | September 2019 DELIVERY METHOD | Subcontractor ENGINEER | Schnabel Engineering

Performance Construction Services was hired to construct a new labyrinth stepped spillway with energy dissipating blocks.

The spillway was 125 liner feet wide, 88 linear feet long and contained 2,300 cubic yards of Class AAA concrete.

The spillway contained approximately 2,300 linear feet of water stop.



quandel.com

OSHA's Form 300 (Rev. 01/2004) Log of Work-Related Injuries and Illnesses

Identify the person

(B)

Employee's Name

(C)

Job Title (e.g.

Welder)

(D)

Date of

injury or

onset of

illness

(A)

Case

No.

Attention: This form contains information relating to employee health and must be used in a manner that protects the confidentiality of employees to the extent possible while the information is being used for occupational safety and health purposes. Year 2023 U.S. Department of Labor Occupational Safety and Health Administration

Form approved OMB no. 1218-0176

You must record information about every work-related injury or illness that involves loss of consciousness, restricted work activity or job transfer, days away from work, or medical treatment beyond first aid. You must also record significant work-related injuries and illnesses that are diagnosed by a physician or licensed health care professional. You must also record work-related injuries and illnesses that meet any of the specific recording criteria listed in 29 CFR 1904.8 through 1904.12. Feel free to use two lines for a single case if you need to. You must complete an injury and illness incident report (OSHA Form 301) or equivalent form for each injury or illness recorded on this form. If you're not sure whether a case is recordable, call your local OSHA office for help.

(E)

Where the event occurred (e.g.

Loading dock north end)

Describe the case

Establishment name Performance Construction Company City Pottsville State PA Classify the case Enter the number of (F) CHECK ONLY ONE box for each case based on days the injured or ill Check the "injury" column or choose one type of Describe injury or illness, parts of body affected, he most serious outcome for that case: worker was: illness: and object/substance that directly injured or made (M) person ill (e.g. Second degree burns on right On job forearm from acetylene torch) Days away ē Awav

			(mo./day)			Death	from work	Remain	ed at work	From	restriction		isord	atory ion	ing	g Lo:	her ill
								Job transfer or restriction	Other record- able cases	Work (days)	(days)	Injury	Skin D	Respir Condit	Poison	Hearin	All oth
						(G)	(H)	(I)	(J)	(K)	(L)	(1)	(2)	(3)	(4)	(5)	(6)
1		Superintendent	8/16	Flat Rock Dam	Employee was injecting epoxy into hole and as he released the pressuire on the injection device it bounced up and struck him on the bridge of his nose causing a laceration				x			X					
2		Carpenter	10/4	Flat Rock Dam	Generator Exploded and burned employee		Х			180		Х					
3		Carpenter	10/4	Flat Rock Dam	Generator Exploded and burned employee		Х			110		Х					
4		Carpenter	10/4	Flat Rock Dam	Generator Exploded and burned employee		Х			110		Х					
5		Carpenter	10/4	Flat Rock Dam	Generator Exploded and burned employee		Х			180		Х					
6		Superintendent	10/4	Flat Rock Dam	Generator Exploded and burned employee		Х			120		Х					
7		Foremen	10/4	Flat Rock Dam	Generator Exploded and burned employee		X			180		Х				┟───┤	
																 	
																J	
																ł	
		1	1	l	I Totals		6		1	880							

	Be sure to transfer these totals to the Summary page (Fe	orm 300A) before	you post it.		njury	order	atory dition	ning	Loss	sses
Public reporting burden for this collection of information is estimated to average 14 minutes per response, including time to review the instruction, search and gather the data needed, and complete and review the collection of information. Persons are not required to respond to the collection of information unless it displays a currently valid OMB control number. If you have any comments about these estimates or any aspects of this data collection, contact:					_	Skin Disc	Respira	Poisc	Hearing	All other illne
20210. Do not send the completed forms to this office.		_	Page	1 of 1	(1)	(2)	(3)	(4)	(5)	(6)

OSHA's Form 300A (Rev. 01/2004) **Summary of Work-Related Injuries and Illnesses**



202 U.S. Department of Labor **Occupational Safety and Health Administration**

Year

Form approved OMB no. 1218-0176

All establishments covered by Part 1904 must complete this Summary page, even if no injuries or illnesses occurred during the year. Remember to review the Log to verify that the entries are complete

Using the Log, count the individual entries you made for each category. Then write the totals below, making sure you've added the entries from every page of the log. If you had no cases write "0."

Employees former employees, and their representatives have the right to review the OSHA Form 300 in its entirety. They also have limited access to the OSHA Form 301 or its equivalent. See 29 CFR 1904.35, in OSHA's Recordkeeping rule, for further details on the access provisions for these forms.



0

(3) Respiratory Condition

Post this Summary page from February 1 to April 30 of the year following the year covered by the form

(6) All Other Illnesses

0

Public reporting burden for this collection of information is estimated to average 58 minutes per response, including time to review the instruction, search and gather the data needed, and complete and review the collection of information. Persons are not required to respond to the collection of information unless it displays a currently valid OMB control number. If you have any comments about these estimates or any aspects of this data collection, contact: US Department of Labor, OSHA Office of Statistics, Room N-3644, 200 Constitution Ave, NW, Washington, DC 20210. Do not send the completed forms to this office.

Esta	ablish	ment information				
	Your e	stablishment name	Performance Con	struction Company	y	
	Street	25 S. Centre Street				
	City	Pottsville		State	PA	Zip 17901
	Industr	y description (e.g., Ma Commercial Constru	anufacture of moto action	r truck trailers)		
	Standa	ard Industrial Classific	ation (SIC), if know	n (e.g., SIC 3715)		
OR	North /	American Industrial Cl	assification (NAICS	S). if known (e.g., 3	336212)	
		2 36 6	2 2 2	<u>0</u>	,	
Emr	olovm	ent information				
	,					
	Annua	l average number of e	employees	68		
	Total h year	ours worked by all en	nployees last -	137,779		
Sigr	n here					
	Knowi	ngly falsifying this d	ocument may res	ult in a fine.		
	l certify comple	/ that I have examined	this document and	d that to the best o	f my knowledge the entries a	are true, accurate, and
		In l'a	holen			Vice President
		Eric Eiche	nberg			l itle
		717-671-	9011			1/12/2024
		Phon	e			Date

OSHA's Form 300 (Rev. 01/2004) Log of Work-Related Injuries and Illnesses

Attention: This form contains information relating to employee health and must be used in a manner that protects the confidentiality of employees to the extent possible while the information is being used for occupational safety and health purposes.

City

Year 2022 U.S. Department of Labor Occupational Safety and Health Administration

Form approved OMB no. 1218-0176

PA

You must record information about every work-related injury or illness that involves loss of consciousness, restricted work activity or job transfer, days away from work, or medical treatment beyond first aid. You must also record significant work-related injuries and illnesses that are diagnosed by a physician or licensed health care professional. You must also record work-related injuries and illnesses that meet any of the specific recording criteria listed in 29 CFR 1904.8 through 1904.12. Feel free to use two lines for a single case if you need to. You must complete an injury and illness incident report (OSHA Form 301) or equivalent form for each injury or illness recorded on this form. If you're not sure whether a case is recordable, call your local OSHA office for help.

Establishment name

Pottsville

Performance Construction Company

State

ŀ	dentify the person			Describe the	case	Class	ify the case	;									
(A) Case No.	(B) Employee's Name	(C) Job Title (e.g., Welder)	(D) Date of injury or	(E) Where the event occurred (e.g. Loading dock north end)	(F) Describe injury or illness, parts of body affected, and object/substance that directly injured or	CHECP the mos	CONLY ONE st serious out	box for each c come for that c	ase based on ase:	Enter the nu days the inj worker was	umber of ured or ill :	Check t	he "inj	ury" colu of ill	ımn or c ness:	;hoose o	ne type
			onset of illness (mo./day)		made person ill (e.g. Second degree burns on right forearm from acetylene torch)	Death	Days away from work	Remain Job transfer or restriction	ed at work Other record- able cases	Away From Work (days)	On job transfer or restriction (days)	(M)	Skin Disorder	Respiratory Condition	Poisoning	ັກ Hearing Loss	All other illnesse:
22-1		Carpenter	07/14	LCTA Transit Facility	Injured worker was assembling form work for footers when he tripped over rebar and fell breaking his left wrist	(6)	(H) X	(1)	(3)	(K) 47	11	x	(2)	(3)	(4)	(3)	(0)
22-2		Operator	10/12	Modern Landfill	Injured worker was pulling nails from formwork and nail gave way quickly causing him to bump his right elbow against rebar. Elbow Contusion				х			x					
22-3		Carpenter	10/25	Spruce St Culvert-Frackville	Injured worker was standing next to Jersey Barrier when it was struck by a truck forcing it into his left great toe. Broken Toe				x			х					
															<u> </u> '	──	
															'	<u> </u>	
															 '	──	
															├ ───'	┣───	
		+	<u> </u>												├───'	├───	
		1	I		I Totolo		1			47	44	4		1	├ ────'	┝───	├ ──

45

Be sure to transfer these totals to the Summary page (Form 300A) before you post it. Injury Respiratory Condition Hearing Loss other illnesses Skin Disorder Poisonin P Page 1 of 1 (1) (2) (3) (6) (4) (5)

Public reporting burden for this collection of information is estimated to average 14 minutes per response, including time to review the instruction, search and gather the data needed, and complete and review the collection of information. Persons are not required to respond to the collection of information unless it displays a currently valid OMB control number. If you have any comments about these estimates or any aspects of this data collection, contact: US Department of Labor, OSHA Office of Statistics, Room N-3644, 200 Constitution Ave, NW, Washington, DC 20210. Do not send the completed forms to this office.

OSHA's Form 300A (Rev. 01/2004) Summary of Work-Related Injuries and Illnesses

Must Remain Posted until May 1, 2023

U.S. Department of Labor Occupational Safety and Health Administration

Year 2022

Form approved OMB no. 1218-0176

All establishments covered by Part 1904 must complete this Summary page, even if no injuries or illnesses occurred during the year. Remember to review the Log to verify that the entries are complete

Using the Log, count the individual entries you made for each category. Then write the totals below, making sure you've added the entries from every page of the log. If you had no cases write "0."

Employees former employees, and their representatives have the right to review the OSHA Form 300 in its entirety. They also have limited access to the OSHA Form 301 or its equivalent. See 29 CFR 1904.35, in OSHA's Recordkeeping rule, for further details on the access provisions for these forms.

Number of Cases Total number of Total number of cases Total number of Total number of deaths cases with days with job transfer or other recordable away from work restriction cases 0 1 0 2 (G) (H) (I) (J) Number of Days Total number of Total number of days of days away from job transfer or restriction work 11 (K) (L) Injury and Illness Types Total number of.... (M) (1) Injury (4) Poisoning (2) Skin Disorder (5) Hearing Loss (3) Respiratory Condition (6) All Other Illnesses 0 n

Post this Summary page from February 1 to April 30 of the year following the year covered by the form

Public reporting burden for this collection of information is estimated to average 58 minutes per response, including time to review the instruction, search and gather the data needed, and complete and review the collection of information. Persons are not required to respond to the collection of information unless it displays a currently valid OMB control number. If you have any comments about these estimates or any aspects of this data collection, contact. US Department of Labor, OSHA Office of Statistics, Room N-S444, 200 Constitution Ave. NV, Washington, DC 20210. Do not send the completed forms to this office.

Esta	ablish	ment informatio	n			
	Your e	stablishment name	Performance Co	nstruction Compar	чy	
	Street	25 S. Centre Street				
	City	Pottsville		State	PA	Zip17901
	Indust	ry description (e.g., N Commercial Constr	Nanufacture of mot ruction	or truck trailers)		
	Standa	ard Industrial Classifi	cation (SIC), if know	wn (e.g., SIC 3715)	
OR	North .	American Industrial C	Classification (NAIC	CS), if known (e.g., 0_	336212)	
Emp	oloym	ent information				
	Annua	l average number of	employees	82		
	Total H year	ours worked by all e	mployees last	123,348		
Sigr	1 here					
	Knowi	ngly falsifying this	document may re	sult in a fine.		
	l certify comple	y that I have examine ste.	d this document ar	nd that to the best	of my knowledge the entries a	re true, accurate, and
,	7	Jerome	Al~			President and CEO Title
	5	717-671 Phor	-9011 ne			Date

OSHA's Form 300 (Rev. 01/2004) Log of Work-Related Injuries and Illnesses

Attention: This form contains information relating to employee health and must be used in a manner that protects the confidentiality of employees to the extent possible while the information is being used for occupational safety and health purposes.

Citv

Establishment name

Pottsville

Page

1 of 1

(1)

(2)

(3)

(4)

(5)

(6)



Performance Construction Company

Form approved OMB no. 1218-0176

You must record information about every work-related injury or illness that involves loss of consciousness, restricted work activity or job transfer, days away from work, or medical treatment beyond first aid. You must also record significant work-related injuries and illnesses that are diagnosed by a physician or licensed health care professional. You must also record work-related injuries and illnesses that meet any of the specific recording criteria listed in 29 CFR 1904.8 through 1904.12. Feel free to use two lines for a single case if you need to. You must complete an injury and illness incident report (OSHA Form 301) or equivalent form for each injury or illness recorded on this form. If you're not sure whether a case is recordable, call your local OSHA office for help.

State PA Identify the person Describe the case Classify the case Enter the number of (A) (B) (C) (D) (E) (F) CHECK ONLY ONE box for each case based on days the injured or ill Check the "injury" column or choose one type of Case Employee's Name Job Title (e.g. Date of Where the event occurred (e.g. Describe injury or illness, parts of body affected, the most serious outcome for that case: worker was: illness: No. Welder) injury or Loading dock north end) and object/substance that directly injured or made onset of person ill (e.g. Second degree burns on right (M) illness All other illness forearm from acetylene torch) On job Days away Away Hearing Loss Death Skin Disorde (mo./day) Remained at work transfer or Respiratory Condition from work From Poisoning restriction Work Other record-Job transfer (days) Injury or restriction able cases (days) (3) (G) (1) (2) (H) (I)(J) (K) (4) (5) (L) (6) Employee was assisting in repositioning of a 24 inch valve. While raising the valve from the floor 1 10/11 PA American Water - Hershey Carpenter the valve spun and trapped employees ankle Х 34 39 Х against pipe laying on the floor. Fractured Right lankle Page totals 0 1 0 0 34 39 1 0 n 0 0 0 se totals to the Summary page (Form 300A) before you post it. Injury Respiratory Condition Poisoning Skin Disorder Hearing Loss other illnesses

Public reporting burden for this collection of information is estimated to average 14 minutes per response, including time to review the instruction, search and gather the data needed, and complete and review the collection of information. Persons are not required to respond to the collection of information unless it displays a currently valid OMB control number. If you have any comments about these estimates or any aspects of this data collection, contact: US Department of Labor, OSHA Office of Statistics, Room N-3644, 200 Constitution Ave, NW, Washington, DC 20210, Do not send the completed forms to this office.

OSHA's Form 300A (Rev. 01/2004) Summary of Work-Related Injuries and Illnesses

Must Remain Posted until May 1, 2022

Year 2021

U.S. Department of Labor Occupational Safety and Health Administration

Form approved OMB no. 1218-0176

All establishments covered by Part 1904 must complete this Summary page, even if no injuries or illnesses occurred during the year. Remember to review the Log to verify that the entries are complete and

Using the Log, count the individual entries you made for each category. Then write the totals below, making sure you've added the entries from every page of the log. If you had no cases write "0."

Employees former employees, and their representatives have the right to review the OSHA Form 300 in its entirety. They also have limited access to the OSHA Form 301 or its equivalent. See 29 CFR 1904.35, in OSHA's Recordkeeping rule, for further details on the access provisions for these forms.



Post this Summary page from February 1 to April 30 of the year following the year covered by the form

Public reporting burden for this collection of information is estimated to average 58 minutes per response, including time to review the instruction, search and gather the data needed, and complete and review the collection of information. Persons are not required to respond to the collection of information unless it displays a currently valid OMB control number. If you have any comments about these estimates or any aspects of this data collection, contact: US Department of Labor, OSHA Office of Statistics, Room N-3644, 200 Constitution Ave, NW, Washington, DC 20210. Do not send the completed forms to this office.

stablishment information	· ·
Your establishment name	
Street 25 S. Centre Street	
City Pottsville State PA	Zip <u>17901</u>
Industry description (e.g., Manufacture of motor truck trailers)	
Standard Industrial Classification (SIC), if known (e.g., SIC 3715)	
DR North American Industrial Classification (NAICS), if known (e.g., 336212)	
$\underline{} \underline{} \phantom{$	
mployment information	
Annual average number of employees60	
Total hours worked by all employees last53,863	
ign here	
Knowingly falsifying this document may result in a fine.	
I certify that I have examined this document and that to the best of my knowledge the entries are true, a complete.	accurate, and
Jerofie Urban -	President and CEO Title
717-671-9011 Phone	1/7/2022 Date

OSHA's Form 301 Injuries and Illnesses Incident Report

Attention: This form contains information relating to employee health and must be used in a manner that protects the confidentiality of employees to the extent possible while the information is being used for occupational safety and health purposes.

U.S. Department of Labor
Occupational Safety and Health Administration
Form approved OMB no. 1218-0176
number from the Log after you record the case.)
<i>a</i>

This *Injury and Illness Incident Report* is one of the first forms you must fill out when a recordable work-related injury or illness has occurred. Together with the *Log of Work-Related injuries and Illnesses* and the accompanying *Summary*, these forms help the employer and OSHA develop a picture of the extent and severity of work-related incidents.

Within 7 calendar days after you receive information that a recordable work-related injury or illness has occurred, you must fill out this form or an equivalent. Some state workers' compensation, insurance, or other reports may be acceptable substitutes. To be considered an equivalent form, any substitute must contain all the information asked for on this form.

According to Public Law 91-596 and 29 CFR 1904, OSHA's recordkeeping rule, you must keep this form on file for 5 years following the year to which it pertains

If you need additional copies of this form, you may photocopy and use as many as you need.

Date

Completed by

Title

Phone

Information about the employee	Information about the case
1) Full Name	10) Case number from the Log (Transfer the case number from the Log after you record the case.)
ie 2) Street	11) Date of injury or illness
ith CityStateZip	12) Time employee began work AM/PM
e 3) Date of birth	13) Time of event AM/PM Check if time cannot be determined
nt	*Please do not include any personally identifiable information (Pil) pertaining to worker(s) involved in the incident (e.g., no names, phone numbers, or SSNs) in the following fields.
4) Date hired	*14) What was the employee doing just before the incident occurred? Describe the activity, as well
r 5) Male	as the tools, equipment or material the employee was using. Be specific. Examples: "climbing a
	entry."
x	
Information about the physician or other health care	
professional	*15) What happened? Tell us how the injury occurred. Examples: "When ladder slipped on wet floor
6) Name of physician or other health care professional	worker fell 20 feet"; "Worker was sprayed with chlorine when gasket broke during replacement"; "Worker developed soreness in wrist over time."
7) If treatment was given away from the worksite, where was it given?	2
Facility	*16) What was the injury or illness? Tell us the part of the body that was affected and how it was
Street	affected. Examples: "strained back"; "chemical burn, hand"; "carpal tunnel syndrome."
City State Zin	
8) Was employee treated in an emergency room?	
Yes No	*17) What object or substance directly harmed the employee? Examples: "concrete floor"; "chlorine"; "radial arm saw." If this question does not apply to the incident, leave it blank.
9) Was employee hospitalized overnight as an in-patient?	
No	18) If the employee died, when did death occur? Date of death

Public reporting burden for this collection of information is estimated to average 22 minutes per response, including time for reviewing instructions, searching existing data sources, gathering and maintaining the data needed, and completing and reviewing the collection of information. Persons are not required to respond to the collection of information unless it displays a current valid OMB control number. If you have any comments about this estimate or any other aspects of this data collection, including suggestions for reducing this burden, contact: US Department of Labor, OSHA Office of Statistics, Room N-3644, 200 Constitution Ave, NW, Washington, DC 20210. Do not send the completed forms to this office.

APPENDIX G

DESIGNATED CRITICAL WORK QUALIFICATIONS STATEMENT

APPENDIX G DESIGNATED CRITICAL WORK QUALIFICATIONS STATEMENT

COVER SHEET

DGS Project Name Marquette Lake Dam - Rehabilitation

DGS Project Number _____ C-0960-0086.1

DESIGNATED CRITICAL WORK: For proper evaluation, the Proposer MUST submit at least one "Designated Critical Work Qualification Statement" for each Work item listed in T-1C for the respective contract. NOTE: The selected Proposer shall enter subcontracts with each listed subcontractor in T-1C.

Check One Work item for which this Qualification Statement is being submitted:

General Construction (.1 contract)

- Cast-in-place Concrete spillways with watertight waterstop joints
- X Graded aggregate filterdrain construction
- X Earthwork including placement and compaction of fill material for earthen dam embankments

Name of Firm	KC Construction Co.	
Address 1737	Stout Drive, Ivyland, PA 18974	
Principal Office	Same	
Owner or Authorized Representative _	Gino Yannuzzelli	

SECTION 1 – FIRM INFORMATION

ς,	How many years has the firm	n been in business?	40 Years
	field many years has the min		
b)	How many years has the firm	n been doing business in p	roposed contract field? <u>36 Ye</u>
	Under what former names hat former names hat KC Engineering and	as the firm conducted busir Construction Company	ness?
c)	Identify all jurisdictions in wh	ich the firm is licensed or o New Jersey	therwise qualified to do busine Delaware
	Maryland	Virginia	Massachusetts
,	Date of incorporation State of incorporation President's name Vice President's name(s) Secretary's name Treasurer's name	October 17, 1983 Pennsylvania John V. Lima Gino Yannuzzelli Gino Yannuzzelli John V. Lima	
e)	If the firm is a partnership, p Date of formation Type of partnership Names of partners	rovide the following informa	ation:

principals:

SECTION 2 - EXPERIENCE AND PERFORMANCE

2.1 General

a) Provide the annual construction volume in dollars completed by the firm in the past three years:

Year 2023 \$ 12,790,741 Year 2022 \$ 16,618.240 Year 2021 \$ 15,339,475

- b) Identify the percentage of work on similar projects the firm typically performs with its own work force <u>65%</u>
- c) List the categories of work that the firm normally performs with its own forces on similar projects.

2.2 Project Experience and References

Submit as Attachment 1 to this Qualifications Statement:

- a) Suggested number of Sheets/Pages:
 - 3 sheets/(6 pages)

Three (3) detailed project descriptions for relevant projects similar in size and scope to the Contract Work. The project descriptions shall include, at a minimum, the following information presented in the order listed below:

- vii. Name of project, type of project and location
- viii. Description of the project and relevance of work to the Contract Work
- ix. Contact information for an owner representative familiar with the firm's work performed on this project. Include name, address, telephone number(s) and e-mail address.
- x. The original bid/proposal price and the final contract price. If the project is ongoing, project the final price and relation to proposal price. Contract value for which the firm was/is responsible.
- xi. The original date for project completion and the actual completion date. If the project is ongoing, project the completion date and relation to original schedule.
- xii. As available, performance ratings of the work evaluated by owner or owner's representative.

2.3 Contractor Safety Record

Submit as <u>Attachment 2</u> to this Qualifications Statement the information specified herein and verify this information by providing copies of OSHA 300/200 Forms or appropriate documentation from insurance carriers, as applicable. The firm may submit written explanations to comment on or clarify its safety record.

a) Provide the firm's Workers Compensation Experience Modification Rating for the past three years, beginning with the most recent year available:

Year 1:	2024	0.987		
Year 2:	2023	1.025		

Year 3: 2022 0.968

b) Provide the firm's Total Lost Workday Incidence Rate (LWDIR) for the past three years, beginning with the most recent year available:

Year 1:	2023	0
Year 2:	2022	0
Year 3:	2021	0

*LWDIR Rate = Number of Lost Time Injuries & Illnesses x 200,000 ÷ Total Hours Worked

c) Provide the firm's Recordable Incidence Rate (RIR) for the past three years:

Year 1:	2023	0
Year 2:	2022	0
Year 3:	2021	0

*RIR Rate = Number of Injuries x 200,000 ÷ Total Hours Worked

d) Provide in an <u>Attachment 3</u> to this Qualifications Statement a list of any health or safety citations issued by federal or state agencies for serious or willful violations issued in the past 3 years. Include a separate statement for any such violations and include the citation number, a brief description of the violation and the amount of penalty, if any, for each violation and current status of violation.

N/A

SECTION 3 - REQUIRED DISCLOSURES

The firm shall answer the following questions with regard to the past three (3) years. If any question is answered in the affirmative, the firm shall submit in an <u>Attachment 5</u> to this Qualifications Statement, for each affirmative answer, a written explanation which shall provide details concerning the matter in question, including applicable dates, locations, names of projects/project owners and current status of any such matter.

3.1 Is the firm currently debarred or suspended from doing business with any federal, state or local government agency or private entity?

Yes No X

3.2 Has the firm ever been debarred or suspended from doing business with any federal, state or local government agency or private entity?

Yes ____ No <u>X</u>

3.3 Is the firm currently or has the firm been otherwise prohibited from doing business with any federal, state or local government agency or private entity?

Yes No X

3.4 Has the firm been denied prequalification (not including short listing), declared nonresponsible, or otherwise declared ineligible to submit bids or proposals for work by any federal, state or local government agency or private entity?

Yes ____ No _X__

3.5 Has the firm defaulted, been terminated for cause or otherwise failed to complete any project that it was awarded?

Yes No X

3.6 Has the firm been assessed or required to pay liquidated damages in connection with work performed on any project?

Yes <u>No X</u>

3.7 Has the firm had any business or professional license, registration, certificate or certification suspended or revoked?

Yes <u>No X</u>

3.8 Have any liens been filed against the firm as a result of its failure to pay subcontractors, suppliers, or workers?

Yes <u>No X</u>

3.9 Has the firm been denied bonding or insurance coverage or been discontinued by a surety or insurance company?

Yes No X

3.10 Has the firm been found in violation of any laws, including but not limited to contracting or antitrust laws, tax or licensing laws, labor or employment laws or environmental laws by a final decision of a court or government agency?

Yes ____ No _X__

*Note: information regarding health and safety violations is addressed in a previous section.

3.11 Has the firm or its owners, officers, directors or managers been the subject of any criminal indictment or criminal investigation concerning any aspect of the firm's business?

Yes <u>No X</u>

3.12 Has the firm been the subject to any bankruptcy proceeding?

Yes ____ No X

SECTION 4 - REQUIRED REPRESENTATIONS

In submitting this Qualifications Statement, along with the other representations and authorizations listed in the RFP, the firm also makes the following representations, which it understands are required as a condition of performing the Contract Work and receiving payment for same.

- 4.1 The firm will possess all applicable professional, business and trade licenses required for performing the Contract Work.
- 4.2 The firm satisfies all bonding and insurance requirements as stipulated in the solicitation for the Contract Work.
- 4.3 The firm and all subcontractors it employs in execution of the Contract Work shall be in full compliance with the Commonwealth's requirements for workers' compensation insurance according to all applicable laws, and unemployment insurance according to all applicable laws.
- 4.4 The firm and all subcontractors it employs in execution of the Contract Work shall be in full compliance with all requirements of the Commonwealth's prevailing wage law and Public Works Employment Verification Act.

- 4.5 If awarded the Contract Work, the firm represents that it will not exceed its current bonding limitations when the Contract Work is combined with the total aggregate amount of all unfinished work for which the Contractor is responsible.
- 4.6 The firm represents that it has no conflicts of interests with the Commonwealth of Pennsylvania and, if awarded the Contract Work, any potential conflicts of interest that may arise in the future will be disclosed immediately to the Department of General Services.
- 4.7 The firm represents the price offered in connection with its proposal for the Contract Work was arrived at independently without consultation, communication or agreement with any other Proposer or competitor.
- 4.8 The firm will ensure that employees and applicants for employment are not discriminated against because of their race, color, religion, sex or national origin.

SHEPPARD-MYERS DAM REHABILITATION

Hanover, York County, PA



OWNER: THE BOROUGH OF HANOVER HANOVER, PA Eric Mains (717) 797-4210 | emains@hanoverboroughpa.gov



ENGINEER: Gannett Fleming Camp Hill, PA Craig Snyder (717) 886-5475 <u>csnyder@gfnet.com</u>



ORIGINAL CONTRACT PRICE \$10,846,975 FINAL CONTRACT PRICE \$10,484,164 CONTRACT COMPLETION DATE August 2023 ACTUAL COMPLETION DATE July 2023



<u>PROJECT</u> :	Sheppard-Myers Dam Rehabilitation
LOCATION:	Hanover, York County, PA
PROJECT TYPE:	Dam Rehabilitation
PROJECT ROLE:	Prime Contractor

DESCRIPTION OF PROJECT:

The Sheppard-Myers Dam is a 38 ft high, 760 LF wide, high hazard classified earth embankment dam located in West Manheim Township, Pennsylvania. The Project consists of the rehabilitation of the existing Dam generally including:

- Installation and maintenance of control of water cofferdams and dewatering sumps and wells necessary to protect the work.
- Permanent storm drainage bypass.
- Regrading of the upstream reservoir approach channel
- Demolition, removal, and protection of existing concrete structures, masonry structures and other features designated for demolition.
- New reinforced watertight cast-in-place concrete auxiliary spillway structure.
- Modifications and repairs to the existing principal spillway intake tower including the removal of existing flap valve, removal of existing and installation of new gate valves, slide gates, and related appurtenances, installation of new trash racks, instrumentation, and controls.
- Concrete repairs and modifications to the existing principal spillway intake tower, pedestrian bridge, outlet conduit, outlet structure, and outlet channel.
- Removal of existing outlet structure and discharge channel.
- Masonry and concrete repairs.
- New reinforced concrete outlet conduit extension, outlet structure and outlet channel slab.
- Dam embankment modifications including excavations, toe drains, blanket drains, aggregate drainage filters, seepage collection systems, and earth fill.
- Installation and raising of Piezometers.
- Construction of abutment berm, parking lot, realigned site access road.
- Associated storm water management facilities and,
- Electrical improvements and monitoring instrumentation and associated controls.

PROJECT TEAM:

John Lima, PE | President

Gino Yannuzzelli | VP/Operations

Bobby Machiesky | Project Manager & Surveyor

Steve Sickler | Site Superintendent



KYLE LAKE DAM REHABILITATION

Washington Township, Jefferson County, PA



OWNER: PENNSYLVANIA FISH & BOAT COMMISSION Harrisburg, PA Gerald Woomer, PE (814) 359-5170 gwoomer@pa.gov



ENGINEER: Michael Baker International Pittsburgh, PA Edward Kaminiski (412) 269-6218 <u>ekaminiski@mbakerintl.com</u>



ORIGINAL CONTRACT PRICE \$4,325,000 FINAL CONTRACT PRICE \$4,701,281 CONTRACT COMPLETION DATE May 2019 ACTUAL COMPLETION DATE May 2019



<u>PROJECT</u> :	Kyle Lake Dam Rehabilitation
LOCATION:	Washington Township, Jefferson County, PA
PROJECT TYPE:	Dam Rehabilitation
PROJECT ROLE:	Prime Contractor

DESCRIPTION OF PROJECT:

The Kyle Lake Dam is a 33 ft high, 1,000 LF wide, high hazard classified earth embankment dam located in Washington Township, Jefferson County, Pennsylvania. The renovation of Kyle Lake Dam generally includes the armoring of the embankment with Articulated Concrete Block (ACB); partial demolition of the Auxiliary Spillway and Gate House; partial replacement of the Auxiliary Spillway and Gate House; and replacing the existing outlets works within the Gate House to meet current dam safety criteria. Work items include:

- Clearing, grubbing and stripping the site.
- Installing and maintaining control of water cofferdams and dewatering as necessary to protect the work.
- Removing and replacing the watertight cast-in-place concrete overlay slab and the exposed portions of the sidewalls in the Auxiliary Spillway.
- Excavating to prepare downstream embankment for installation of Articulated Concrete Block (ACB) revetment.
- Placing 93,670 SF of ACB revetment system at a slope of 2.75 Horizontal :1 Vertical on the downstream face and the toe of the embankment.
- Installing a 6-inch diameter collector drain with aggregate filter system at the toe of the embankment.
- Removing the upper portion of the Gate House, removing the existing sluice gates and hoisting mechanism, installing four (4) new sluice gates and hoisting mechanism, removing and replacing the access steps and reconstructing the upper portion of the Gate House.
- Removing the two water intake pipes.
- Installing one new water intake pipe and abandoning the other.
- Earth Fill Covering the ACB surface with one (1) foot of soil to maintain the existing appearance of the dam.
- Installing new Piezometers.
- Repairing cracks and spalls in the concrete of the Primary Spillway and Gate House.
- Placement of scour protection downstream of the Primary Spillway and replacing Ford Crossing.

PROJECT TEAM:

John Lima, PE | President Gino Yannuzzelli | VP/Operations Derek Fuller | Project Manager Steve Sickler | Site Superintendent



MEADOW GROUNDS LAKE DAM REHABILITATION

FULTON COUNTY, PA

OWNER: PENNSYLVANIA FISH & BOAT COMMISSION Harrisburg, PA Gerald Woomer, PE (814) 359-5170 | gwoomer@pa.gov



ENGINEER: D'APPLONIA DIVISION OF GROUND TECHNOLOGY, INC. Pittsburgh, PA Aaron Antell, PE (412) 229-1596 | AJAntell@dappolonia.com

FINAL CONTRACT PRICE \$5,172,623 ACTUAL COMPLETION DATE April 2021

ORIGINAL CONTRACT PRICE \$5,090,000 CONTRACT COMPLETION DATE April 2021











PROJECT:	Meadow Grounds Lake Dam Rehabilitation
LOCATION:	Fulton County, PA
PROJECT TYPE:	Rehabilitation of Existing Earthen Dam Appurtenant Structures
PROJECT ROLE :	Prime Contractor

DESCRIPTION OF PROJECT:

The Meadow Grounds Lake Dam is a 40 ft high, 950 LF wide, high hazard classified earth embankment dam located in Ayer Township, Fulton County, Pennsylvania. The Meadow Grounds Dam Rehabilitation Project comprises modifying the dam and appurtenant structures to meet current dam safety criteria and design standards. Construction activities generally include removal of the existing concrete spillway structure, construction of a cast-in-place concrete replacement spillway and stilling basin, slip-lining the existing cast-in-place principal spillway conduit with pipe, modifications and improvements to the existing control tower, installing a seepage collection/toe drain and conveyance system consisting of a sand and stone filter with PVC pipe and a sand chimney/blanket drain, flattening the downstream slope, and raising dam crest approximately 3.6 feet. Work activities include:

- Clearing, grubbing and stripping of topsoil in earthwork areas.
- Demolition and removal of the existing cast-in-place concrete spillway.
- Control of water to complete all construction activities.
- Excavation, subgrade preparation, placement of general and embankment fill.
- Construction of seepage collection and conveyance system that includes an aggregate filter chimney drain, aggregate filter blanket drain, aggregate filter abutment trench drain, and piping system for collection and controlled discharge of water.
- Construction of concrete spillway, concrete spillway channel, and concrete stilling basin.
- Construction of permanent erosion protection ancillary to concrete spillway.
- Slip-lining and extension of existing concrete principal spillway conduit.
- Improvements to control tower including installing sluice gate and assemblies ancillary to the operation of the sluice gate.
- Installation and maintenance of all Erosion and Sedimentation Control features necessary for completion of the project.
- Installation of standpipe piezometers in dam embankment.
- Site restoration and revegetation.

PROJECT TEAM:

John Lima, PE | President Gino Yannuzzelli | VP/Operations Derek Fuller, PE | Project Manager Chris Knash | Superintendent & Surveyor Darren Rascher | Site Foreman Schnabel Engineering | Consulting Engineer



Appendix G -Attachment 1

MINSI LAKE DAM DAM REPAIRS & SPILLWAY REPLACEMENT

NORTHAMPTON COUNTY, PA



INSYLVANIA

gwoomer@pa.gov

ORIGINAL CONTRACT PRICE \$4,795,000

CONTRACT COMPLETION DATE April 2020

63

FINAL CONTRACT PRICE \$4,891,357

ACTUAL COMPLETION DATE November 2019





SCHNABEL ENGINEERING

LCiampitti@schnabel-eng.com





PROJECT:	Dam Repairs & Spillway Replacement – Minsi Lake Dam
LOCATION:	Northampton County, PA
PROJECT TYPE:	Rehabilitation of Existing Earthen Dam & Installation of a new Primary Labyrinth Spillway

PROJECT ROLE: Prime Contractor

DESCRIPTION OF PROJECT:

Minsi Lake Dam is a 26 ft high, 3,600 LF long, high hazard classified earth embankment dam located in Upper Mt. Bethel Township, Northampton County, Pennsylvania. The Minsi Lake Dam Rehabilitation Project comprises modifying the dam and appurtenant structures to meet current dam safety criteria and design standards. Construction activities generally includes removal of the existing concrete spillway, construction of a cast-in-place concrete replacement spillway, and modifications to raise the crest of the dam approximately two feet. Work activities include:

- Clearing, grubbing, and stripping the site, and removal of the existing concrete spillway and bituminous walk.
- Demolition and removal of the existing cast-in-place concrete spillway.
- Excavation and subgrade preparation.
- Construction of a cast-in-place concrete labyrinth weir and concrete spillway chute.
- Raising the existing embankment with earthfill and rip rap armorment.
- Construction of new embankment section, within the existing spillway approach channel, to tie into the existing embankment.
- Precast Concrete Low Water Crossing
- Spreading topsoil and seeding disturbed areas.

PROJECT TEAM:

John Lima, PE President	Gino Yannuzzelli VP/Operations

Derek Fuller, PE | Project Manager GEI Consultants | Consulting Engineer

Dan Samoni | Onsite Superintendent

RELEVANCE OF WORK:

The Minsi Lake Dam project as described above has following similarities as it relates the "Designated Critical Work":

- CIP Concrete Labyrinth Spillway (for watertight hydraulic & marine structures)
- Water Control including Dewatering & Diversion of Water
- Aggregate Drainage Filters & Seepage Collection Systems
- Earthwork and Excavated Material Screening on Dams
- Rip Rap Lining
- Concrete Spillway and Dam Embankment Demolition





INSURANCE BROKERS AND CONSULTANTS

April 25, 2024

KC Construction Company Attn: Wayne Randall 1737 Stout Drive Ivyland, PA 18974

Re: PA Workers Compensation Experience Modification Ratings Policy Terms: 2024, 2023, 2022, 2021, 2020 Bureau file Number: 2663455

Dear Wayne:

This is to confirm that the 4 year history of Pennsylvania Experience Modification Rates are as follows:

Effective Date	Expiration Date	Experience Rating Modification
06/01/2024	06/01/2025	0.987
06/01/2023	06/01/2024	1.025
06/01/2022	06/01/2023	0.968
06/01/2021	06/01/2022	0.774
07/01/2020	06/01/2021	0.760
07/01/2019	07/01/2020	0.754

Should you have any questions or require additional information, please contact me.

Sincerely,

Lauren Anderson

Lauren Anderson Account Assistant

100 Granite Drive – Suite 205 – Media, PA 19063 OFFICE 610-892-7688 – FAX 610-892-7695 www.safegardgroup.com

OSHA's Form 300 (Rev. 01/2004) Log of Work-Related Injuries and Illnesses

Attention: This form contains information relating to employee health and must be used in a manner that protects the confidentiality of employees to the extent possible while the information is being used for occupational safety and health purposes.

You must record information about every work-related injury or illness that involves loss of consciousness, restricted work activity or job transfer, days away from work, or medical treatment beyond first aid. You must also record significant work-related injuries and illnesses that are diagnosed by a physician or licensed health care professional. You must also record work-related injuries and illnesses that meet any of the specific recording criteria listed in 29 CFR 1904.8 through 1904.12. Feel free to use two lines for a single case if you need to. You must complete an injury and illness incident report (OSHA Form 301) or equivalent form for each injury or illness recorded on this form. If you're not sure whether a case is recordable, call your local OSHA office for help.

Establishment name

City lvyland

	Identify the person			Describe the o	case	Class	ify the case	9			
(A) Case No.	(B) Employee's Name	(C) Job Title (e.g., Welder)	(D) Date of injury or onset of illness	(E) Where the event occurred (e.g. Loading dock north end)	(F) Describe injury or illness, parts of body affected, and object/substance that directly injured or made person ill (e.g. Second degree burns on right	CHECP the mos	CONLY ONE st serious outo	box for each c come for that c	ase based on ase:	Enter the nu days the inju worker was:	imbe ured :
			(mo./day)		forearm from acetylene torch)	Death	Days away from work	Remain	ed at work	Away From Work	C trai res
								Job transfer or restriction	Other record- able cases	(days)	(
						(G)	(H)	(I)	(J)	(K)	
	None										
											<u> </u>
											-
											-
											+
											+
					l						
					Page totals	0	0	0	0	0	

Be sure to transfer these totals to the Summary page (Form 300A) before you post it.

Public reporting burden for this collection of information is estimated to average 14 minutes per response, including time to review the instruction, search and gather the data needed, and complete and review the collection of information. Persons are not required to respond to the collection of information unless it displays a currently valid OMB control number. If you have any comments about these estimates or any aspects of this data collection, contact: US Department of Labor, OSHA Office of Statistics, Room N-3644, 200 Constitution Ave, NW, Washington, DC 20210. Do not send the completed forms to this office.

Page 1 of 1

Appendix G -Attachment 2



Year 2023

U.S. Department of Labor

Occupational Safety and Health Administration

Form approved OMB no. 1218-0176

KC Construction Co.

 State	

PA

of or ill	Check th	e "injur	y" colum illne	nn or ch ess:	oose one	e type of
n job sfer or triction lays) (L)	(M) Kunțul (1)	Skin Disorder	 Respiratory Condition 	(4)	(G) Hearing Loss	(9) All other illnesses
0	0	0	0	0	0	0
	Injury	Skin Disorder	Respiratory Condition	Poisoning	Hearing Loss	All other illnesses
	(1)	(2)	(3)	(4)	(5)	(6)

OSHA's Form 300A (Rev. 01/2004) Summary of Work-Related Injuries and Illnesses

All establishments covered by Part 1904 must complete this Summary page, even if no injuries or illnesses occurred during the year. Remember to review the Log to verify that the entries are complete

Using the Log, count the individual entries you made for each category. Then write the totals below, making sure you've added the entries from every page of the log. If you had no cases write "0."

Employees former employees, and their representatives have the right to review the OSHA Form 300 in its entirety. They also have limited access to the OSHA Form 301 or its equivalent. See 29 CFR 1904.35, in OSHA's Recordkeeping rule, for further details on the access provisions for these forms.

Number of Cases



Number of Days

Total number of days away from work	Total number of days of job transfer or restriction
0	0
(K)	(L)

Injury and Illness Types

Total number of… (M)			
(1) Injury	0	(4) Poisoning	0
(2) Skin Disorder	0	(5) Hearing Loss	0
(3) Respiratory			
Condition	0	(6) All Other Illnesses	0

Post this Summary page from February 1 to April 30 of the year following the year covered by the form

Public reporting burden for this collection of information is estimated to average 58 minutes per response, including time to review the instruction, search and gather the data needed, and complete and review the collection of information. Persons are not required to respond to the collection of information unless it displays a currently valid OMB control number. If you have any comments about these estimates or any aspects of this data collection, contact: US Department of Labor, OSHA Office of Statistics, Room N-3644, 200 Constitution Ave, NW, Washington, DC 20210. Do not send the completed forms to this office.



U.S. Department of Labor Occupational Safety and Health Administration

Form approved OMB no. 1218-0176

Esta	ıblishı	nent informatio	n				
	Your e	stablishment name	KC Construction	Co.			
	Street	1737 Stout Drive					
	City	lvyland		State	PA	Zip	18974
	Industr	y description (e.g., Construction	Manufacture of mo	tor truck trailers)			
	Standa	rd Industrial Classif	ication (SIC), if kno	own (e.g., SIC 3715	5)		
OR	North A	xmerican Industrial	Classification (NAI	CS), if known (e.g., 0	336212)		
Emp	oloyme	ent information					
	Annual	average number o	femployees	28			
	Total h year	ours worked by all e	employees last	54,913			
Sign	n here						
	Knowi	ngly falsifying this	document may re	sult in a fine.			
	I certify comple	that I have examin te.	ed this document a	and that to the best	t⊾of my knowledge the entries a	ire true, accurate, Vice Presid	and
		Company	ecutive			Titl	e
	215-44	3-5553 Pho	ne			Dat	1/3/2024 e

OSHA's Form 300A (Rev. 01/2004) Summary of Work-Related Injuries and Illnesses

All establishments covered by Part 1904 must complete this Summary page, even if no injuries or illnesses occurred during the year. Remember to review the Log to verify that the entries are complete

Using the Log, count the individual entries you made for each category. Then write the totals below, making sure you've added the entries from every page of the log. If you had no cases write "0."

Employees former employees, and their representatives have the right to review the OSHA Form 300 in its entirety. They also have limited access to the OSHA Form 301 or its equivalent. See 29 CFR 1904.35, in OSHA's Recordkeeping rule, for further details on the access provisions for these forms.

Number of Cases



Number of Days

Total number of days away from work	Total number of days of job transfer or restriction
0	0
(K)	(L)

Injury and Illness Types



Post this Summary page from February 1 to April 30 of the year following the year covered by the form

Public reporting burden for this collection of information is estimated to average 58 minutes per response, including time to review the instruction, search and gather the data needed, and complete and review the collection of information. Persons are not required to respond to the collection of information unless it displays a currently valid OMB control number. If you have any comments about these estimates or any aspects of this data collection, contact: US Department of Labor, OSHA Office of Statistics, Room N-3644, 200 Constitution Ave, NW, Washington, DC 20210. Do not send the completed forms to this office.



U.S. Department of Labor Occupational Safety and Health Administration

Form approved OMB no. 1218-0176

Estal	olishr	nent information				
`	Your e	stablishment name KC Construction	Co.			
5	Street	1737 Stout Drive				
(City	lvyland	State	PA	Zip	18974
I	ndustr	y description (e.g., Manufacture of mot Construction	or truck trailers)			
ŝ	Standa	rd Industrial Classification (SIC), if kno	wn (e.g., SIC 3715)			
)R I	North A	merican Industrial Classification (NAIC <u>2</u> <u>3</u> <u>7</u> <u>1</u> <u>1</u>	CS), if known (e.g., 3 0	336212)		
mpl	oyme	ent information				
,	Annual	average number of employees	33			
}	Γotal h ∕ear	ours worked by all employees last	63,214			
ign	here					
I	Knowii	ngly falsifying this document may re	sult in a fine.			
l	certify comple	that I have examined this document a te.	ind that to the best o	of my knowledge the entries are t	rue, accurate, a	nd
_	/	Company executive	7		Vice Preside Title	nt
2	215-44	3-5553			1	/31/2023

Appendix G -Attachment 2

OSHA's Form 300A (Rev. 01/2004) Summary of Work-Related Injuries and Illnesses

All establishments covered by Part 1904 must complete this Summary page, even it no injuries or illnesses occurred during the year. Remember to review the Log to verify that the entries are complete

Using the Log, count the individual entries you made for each category. Then write the totals below, making sure you've added the entries from every page of the log. If you had no cases write "0."

Employees former employees, and their representatives have the right to review the OSHA Form 300 in its entirety. They also have limited access to the OSHA Form 301 or its equivalent. See 29 CFR 1904.35, in OSHA's Recordkeeping rule, for further details on the access provisions for these forms.



Post this Summary page from February 1 to April 30 of the year following the year covered by the form

Public reporting burden for this collection of information is estimated to average 58 minutes per response, including time to review the instruction, search and gather the data needed, and complete and review the collection of information. Persons are not required to respond to the collection of information unless it displays a currently valid OMB control number. If you have any comments about these estimates or any aspects of this data collection, contact. US Department of Labor, OSHA Office of Statistics, Room N-3644, 200 Constitution Ave. NW. Washington, DC 20210. Do not send the completed forms to this office.



U.S. Department of Labor Occupational Safety and Health Administration

Form approved OMB no. 1218-0176

Your establishment name KC Cons	struction Co.		
Street 1737 Stout Drive			
City Ivyland	State	PA	Zip 18974
Industry description (e.g., Manufactur Construction	e of motor truck trailers)		
Standard Industrial Classification (SIC	;), if known (e.g., SIC 3715)		
OR North American Industrial Classification	on (NAICS), if known (e.g., 3	36212)	
<u>2 3 7 1</u>	<u> 1 0 </u>		
Employment information			
Annual average number of employees	36		
Total hours worked by all employees is year	est68,229		
Sign here			
Knowingly falsifying this document	may result in a fine.		
I certify that I have examined this docu complete.	ment and that to the best of	f my knowledge the entries	are true, accurate, and
pl-p	let		Vice President
Company executive			Title
04E 440 EEE0			

OSHA's Form 300 (Rev. 01/2004) Log of Work-Related Injuries and Illnesses

Attention: This form contains information relating to employee health and must be used in a manner that protects the confidentiality of employees to the extent possible while the information is being used for occupational safety and health purposes.

Establishment name



Occupational Safety and Health Administration Form approved OMB no. 1218-0176

KC Construction Co.

You must record information about every work-related injury or illness that involves loss of consciousness, restricted work activity or job transfer, days away from work, or medical treatment beyond first aid. You must also record significant work-related injuries and illnesses that are diagnosed by a physician or licensed health care professional. You must also record significant work-related injuries and illnesses that are diagnosed by a physician or licensed health care professional. You must also record significant work-related injuries and illnesses that meet any of the specific recording criteria listed in 29 CFR 1904.8 through 1904.12. Feel free to use two lines for a single case if you need to. You must complete an injury and illness incident report (OSHA Form 301) or equivalent form for each injury or illness recorded on this form. If you're not sure whether a case is recordable, call your local OSHA office for help.

		And the second second second	entrine in the participation of the	Construction and a state of the solution of the solution of the		Contraction of the local division of the loc		City	ivyiand			- State		-	PA		
Id	entify the person			Describe the	case	Class	ify the case	e	- 和空影	Ser Charles		See all all	-			1 3 H	
(A) (B) Case Employee's Name No.	(C) (D) (E) Job Title (e.g., Date of injury Where the event occurred (e.g. Welder) or onset of Loading dock north end)		(E) Where the event occurred (e.g. Loading dock north end)	(F) Describe injury or illness, parts of body affected, and object/substance that directly injured or made	CHECK ONLY ONE box for the most serious outcome f		box for each case based on come for that case:		Enter the number of days the injured or ill worker was:		Check the "injury" column or choose one type illness:						
			(mo./day)	n Example cock for the end	person ill (e.g. Second degree burns on right forearm from acetylene torch)	Death Days	Death Days away from work	Days away from work Jo or	way work Remai Job transfer or restriction	other record- able cases	Away From Work (days)	On job transfer or restriction (days)	Injury (3)	Skin Disorder	Respiratory Condition	guinosio	Hearing Loss
_						(G)	(H)	(1)	(J)	(К)	(L)	(1)	(2)	(3)	(4)	(5)	(6)
-		-				-			-		-		-		-		-
-																	
-				-						-			-				-
-																	
-						-								-	-	_	-
_																	
_					Page totals	0	0	0	0	0	0	0	0	0	0	0	0
					Be sure to transfer these totals	to the	Summary	ane (Form	300A) befor		1	2		2 5		s,	w)
ic report iew the in not require any con	ing burden for this collection o struction, search and gather th red to respond to the collection mments about these estimates interse Room N3644 200 Con	f information is estimat the data needed, and co n of information unless or any aspects of this stitution Ave. NW Wa	ed to average 14 implete and review it displays a curre data collection, co	minutes per response, including time to w the collection of information. Persons intly valid OMB control number. If you pritact: US Department of Labor, OSHA 0. Do not acent the completed forms to		to the	Summary	Jage (Form	SUCA) DEION	e you post	п.	Injur	Skin Disorde	Respirator Conditio	Poisonin	Hearing Los	All other illnesse
office.		or 100, 117, 110, 1117, 110,	aningion, DO EUE	to the rest same the completed round to					Page	1 of 1		(1)	(2)	(3)	(4)	(5)	(6)



Marquette Lake Dam - Rehabilitation

Project No. DGS C-0960-0086 Phase 1

SECTION 2.

Project Management

<u>Team</u>

KC CONSTRUCTION CO.

1737 Stout Drive, Ivyland, PA 18974 | 215-443-5553

Marquette Lake Dam Rehabilitation

Project No. DGS C-0960-0086 Phase 1

TECHNICAL SUBMITTAL

Section 2. Project Management Plan

T-2A Project Management Team

KC CONSTRUCTION CO.
MARQUETTE LAKE DAM REHABILITATION PROJECT NO. DGS C-0960-0086 PHASE 1

TECHNICAL SUBMITTAL

T-2A Project Management Team

<u>KC Construction Co. – John V. Lima, PE</u> – President - Geotechnical Engineer - Mr. Lima has 45 years of geotechnical field experience which he utilizes to solve field problems and keep a job running. In his role as internal QA/QC he is a resource to tap when an unusual condition occurs using his technical training as an Engineer and his unique field experience.

<u>KC Construction Co. – Gino Yannuzzelli</u> – Vice President – With 30 years of experience, Mr. Yannuzzelli is responsible for the day-to-day field operations of the company. He will oversee the project managers and project superintendents and will coordinate, and schedule required project manpower and equipment with the project team. Reports to Mr. Lima

<u>KC Construction Co. – Tim Wintermute</u> – Sr. Project Manager – With over 30 years of hands-on experience, Mr. Wintermute has been involved in all aspects civil construction including dam rehabilitation and flood control projects ranging in size and complexity. Mr. Wintermute will be responsible for the day-to-day project management including scheduling, submittals, RFI's, and change order management. Reports to Mr. Yannuzzelli.

<u>KC Construction Co. – Bobby Machiesky</u> – General Superintendent – Responsible for the daily activities performed onsite by KC forces and our subcontractors. Mr. Machiesky is also in charge of KC's construction surveying efforts. Bobby has served as project superintendent on many of our more complex dam rehabilitation projects and will work closely with the site foreman to ensure planning and approach are in best practice for this project. Reports to Mr. Yannuzzelli

<u>KC Construction Co. – Dan Samoni</u> – Project Site Forman – Responsibilities include coordination among subs and suppliers, trade supervision and harmony, problem solving from start to successful completion. Supervises all KC onsite crews along with all subcontractors and the coordinating with the Quality Control Agency. Mr. Samoni has over 15+ years of experience acting as the responsible party for coordinating the field resources while interacting with the Owner's representatives to ensure that the projects were constructed in accordance with the engineer's design and overall project intent. He has extensive experience in Heavy Civil projects involving watertight concrete structures, dams, and flood control projects. Reports to Mr. Wintermute and Mr. Machiesky.

<u>GEI Consultants Engineering – Andy Baxter, PE</u> – Sr. Project Manager – Water Control, Diversion, and Dewatering Consultant – Andrew is a Professional Geologist and Professional Engineer who specializes in performing design of below grade and temporary hydraulic structures related to dams and levees. Andrew has provided project and construction management, development of construction documents for geo-structural designs for specialty foundations, ground improvement, excavation support, permanent cut walls, dewatering, soil and rock slopes, cofferdams and other subsurface structures. He will work with KC's in-house engineers to develop a custom-designed system based on the site conditions and the constraints of the project. Mr. Baxter reports to KC Project Managers.

<u>GEI Consultants Engineering – Marat Mardenov, PE</u> – Sr. Engineer – Water Control, Diversion, and Dewatering Consultant - Mr. Mardenov has approximately 12 years of experience that includes Civil Design, Hydraulic/Hydrologic, Modeling, Remedial Construction, Storm Water Design, Construction Permitting, Construction Management, Environmental Compliance and Consulting. His primary role on this project includes

development of work plans, H&H modeling and completing necessary calculations for cofferdam installations. Marat will also provide recommendations to improve quality, schedule, and cost control associated to the control of water and dewatering scope.

<u>Performance – Eric Eichenberg</u> - Vice President - Eric has over 25 years of project management experience, beginning his career with Performance's sister company, Quandel Construction Group. Since transferring to Performance's team, he has worked on two dam projects and three treatment plant upgrades. Eric will serve as team leader for the staff assigned to the project's day-to-day operations Examples of his experience specific to this contract include:

- Greater Pottsville Sewer Authority | Fleet and Operations Superintendent for this project, which included the total rehabilitation of the spillway consisted of 3800 CY of concrete with walls up to 25' in height. The project also involved water control and sluice gate installation. Two tropical storms hit in the middle of the project, delaying its completion; however, due to Performance's proper planning and attention to detail, all excess water was managed without any failure in function.
- Binghamton Wastewater Treatment Plant | Fleet and Operations Superintendent for this ongoing project, which included the total rehabilitation of the wastewater treatment plant.
- Meadow Grounds Lake Dam | Project Executive for this project. He was responsible for the schedule and operations working closely with the superintendent. This project was scheduled for a 6-month completion and our team completed it within 5 months which included a one month delay due to COVID-19 shutdown.

<u>Performance – Brian Mickatavage</u> - General Superintendent - Brian has 30 years of construction experience and has successfully accomplished five dam projects. He served as a Carpenter, Carpenter Foreman, and Project Superintendent and is experienced in all facets of building construction. Examples of his experience specific to this contract include:

- Binghamton Wastewater Treatment Plant | Project Superintendent. He was responsible for all aspects of the work, scheduling and coordination, quality control, monitoring of sub grades, cast in place structural concrete and project safety.
- Abington Regional Wastewater Treatment Plant | Project Superintendent. He was responsible for all aspects of the work, scheduling and coordination, quality control, following the new federal mandate of reducing the levels of nitrates and phosphates into local waterways. This project was completed five months ahead of schedule.
- Lackawanna River Basin Sewer Authority, Archbald WWTP | Project Superintendent. He was responsible for all aspects of the work, scheduling and coordination, quality control and safety.

<u>Performance – Leah Eichenberg</u> - Project Manager - Leah has served the construction industry for 4 years. Her attention to detail and insistence on high standards and quality work make her a very valuable member of the Performance team. She is experienced in all facets of construction, especially environmental, highway, municipal and commercial construction.

<u>Performance – Andy Studlack</u> – Project Foreman – Robert has served in the construction industry for 25 plus years. His skills in running efficient and timely projects have made him a very valuable member of the Performance construction team. His safety record has been exemplary. He has served as a carpenter and carpenter foreman and is experienced in all facets of building construction.



JOHN V. LIMA, P.E. PRESIDENT

1737 Stout Drive Ivyland, Pennsylvania 18974

T (215) 443-5553 C (267) 784-6999 E JohnL@kcconstruct.com

EXPERIENCE SUMMARY

Over thirty years as a General Contractor/Construction Manager and Consulting Engineer. Most recent experience as President, Estimator, Project Manager, and Quality Control Manager of KC Construction Company with annual business volume of \$20 to \$30 million dollars. Experience includes the management of numerous Heavy Civil construction projects relating to water, wastewater, dam safety improvements, Roller Compacted Concrete (RCC) and environmental protection projects. Experienced Geotechnical and Foundation Engineer and Licensed Land Surveyor with specific expertise in earth dam design and inspection.

EXPERIENCE

KC CONSTRUCTION CO., IVYLAND, PENNSYLVANIA 1983 TO PRESENT PRESIDENT

Responsible for the overall management of the company, provide technical assistance and troubleshooting to resolve unforeseen site conditions and value engineering alternatives. Responsible for quality control of all earthwork activities including structural backfill of embankments and levees, sheeting and shoring applications and dewatering facilities.

Project Management responsibilities have included a wide range of Public Works, Commercial and Industrial Projects. Recent Public Works projects include: landfills, earth dams, site development, municipal complexes, transit facilities, water treatment facilities and water distribution systems.

ENVIROSAFE SERVICES, INC., HORSHAM, PENNSYLVANIA 1981-1982

ENGINEERING SUPERVISOR/LEAD TECHNICAL ENGINEER

IU CONVERSION SYSTEMS, HORSHAM, PENNSYLVANIA 1979-1981

QC SUPERVISOR - LANDFILLS

CITY OF PHILADELPHIA, PENNSYLVANIA

1976-1978

CONSTRUCTION ENGINEERING SUPERVISOR

U.S. ARMY CORPS OF ENGINEERS, PHILA., PENNSYLVANIA 1974-1974 FOUNDATION DESIGN

EDUCATION

TEMPLE UNIVERSITY

- B.S. Civil Engineering Drexel University, 1974
- M.S. Civil Engineering (Geotechnical) Drexel University, 1977
- Real Estate School Temple University (1978-1979)
- Graduate Studies Finance LaSalle College (1980-1981)

CERTIFICATIONS

- Professional Engineer Pennsylvania
- Professional Land Surveyor Pennsylvania
- American Society of Civil Engineers (A.S.C.E.)
- American Society of Testing Materials (A.S.T.M.)



GINO YANNUZZELLI VICE PRESIDENT OPERATIONS

1737 Stout Drive Ivyland, Pennsylvania 18974

T (215) 443-5553 C (484) 894-9063 E GinoY@kcconstruct.com

EXPERIENCE SUMMARY

Over twenty-five years of experience in the business administration, project management, and operations management of building, sitework, and heavy civil construction projects and companies. Gino joined KC in 2005 and has held the positions of Procurement Manager, Controller, Project Manager, Estimator, and Operations Manager working on sitework, water/wastewater treatment plants, and flood control/dam projects ranging from \$1mm to \$25mm.

EXPERIENCE

KC CONSTRUCTION CO., IVYLAND, PENNSYLVANIA

2005 TO PRESENT

VICE PRESIDENT

Responsible for the overall day to day corporate operation of the company, including the development, implementation, and management of strategic business, financial, and operational plans, and budgets.

OPERATIONS

Oversees the company project managers and superintendents. Coordinates and schedules required project manpower and equipment with the project team. Responsible for the hiring, training, management, and evaluation of field labor as required.

PROJECT MANAGER

Job tasks include development of job costs and project schedule, buyout of subcontracts and materials, in-house and subcontractor workforce management for dam rehabilitation and flood control projects ranging from \$1million to \$25million.

PROJECT ESTIMATOR

Assists with estimating performing earthwork take-offs and material calculations, cost estimates, vendor and subcontractor solicitations. Review of subcontractor and supplier bids in accordance with contract requirements.

KULLMAN INDUSTRIES, INC., LEBANON, NEW JERSEY 1995-2004

SR. PROCREMENT MANGER AND ESTIMATOR

Responsible for the project procurement and contract management for general contractor/modular construction manufacturer with annual contract revenues of \$75mm to \$100mm specializing in construction of retail buildings, schools, hospitals, prisons, cellular equipment housing, and international U.S. embassy compounds. Assisted the estimating team as needed.

EDUCATION

• A.S. Civil Engineering/Construction Technologies Essex County Community College, Newark, NJ 1995

CERTIFICATIONS

- OSHA 30
- American Red Cross CPR & First Aid
- State of Maryland Erosion and Sediment Control Responsible Person
- State of Delaware Erosion and Sediment Control Responsible Person (Blue Card)



KC CONSTRUCTION CO.

1737 Stout Drive, Ivyland, PA 18974 | 215-443-5553

Resume for Timothy R. Wintermute - A distinguished Project Manager with a rich background in the heavy civil construction industry, starting out as a heavy equipment operator, laborer, and grade foreman, advancing to a supervisor, project manager, and project executive level position before reaching the position of chief operations officer. With experience on numerous large-scale earthwork projects across the tri-state area, ability has been demonstrated in handling diverse challenges including sheeting/shoring, dewatering, historic dredge management, soil stabilization, and large outlet drainage structures. This journey through various roles underscores the deep understanding of project dynamics and exemplifies an ability to lead teams effectively through complex endeavors.

<u>Updated on</u>: 07.08.24

Skills

- Operations management
- Brand development

- Business structure/division development
- Budgeting and cost control

Experience

<u>Senior Project Manager</u>

06/03/24 to present

KC Construction Company – Ivyland, PA

- Potomac Dam No. 5: West Abutment Preservation Project Clear Spring, MD, United States; (06/24 present); \$6.68M contract value:
 - Client = Bureau of Reclamation / National Park Service
 - Scope of Work: Stabilization of historic stone masonry abutment, installation of drainage and flood overtopping protection.
- Stony Garden Dam Rehabilitation Project Wind Gap, PA (06/24 present); \$5.40M contract value:
 - Client = Pennsylvania American Water
 - Scope of Work: Installation of new concrete spillway/removal of existing, installation of new chimney & toe drain system, upgrade of water utility service mains, ect.





1737 Stout Drive, Ivyland, PA 18974 | 215-443-5553

<u>Senior Project Manager</u> Thalle Construction Company – Hillsborough, NC

06/2020 to 06/2024

- Round Valley Reservoir WSA B19030 Lebanon, NJ, United States; (01/2020 present); \$67.3M; Sr. Project Manager: work necessary to facilitate the Dam Rehabilitation including:
 - major earthwork exceeding 1.3M c.y. in dam embankment cuts and fills,
 - o abandonment of existing dam instrumentation and installation of new dam,
 - o installation, operation, and maintenance of a dewatering system during construction,
 - importing several thousand tons of drainage fill for installation of chimney, abutment, and collector drains,
 - road closures, maintenance of traffic, erosion, and sediment control, clearing and grubbing stockpile areas, stripping topsoil, relocation of utilities, and spreading topsoil and establishment of permanent turf.
 - ancillary work related to the Dam Structure included removal and replacement of piping (12-inch or less), grouting of approximately 1,400 LF of 36-inch piping, and building improvements (roofing, gutters, rooftop access system, concrete repairs, general building repairs, window replacement, sluice gate repair, transfer switch installation, provide portable generator, and crane replacement).
- Cooper Lake Dam Rehabilitation Project: for the City of Kingston Water Department Contract No. C-205 & Schnabel Engineering Project No. 14925003.03 from June 2021 – June 2024; \$15.8M; Sr. Project Manager: work necessary to facilitate the Dam Rehabilitation.

Chief Operations Officer

03/2017 to 06/2020

Vollers, Inc. – *North Branch, New Jersey*

- Formulated analysis assessments to make informed decisions on proposed projects.
- Increased profitability by optimizing sales and fulfilling lower overhead costs.
- Streamlined company processes and procedures while enhancing customer satisfaction.
- Collaborated with board members, senior executives, and industry partners to revitalize operations and achieve ambitious targets.



KC CONSTRUCTION CO.

1737 Stout Drive, Ivyland, PA 18974 | 215-443-5553

Project Executive

Vollers, Inc. – North Branch, New Jersey

- Created strategic plans to turn leadership mandates into actionable project plans.
- Collaborated with upper management to assess business needs and develop road maps.
- Accurately estimated time and materials costs for projects.

Project Manager, V.P.

Vollers Excavation & Construction Co., Inc – North Branch, New Jersey

- Maintained project schedules by managing timelines and making initiative-taking adjustments.
- Maintained project quality with a firsthand management style.
- Directed planning, budgeting, vendor selection and quality assurance efforts.
- *Kept meticulous records of all costs and expenses and analyzed that data against the budget.*

Project Superintendent

Vollers Excavation & Construction Co., Inc – North Branch, New Jersey

- Continuously inspected job sites to ensure that staff and subcontractors strictly observed all safety protocols.
- Implemented changes requested by designers, owners, or inspectors.
- Accurately estimated time and materials costs for projects.
- Reviewed blueprints and specifications to understand each job and plan the correct sequence, minimizing errors and avoiding wasted materials.

Project Engineer

Vollers Excavation & Construction Co., Inc – North Branch, New Jersey

- Completed daily construction tasks while ensuring safe working conditions, staying on budget, and meeting project deadlines.
- Consulted with company executives and projects managers to acquire resources to move projects forward.
- Analyzed blueprints and delivered concise instructions to the technical team to maintain quality control.
- Assisted in planning site layouts and blueprints.



12/2015 to 03/2017

12/2005 to 12/2015

01/1998 to 12/2005

01/1994 to 01/1998





1737 Stout Drive, Ivyland, PA 18974 | 215-443-5553

Accomplishments

- Started on Div. II NAIA football team at Taylor University all (4) seasons of eligibility.
- Member of Chi Epsilon Civil Engineering Honor Society at NJIT.
- Served on the Franklin Township Committee (Hunterdon County, NJ).
- Served on the Building & Planning Committee and Community Outreach Group at the Southridge Community Church.

Education

•	Bachelor of Science : Civil & Environmental Engineering <u>New Jersey Institute of Technology</u> - Newark, NJ	Jan 1994
•	Bachelor of Science : Systems Analysis/Natural Science Taylor University - Upland, IN	Jan 1991

Additional Information

• Married with three children – daughter, Paige is a S.L.P. graduate student at NC – Chapel Hill / daughter, Gillian is a business student at Raritan Valley Community College / son, Shane is a senior at North Hunterdon H.S. heading the University of Pittsburgh to study architecture in the fall.

List of Key Projects Detailing Experiences Per Position:

Chief Operations Officer

03/2017 to 03/2020

Vollers, Inc. – *North Branch, New Jersey*

• As C.O.O., took over, retooled, and stabilized the organization over a three-year period while achieving the following revenue totals: 2017 = \$82M / 2018 = \$74M / 2019 = \$66M.



ROBERT MACHIESKY PROJECT MANAGER GENERAL SUPERINTENDENT

1737 Stout Drive Ivyland, Pennsylvania 18974

T (215) 443-5553 **C** (570) 780-8560

C(5/0)/80-8560

E <u>bobm@kcconstruct.com</u>

EXPERIENCE SUMMARY

20 years' experience in the administration and field management of sitework, dam, levee, and heavy civil construction projects.

RELEVANT PROJECTS

2023 – Dunmore No.7 Dam 2023 – Lake Montrose Dam 2022-2023 – Shikellamy Fish Passage 2021-2023 – Sheppard Myers Dam 2022 – Upper Birchwood Lake Dam 2021-2022 - Rawson Hill Dam 2021 – Beaver Creek Dam 2020 – Montour Ash Basin Spillway 2020 – Harrisburg Airport Levee 2019-2020 - Pecks Pond Dam 2019 – Donegal Lake Dam 2017-2018 - Chapman Lake Dam 2017-2018 – Lake Scranton Dam 2016-2017 - Bear Gap Dam 2016-2017 – Silver Lake Dam 2016 – Glade Run Lake Dam 2015 – Speedwell Forge Lake Dam 2014 - Swimming River Reservoir 2013-2014 - Delaware Bay Dikes 2013 – Kauffman Dam 2013 – Lake Oneida Dam

EXPERIENCE

KC CONSTRUCTION CO., IVYLAND, PENNSYLVANIA

2005 TO PRESENT SUMMARY

Over 15 years' experience in heavy civil and site work project management. Most recent experience as an onsite project manager and superintendent for KC Construction specializing in dam rehabilitation projects. Robert's expertise is in the planning, management, and supervision of rehabilitation projects featuring embankment fill, toe drains, cast-in-place concrete spillways, roller compacted concrete (RCC), riprap armoring, and articulated block (ACB) overtopping protection.

2005 TO PRESENT - IN-HOUSE SURVEYOUR

Robert is also the surveyor for most of KC's projects. Responsible for construction layout, location verification, topographic surveys, quantity measurements, and as-built documentation as a PLS.

2016 TO PRESENT – PROJECT MANAGER

Responsible for: the development of job costs and project schedule; buyout of subcontracts and materials; submit product data and shop drawings as required; coordinate all work and schedule with onsite project superintendent; initiate and submit all requests for information and requests for change orders; coordinate and attend project meetings with the owner and engineer; update job costs and schedules; and provide monthly project status updates to company principals.

2010 TO 2016 – PROJECT, RCC, AND ACB SUPERINTENDENT Monitor all contract operations onsite for schedule, quality, and overall contract compliance. Interface with Owner's onsite representative and Engineer as required. Oversee and schedule the use of independent testing laboratories for compliance verification of soils, concrete, structural, and mechanical systems. Monitor subcontractors and "in house" construction for contract compliance as well as reviewing vendor submittals for field conditions and installation requirements

EDUCATION

PENN STATE UNIVERSITY

• Associates of Science, Survey Technology, December 2010

CERTIFICATIONS

- Pennsylvania Professional Land Surveyor (PLS)
- OSHA 30
- OSHA 10
- National Safety Council CPR, First Aid, and AED



SITE FOREMAN

SHEIOKLINAN

1737 Stout Drive Ivyland, Pennsylvania 18974

T (215) 443-5553 C (267) 220-0985 E dans@kcconstruct.com

EXPERIENCE SUMMARY

Over 15 years' experience in the administration and field management of sitework, dam, levee, and heavy civil construction projects.

RELEVANT PROJECTS

2021 – Round Valley North Dam
Rehabilitation
2020 – Hibernia Dam Rehabilitation
2019 – Strawberry Fields Dam Repair
2018 – Dam Repairs and Spillway
Replacement Minsi Lake Dam
2013 – Lake Oneida Dam Rehabilitation
2012 – Rehabilitation of Mt. Laurel Dam
2011 – Lycoming Landfill Field 11

EXPERIENCE

KC CONSTRUCTION CO., IVYLAND, PENNSYLVANIA

OCTOBER 2018 TO PRESENT MAY 2004 TO JANUARY 2013

Project Superintendent and Site Foreman on heavy civil site work, athletic field, and earthen dam and levee projects ranging from \$500,000 to \$20 million. Responsible to lead and manage in-house earthwork and utility crews, monitor all contract operations onsite for schedule, quality, and overall contract compliance. Interface with Owner's onsite representative and Engineer as required. Oversee and schedule the use of independent testing laboratories for compliance verification of soils, concrete, structural, and mechanical systems. Monitor and direct the work subcontractors and "in house" construction for contract compliance as well as reviewing vendor submittals for field conditions and installation requirements.

B. BLAIR CORPORATION, IVYLAND, PENNSYLVANIA

JANUARY 2013 TO OCTOBER 2018

Project Manager for sitework projects ranging from \$100,000 to \$8 million in the residential, commercial, and institutional market. Responsible for the management and coordination of project construction activities following the project schedule to assure timely completion and close-out of the project; buyout for project materials and subcontractors; process project billings, change orders, submittals, RFI's, and as-builts; provide daily liaison with project owners, engineers, and reviewing agencies.

EDUCATION

CALIFORNIA UNIVERSITY OF PENNSYLVANIA

• Bachelor of Science in Graphic Communications Technology, December 2000

CERTIFICATIONS

- OSHA 30
- OSHA 10
- National Safety Council CPR, First Aid, and AED
- State of Delaware Erosion and Sediment Control and Stormwater Management CERTIFICATIONS

Andrew C. Baxter, P.G., P.E. Senior Professional

Andrew Baxter is a professional geologist and professional engineer who specialize in performing design, engineering bid support, and construction quality management of embankment, structural remediation, and below grade and temporary hydraulic structures related to dams and levees and specialty geostructural projects. He has provided project and construction management, development of construction documents for dam, dam remediation, and specialty geostructural designs for foundations, ground improvement, excavation support, permanent cut walls, dewatering, soil and rock slopes, cofferdams, and other subsurface structures. In addition, he has performed geotechnical engineering studies, soil and rock slope evaluations, geologic site assessments for various structures.

PROJECT EXPERIENCE

Sanford Dam (Restoration), Midland, MI. Mr. Baxter is the Lead design engineer and co- EOR for the Sanford Dam restoration. Construction is underway for the rebuilding of the dam including filtered embankment construction, sheetpile cutoff wall, RCC armoring and new RCC spillway, crest gates, slide gates, new CIP concrete primary spillway, pier, and apron, and supporting floodwalls and structures and armoring. Mr. Baxter provided background and participated in the project PFMA and SQRA efforts. The design process included the reviews by peer reviewers and the state agency officials. Mr. Baxter's team coordinated with a local partner firm for permitting and Architectural and MEP elements. Cost: >\$80M

Pikes Creek Dam, Ceasetown, PA. Geologist of Record and Project and Technical Manager for the dewatering design and construction engineering services of a 65-ft high, 2,155-ft long earth embankment with stone masonry core and structure. Rehabilitation included a new toe drain, outlet structure, and spillway improvements. The dewatering system was applied along nearly the full length of the dam, over 2,000 ft. The dewatering consisted of shallow sumps in the foundation materials and deep dewatering wells for the new outlet structure on rock. The excavation was dry when exposed. Prior to the dewatering system activation the groundwater was artisan in the area of the deep excavation.

George B. Stevenson Dam, Grove Township, PA. Geologist of Record and Project and Technical Manager for the dewatering design and construction engineering services of a 160 ft high, 1,600-ft long earth embankment dam. Rehabilitation included a new toe and blanket drain to relieve foundation pressures. The perimeter of the blanket drain was about 1,050 ft. Mr. Baxter used bedrock sump wells installed from an early stage of excavation. The sump system used planned rock drains so to eliminate the need for a costly deep well system. The groundwater piezometeric height before dewatering was over 25 ft above the bottom of the excavation. Additionally Mr. Baxter assisted the client to develop a threshold monitoring plan to facilitate



EDUCATION M. Eng., Geotechnical Engineering, Drexel University B.S., Geology, Virginia Polytechnic Institute and State University

EXPERIENCE IN THE INDUSTRY 25 years

EXPERIENCE WITH GEI 9 year(s)

REGISTRATIONS AND LICENSES Professional Engineer, DE No. 15483 Professional Geologist, PA No. 004573 excavation safety.

Pine Creek Dam, OK. Engineer of Record and Project and Technical Manager for the dewatering design and construction engineering services for dewatering design for a Chimney filter. The two phase dewatering system was for a 125 ft long by 100 ft deep chimney drain located close to the centerline of the dam. The dewatering system consisted of deep wells that were designed to prevent erosion of the embankment while draining the groundwater from the proposed excavation. The sonic drilling targeted a narrow gap between a historic rock trench and an existing concrete outlet pipe. Pine creek dam is 125 ft tall and the main embankment is over 1.5 miles long.

Elkhart Dam, Elkhart IN. Mr. Baxter was the lead designer for the seepage mitigation project at Elkhart Dam on the St. James River. The geotechnical investigation lead the design to a sheetpile cutoff that functions as the cofferdam during construction reducing the rework requirements. The design included temporary work design as well as permanent conditions design to reduce the uplift pressures on the concrete gravity spillway of the FERC regulated Dam. The design included seepage cutoff design with sheetpile, LLDPE, reinforced concrete apron, structural steel, and cofferdam design. Andy led a Temporary Construction PFMA and a review of the design mitigating the critical PFM's.

Edenville Dam (Emergency Stabilization), Midland, MI. Mr. Baxter was the Lead design engineer for the Emergency Stabilization for Edenville dam Tittabawassee Reach. Mr. Baxter provided rapid distributions and analysis of alternatives with cost estimating. The project was completed with a multi-delivery design packages so the contractor could start work and continue without schedule delay. Mr. Baxter also lead the Construction Engineering Support working through typical design changes and cost saving value engineering efforts. The project included site development, multiple cofferdams, spillway demolition, sheetpile installation, rip rap, and about 65,000 cy of embankment fill.

Sanford Dam (Emergency Stabilization), Midland, MI. Mr. Baxter was the Lead design engineer for the Emergency Stabilization for Sanford dam on the Tittabawassee. Similar to the Edenville project, Mr. Baxter provided rapid distributions and analysis of alternatives with cost estimating. The project was completed with a multi-delivery design packages so the contractor could start work and continue without schedule delay. The project included site development, concrete demolition and mass concrete placement, sheetpile installation, and rip rap.

Lakeview Dam, Colonial Heights, VA. Mr. was the lead designer for the left abutment protection design for the non-overtopping section of the gravity concrete dam. In a flood of record, the section overtopped and there was end around flow that eroded the abutment and downstream area of the dam. Mr. Baxter performed alternatives analysis and lead the design of the repair for the FERC regulated structure and town owned dam. The design process included a PFMA where Andy participated as the designer. The repair included a mass concrete gravity wall with passive tiedown anchors and filtered drainage.

Racine Dam, Racine, OH. (Technical Manager). Mr. Baxter served as managing technical Engineer for right abutment replacement dam next to 24-MW hydroelectric dam at a USACE lock and dam on the Ohio River. Performed PFMA and options analysis for a repair to allow power generation, full navigation pools and gate operations at the Lock and Dam. The selected repair solution was to construct a replacement dam immediately upstream of the distressed existing dam in the wet. The replacement dam required about 225,000 cu yds of tremie placed and 185,000 cu yds of dry placed mass concrete and CLSM pours to form a mass concrete gravity dam. The dam is founded on pre-drilled 90-ft long, large diameter drilled shafts socketed into bedrock. The project required extensive review by the USACE (Huntington), FERC and an independent Board of Consultants through a process of design alternative studies, PFMA, workshops, and risk-reduction based design and construction process. The USACE allowed repairs to proceed without final dam design drawings. Construction Cost: >\$100M



PREVIOUS PROJECT EXPERIENCE

Dam and Water

Swimming River Lake Dam, New Jersey-American Water Company/ KC Construction, Monmouth County, NJ. Geostructural Design Engineer responsible for evaluating the constructability and design of control of water cofferdams and shoring, potential sequencing and risk of storm overtopping for the project. Specifically, designed three unique cofferdam systems that facilitated reconstruction of the concrete spillway. Cofferdams included buttressed steel and wood lagging vertical panels, sheetpiling, stacked concrete block, and porta-dam systems. The system was designed to be versatile to accommodate varying site conditions while managing significant storm events and high tail water.

Antietam Reservoir, Reading, PA. Project Specialist responsible for the post-tension tiedowns, review of tiedown installation and testing, and review of structural design of anchorage and support slabs. Tiedowns ranged in load from 200 kips to 740 kips.

Canton Lake Dam, Canton, OK. Project Engineer for the 70-ft tall support of excavation for a spillway excavation in a USACE dam, and designer of record for the dewatering system. The project documents by the USACE provided strict performance requirements for the design-build systems. The support of excavation is composed of an existing diaphragm wall underpinned and deepened with a drilled-in soldier pile wall with posttensioned anchors. The design is set to meet tight tolerances for settlement and movement of the existing diaphragm wall. Groundwater levels are about 10 ft. to 15 ft. from the ground surface. The design included rigorous analysis with Plaxis, Slope/W, and other methods. The retained soils included complex over consolidated clays and considered fully softened parameters.

Middle/Upper Dams, Rangeley, ME. Project Engineer and Designer of cofferdams and excavation support for construction of both the primary and auxiliary spillways through and in front of the existing embankment dam. The temporary excavation support system retains the embankment soils and full pond water level, and as designed includes drilled-in steel piles with shotcrete lagging. Piles are retained to provide additional uplift resistance for the auxiliary spillway. Due to the support system embedment within the embankment and inclusion with the permanent structure, location and movement tolerances are tight. The work consists of protection systems including a two-sided cell style sheet pile cofferdam, internally braced composite wall cofferdam, and sheet pile and stone buttress cofferdam. All designs are in accordance with the USACE and the FERC guidelines and recommendations.

Lake Oneida Dam, Pennsylvania-American Water Company, Butler County, PA. Geostructural Engineer responsible for evaluating the constructability and potential sequencing for the project. Specifically, evaluated the cofferdam requirements which resulted in coordination of temporary and permanent elements to reduce construction materials. Also evaluated the feasibility of the steel sheeting cutoff for the proposed spillway to provide uplift resistance. The steel sheeting was also coordinated with temporary cofferdam requirements. Performed a dewatering alternative evaluation with the project team. This evaluation increased the overall efficiency of the project.

PROFESSIONAL ASSOCIATIONS

USSD, Member Post tensioning Institute, PTI, DC-35 Committee Chair ASDSO, The Association of Dam Safety Officials, Member



Marat Y. Mardenov, P.E. Senior Engineer

Mr. Mardenov is a licensed civil engineer, experienced in site design, grading and drainage, hydraulic and hydrologic modeling, erosion and sedimentation control, environmental remediation, critical infrastructure, heavy civil construction, hydraulic structures, and landfills for public and private clients throughout the United States of America. He has acted as the Resident Engineer on several dam projects, focused on safety, construction quality, cost and schedule. Marat understands the nuances of interdisciplinary design, constructability, value engineering and multi-stakeholder projects. He brings value and ownership to his clients from planning phases, through commissioning, operations, and maintenance.

PREVIOUS PROJECT EXPERIENCE

Secord Dam Reconstruction, Four Lakes Task Force, Midland

MI. Serving as the Quality Assurance Manager for the reconstruction of two deteriorating dams, developed and implemented a program wide quality management system. Lead a team of field and resident engineers overseeing execution of work including, placement of concrete, earth works, exploratory drilling, soil nailing, and installation of approximately 3700 linear feet of steel sheet pile wall. Lead coordination between the project delivery team during the preparatory phase of the Work, and worked with the stake holders to resolve construction deficiencies and non-conformances. [12-22 to 6-24]

Secord Dam Reconstruction, Four Lakes Task Force, Midland

MI. Prepared design specifications prior to mobilization and Contract Award for the installation steel sheet pile cut off wall. Provided on and off-site construction contract administration support as the Resident Engineer, acting on behalf of the Engineer of Record to provide Quality Assurance, review of Contractor submittals, assistance with of field change documents and requests for information. Coordinated the installation of monitoring equipment. Implemented dam safety surveillance and monitoring plan to assess the effect of the Work on adjacent structures, by analyzing the data and issuing direction for remedial measures as necessary. [9-22 to 11-22]

Sanford Dam Interim Stabilization Construction, Four Lakes

Task Force, Midland MI. Provided on and off-site construction contract administration support as the Resident Engineer, acting on behalf of the Engineer of Record to provide Quality Assurance, review of Contractor submittals, assistance with of field change documents and requests for information. Prepared design plans for the interim stabilization of Sanford Dam following the catastrophic dam failure. Work included existing structure demolition, installation of approximately 1,200 linear feet of sheet pile, installation of temporary reinforced concrete spillway. Assisted with the implementation of dam safety surveillance and monitoring plan to assess the effect of the Work



EDUCATION M.S., Civil Engineering, Villanova University B.S., Civil Engineering, Pennsylvania State University

EXPERIENCE IN THE INDUSTRY 14 years

EXPERIENCE WITH GEI 3 years

REGISTRATIONS AND LICENSES Professional Engineer, PA No. PE085052 Professional Engineer, WV No. 24555

TRAINING AND CERTIFICATIONS

40-Hour Hazardous Waste Site Training Course, OSHA 29 CFR 1910.120(e)(3) 8-Hour Hazardous Waste Refresher Course, OSHA 29 CFR 1910.120(e)(8) 30-Hour Construction Safety and Health Training Course, OSHA 29 CFR 1926, Subparts C, E, M, P, and X 8-Hour Managers and Supervisors Course (SHSC), OSHA 29 CFR 1910.120(e)(4) Trenching/Excavation Competent Person Training Course, OSHA 29 CFR 1926 Subpart P Fall Protection Competent Person Training Course – Initial, OSHA 29 CFR 1926 Subpart M Boating Safety, Commonwealth of Pennsylvania Fish and Boat Commission Lean-Sigma Yellow Belt CQCM USACE

PROFESSIONAL AFFILIATIONS

ASCE - Member

SAME - Member

AWARDS

None



on adjacent structures, by analyzing the data and issuing direction for remedial measures as necessary. [12-21 to 9-22].

Elkhart Hydroelectric Dam, AEP, Elkhart IN. Performed a Class 3 Cost estimate for a construction project to install 300 linear feet of steel sheet pile cutoff wall. Functioned as an on and offsite technical lead for the planning and design and implementation of interim risk reduction measures at Elkhart Dam. [1-22 to 11-22].

L-611/614 2019 Missouri River Levee Repairs, U.S. Army Corps of Engineers (USACE) Omaha Rapid Disaster Infrastructure I Program, Mills County, IA. Project engineer for repair the damaged levee system on the Missouri River. The levee cross section was damaged along the 17.7 miles. Inspected the levee to identify damaged levee sections hidden by vegetation. Coordinated survey crews to collect existing condition topography and as-built conditions survey. Analyzed material properties for levee construction and submitted materials testing results to USACE. Performed calculations for material tracking and provided estimates for project schedule. Assisted site QCM and project team in interpreting the design memorandums and submitting requests for information. Deployed photo documentation protocol for collecting existing conditions photography and videography using GPS-enabled camera equipment. Conducted material and site inspections during the repair activities to meet the quality requirements for USACE. Worked closely with site supervision and project management to plan order of operations and maintain project efficiency. [9-19 to 10-20]

Project Engineer, L-550 2019 Missouri River Levee Repairs, U.S. Army Corps of Engineers (USACE) Omaha Rapid Disaster Infrastructure I Program Watson, MO. Provided support as part of the home office team to provide critical erosion velocities for the purpose of levee inlet breach closure. Supported the field engineering staff in successfully executing the contract requirement of inlet breach closure by developing a USACE HEC-RAS model for the inlet breach at the Nishnabotna River. Coordinated survey crews to collect existing condition topography and as-built conditions survey. Deployed into the field to perform final repairs after initial repairs were completed. Analyzed material properties for levee construction and submitted materials testing results to USACE. Performed calculations for material tracking and provided estimates for project schedule. Assisted site QCM and project team in interpreting the design memorandums and submitting requests for information. (2020)

Military Ocean Terminal Sunny Point (MOTSU) Hurricane Florence Response, Southport, NC. Project Engineer for the U.S. Army Corps of Engineers (USACE) request for emergency design in response to damage as the result of flooding from Hurricane Florence, the MOTSU Army Installation had been inundated and damage to infrastructure has occurred to the point of compromise for the National Defense Mission for world-wide transshipment of critical Department of Defense resources. Assessed the effects of critically damaged infrastructure including rail lines, roads, and wharves on-site and worked with USACE Omaha to develop design plans for submittal to regulatory bodies and to be issued for construction. (2018-2019)

Hatco Woodbridge Pond, Fords, Weston, NJ. Project Engineer for the model hydraulics of contributing channels into reservoir scheduled to be dredged using PCSWMM software to evaluate the anticipated inflow and outflow velocities for the purpose of remedial design and specification. Utilized model output to estimate effects of scour on pond bottom in the area directly at the inflow and outflow points, following dredging effort, and prepared stormwater management report for permit application purposes. (2017)

Existing Pump Station Evaluation, Delaware County Regional Water Quality Control Authority, PA. Project Engineer, utilized calculated peak influent flows under specific design storm condition (sanitary and surface water combined system) to EPS-1, existing system pump curves, level control logic and EPS-1 force main system curve in WESTON Storm Water Management Model to estimate the effects of 54" diameter interceptor line restoration on the pump station flows. The evaluation was performed for purpose of completing a manhole restoration effort. The 54" line would function as a bypass, to reduce the combined sewer overflow discharges to the Delaware River. (2016)

Security, Disaster, Infrastructure, Construction Contract, U.S. Army Corps of Engineers (USACE).

Assistant engineer built 3-dimensional flow simulation of an existing reservoir to evaluate its ability to be used as source of cooling water under different heat exchanger scenario. The thermal capacity of the reservoir was



simulated using the U.S. Environmental Protection Agency Environmental Fluid Dynamics Code (EFDC) model using different locations for cold water intake and hot water discharge using a diffuser. EFDC was applied to this project using the model's 3-dimensional hydrodynamic and temperature simulation capabilities. The model was used as a design tool to determine the location and orientation of the diffuser discharge.

Noll Lane, Pennsylvania Department of Environmental Protection (PA DEP), Fleetwood, PA. Provided engineering support for permitting submittal to PA DEP. Managed site activities to remove 2000 cubic yards of lead contaminated soil, installation of 1200 linear feet of stormwater channel, including setting channel inverts and site grades. Installed eight concrete headwalls. Oversaw and provided engineering support to the widening of 1700 linear feet of private driveway, and preparation of the subbase for paving activities. Coordinated with work with 3 onsite subcontractors, and local utility providers to relocate overhead utilities and poles. Interfaced with residents during site restoration activities. Operated articulated off-road dump truck during excavation and backfill activities. Scheduled material deliveries with the local quarry for stone and backfill deliveries and with environmental supply company for other site materials. (2016-2017)

Hazardous Material Removal Response at Rapid Circuit Site, Pennsylvania Department of Environmental Protection, Levittown, PA. Assistant engineer performing Level B self-contained breathing apparatus entries to categorize unknown hazardous material and performed removal over the course of 5 months. Over 120 hours of SCBA entry hours as well as over 240 Level C full face respirator hours. Performed sludge pump out of main tanks used for onsite treatment. Power washed the platting tanks in the process rooms as part of building decontamination. (2012-2013)

Crown Industries Site, Pennsylvania Department of Environmental Protection, Hawley, PA. Field lead for semiannual sampling event to monitor water quality at fourteen residences adjacent to contaminant plume. Coordinated with Pennsylvania Bureau of Laboratories with scheduling sampling event. Sampled fifteen groundwater and surface water sources as part of water quality effort. Wrote semiannual reports and resident letters. 2011-2014)

Combined Sewer Overflow (CSO) Overflow, Delaware County Regional Water Quality Control Authority (DELCORA), Modeling, PA. Assistant Engineer for the model simulation of a combined sewer system in the City of Chester using PCSWMM software. During storm periods of high flow rates, the combined sewers discharge directly to the Delaware River and its tributaries via 26 regulator outfalls. In support of a requirement of DELCORA's existing National Pollutant Discharge Elimination System (NPDES) permit to evaluate the frequency of the CSO events as well as their quantity and loads, the SWMM application is used to evaluate both the hydrologic response of the watershed and the hydraulic capacity of the system. The SWMM simulation is performed on a monthly basis and precipitation and collection system statistics and the resulting estimated CSO discharges reported to Pennsylvania Department of Environmental Protection to satisfy the NPDES permit condition. Performed design reviews and modeling scenario analysis for proposed sewer improvement projects. Completed onsite inspection of CSO structures. (2011-2017)

Former Landfill Remediation Project at Fort Indiantown Gap from Remedial Investigation through Remedial Action, Army National Guard, Annville, PA. Associate project engineer for site civil design for soil cover system at the former landfill. Evaluated temporary and permanent stormwater controls for the final cover surface. (2016)







ERIC EICHENBERG

YEARS OF EXPERIENCE Quandel: Since 1984

EDUCATION Minersville Area High School

CERTIFICATIONS 30 Hour OSHA

Crane Signaling

Rigging

ACI Concrete Field Testing Technician-Grade 1 Rough Terrain Forklift Aerial Work Platform Fall Protection Confined Spaces Scaffold Construction

CPR/First Aid

Eric has served in the construction industry for 36 years. His skills in running efficient and timely projects have made him a very valuable member of the Performance Construction team. Eric became Vice President in January of 2019. Eric's safety record has been exemplary. He has served as a carpenter, carpenter foreman, superintendent, and Vice President of Operations. He plays a major role in the field operations and manages our fleet of vehicles and equipment. He is experienced in all facets of building construction.

SELECT PROJECT EXPERIENCE

Village of Waverly WWTP Upgrades Waverly, NY \$10,900,000.00

Village of Binghamton Solid Handlings Improvements Binghamton, NY \$22,000,000.00

Earl Township Sewer Authority WWTP Upgrades New Holland, PA \$7,200,000.00

Prime Wellness Cultivation Facility South Heidelberg, PA \$8,000,000.00

Republic Services Modern Landfill LTP Ugrade York, PA \$22,411,566.00

Dept of General Services Sheppard Myers Dam Hanover, PA \$3,165,379.00

West Cocalico West Cocalico WWTP West Cocalico, PA \$7,011,937.00 **City of Blossburg** Blossburg WWTP Upgrade Blossburg, PA \$14,853,683.00

Dept of General Services Flat Rock Dam Philadelphia, PA \$4,800,000.00

Greater Pottsville Sewer Authority WWTP Upgrade & Expansion Pottsville, PA \$10,400,000.00

York County Solid Waste Authority Resource Recovery Center York, PA \$32,700,000.00

East Stroudsburg University New Science & Technology Center East Stroudsburg, PA \$22,000,000.00

Sid Tool Company Distribution Facility Jonestown, PA \$9,000,000.00

City of Pottsville FEMA Flood Upgrade Pottsville, PA \$1,310,893.00







BRIAN MICKATAVAGE

GENERAL SUPERINTENDENT

YEARS OF EXPERIENCE Quandel: Since 2003

EDUCATION Dairy Science -3 years Penn State University

CERTIFICATIONS

30 Hour OSHA Various ACI Seminars Brian has served in the construction industry since 1989 and specializes in wastewater treatment plant projects. Brian is responsible for managing our field personnel, equipment, on-site activities, and implementing and monitoring our job site safety programs. Through regular job site visits, he maintains a safe working environment, which applies to all employees as well as other members of the construction team.

SELECT PROJECT EXPERIENCE

Federal Bureau of Prisons FCI Minersville Minersville, PA \$53,000,000.00

Morrisville College Foundation, Inc

New Student Housing Facility Morrisville, NY \$15,800,000.00

Dept of General Services Pecks Pond Porter Township, PA \$811,000.00

Community Development Properties

Cayuga Green Parking Garage Ithaca, NY \$13,400,000.00

Abington Regional Wastewater Wastewater Treatment Plant Upgrade Chinchilla, PA \$20,500,000.00

City of Binghamton Solid Handlings Upgrades Binghamton, NY \$22,000,000.00

Village of Waverly Wastewater Treatment Upgrade Waverly, NY \$10,900,000.00 West Cocalico West Cocalico WWTP West Cocalico, PA \$6,876,587.00

Aqua PA Maple Hills Allentown, PA \$73,000.00

Dept of General Servcies Flat Rock Dam Philadelphia, PA \$4,800,000.00

Tower City Borough Authority

Tower City Water System Imp. Tower City, PA \$1,567,218.00

Republic Services Modern Landfill LTP York, PA \$22,411,566.00

ESPOMA ESPOMA Foundations Hegins, PA \$1,420,000.00

Borough of Frackville Spruce Street Bridge Frackville, PA \$1,897,354.00



quandel.com





LEAH EICHENBERG PROJECT MANAGER

YEARS OF EXPERIENCE Quandel: Since 2019 Leah has served in the construction industry for 4 years. Her attention to detail and insistence of high standards and quality work make her a very valuable member of the Performance Construction team. She is experienced in all facets of construction.

EDUCATION

Bachelor of Environmental Design of Architecture-Marywood University

Minersville Area High School

CERTIFICATIONS ICRA 8 Hour Training

AFFILIATIONS

Member of Safety Committee

SELECT PROJECT EXPERIENCE

Blythe Twp Solid Waste Authority BRADS Landfill St. Clair, PA \$2,200,000.00

Borough of Minersville Minersville Legion Memorial Park Minersville, PA \$138,000.00

Dept of General Services Pecks Pond Porter Township, PA \$811,000.00

Aqua PA Beech Mountain Well Station Butler Township, PA \$653,000.00

Aqua PA Country Club Gardens Allentown, PA \$123,000.00

Mahanoy City Sewer Authority Reed Bed Rehab Mahanoy City, PA \$200,000.00

Hegins-Hubley Authority Hubley Water Storage Tank Hubley Township, PA \$500,000.00 Evangelical Community Hospital Evangelical Patient Room Imp. Lewisburg, PA \$1,200,000.00

Aqua PA Maple Hills Allentown, PA \$73,000.00

Dept of General Services Flat Rock Dam Philadelphia, PA \$4,800,000.00

Tower City Borough Authority

Tower City Water System Imp. Tower City, PA \$1,567,218.00

Republic Services Modern Landfill LTP York, PA \$22,411,566.00

ESPOMA ESPOMA Foundations Hegins, PA \$1,420,000.00

Universal Forest Products UFP Foundations Gordon, PA \$310,000.00



quandel.com





ANDY STUDLACK PROJECT FOREMAN

YEARS OF EXPERIENCE 25 Years

EDUCATION Minersville Area High School

CERTIFICATIONS

10 Hour OSHA 30 Hour OSHA Scaffolding Ariel Lift HAZCOM CPR/First Aid Fall Protection Confined Spaces Rigging Andy has served in the construction industry for over 25 years. His skills in running efficient and timely projects have made him a very valuable member of the Performance Construction team. His safety record has been exemplary. He has served as a carpenter and a carpenter foreman and is experienced in all facets of building construction.

SELECT PROJECT EXPERIENCE

PA Dept of Corrections Camp Hill Prison Camp Hill, PA \$83,600.00

PPC Lubricants Corporation New Office & Distribution Facility Jonestown, PA \$1,300,000.00

Borough of Elizabethtown WWTP Upgrade Elizabethtown, PA \$12,700,000.00

Moses Taylor Hospital New Obstetrical Facility Scranton, PA \$3,000,000.00

Sid Tool Company Phase III Addition Jonestown, PA \$6,300,000.00

Community Action Commission Mount Pleasant Plaza Harrisburg, PA \$881,000.00

Wilkes University Student Union Building Wilkes-Barre, PA \$5,400,000.00 Pottsville Hospital Fourth Floor OB/GYN Reno. Pottsville, PA \$211,000.00

Schuylkill Municipal Authority Indian Run Filtration Plant Pottsville, PA \$3,500,000.00

Minersville Municipal Authority WWTP Modifications Minersville, PA \$2,100,000.00

Reading Area Water Authority Residuals Thinkening Project Reading, PA \$2,700,000.00

Wilkes-Barre School District New High School Wilkes-Barre, PA \$6,683,858,00

Cedarbrook Senior Care Skilled Nursing Addition Allentown, PA \$2,488,375.00

Penn State University Berks Campus Beaver Center Reading, PA \$2,222,357.00



quandel.com

Marquette Lake Dam Rehabilitation

Project No. DGS C-0960-0086 Phase 1

TECHNICAL SUBMITTAL

Section 2. Project Management Plan

T-2B.a Overall Project Work Plan & Schedule

MARQUETTE LAKE DAM REHABILITATION PROJECT NO. DGS C-0960-0086 PHASE 1

TECHNICAL SUBMITTAL

T-2B.a Overall Project Work Plan & Schedule

After carefully reviewing the contract documents, KC began developing a comprehensive scope and work plan. The project duration of 730 calendar days should be sufficient to complete the determined project scope. Great effort was put into developing a dewatering and diversion of water plan that would enable us to progress the project in an efficient manner and meet the project timelines.

- ✤ Sequence of Construction
 - KC plans to generally follow the sequence of construction as outlined on the E&S drawings and in the specifications.
 - KC has identified 4 major construction components of the Dam Rehabilitation project and intends to build them in organized sequential steps. The major components are:
 - Auxiliary Spillway Demolition of the existing masonry spillway structure and bridge.
 Excavation and installation of new CIP Concrete Labyrinth Spillway
 - Downstream Channel Excavation and removal of existing downstream channel and armoring. Installation of new CIP concrete retaining walls and newly riprap lined channel.
 - East & West Embankment Excavate existing embankment, subgrade prep and installation of internal drainage system (Chimney/Blanket/Toe Drains); embankment placement to flatten downstream slope.
 - 17th St Bridge Demo existing structure, control of water, install new bridge system
 - The sequence of construction is being driven by the necessary control of water and dewatering measures and staging of earthwork materials all need to be completed in very deliberate steps to progress the work effectively and efficiently. The spillway and embankment construction will run concurrently, which is required to meet the project schedule.
- Resources and Working Hours
 - The site will be staged, and access roads established in such a way to make coordination manageable and multiple activities feasible of running concurrently as needed.
 - KC expects to have the following major dedicated crews on-site
 - (2) Demo/Earthwork Crew access roads, concrete demo and removal, temporary cofferdams, subgrade excavation, material screening, fill placement and compaction, fine grading, drainage systems, and structure backfilling.
 - (2) Subcontractor Concrete Crews form, pour, strip, and finish all CIP Concrete
 - KC expects to work within normal working hours. Additional crews can be added as needed to meet the project schedule demands.
- Project Schedule
 - Attached is a preliminary project schedule (identifying all required milestones).
 - We are anticipating construction to start in early spring. It is our intent to mobilize as soon as possible after the notice to proceed and establish the construction site including necessary clearing, access roads and laydown.
 - Working restrictions (Bald Eagle, Trout) have been addressed and incorporated into our baseline schedule.

ID Task Mode	Task Name	Duration Sta	ırt l	Finish Predecessors	oct Oct Oct Oct Nov Nov Nov Dec Dec Dec Dec Jan Jan Jan Feb Feb Feb Feb F	Mai Mai Mai Mai Mai Apr Apr Apr A	r Mas Mas Mas Jun Jun Jun Jun Jun Jul (Jul i Jul i	ul Aug Aug Aug Aug Aug Sep Sep Sep Sep	Oct Oct Oct Oct Nov Nov Nov Nov Dec Dec	ed Ded Jan Jan Jan Jan Feb Feb Feb Feb	Mai Mai Mai Mai Mai Apr Apr Apr Apr Mai Mai Mai Mai	1ai Jun Jun Jun Jun Jul Jul Jul Jul Aug Aug Aug	Aug Aug Sep Sep Sep Sep Oct Oct Oct	Oct Nov Nov Nov Nov No	√ Dec Dec Dec Jan Jan Jan Jan
1 ->	Pre-Construction	109 days Tu	e 10/1/24	Fri 2/28/25		eson neos no eson neos no eson neos no eson neos no eson neos no I	בשוראבאי ורבאירורבא וורבאי ורבאי		nen regnen re	TEAN I	באין הבאירובאיר הבאירובאין ורבאיר הבאירובאירים אין אינאיין אינאיין אינאיין אינאיין אינאיין אינאיין אינאיין אינא	איז	997599759975997599759975997599759975997	NIVE2010F2011F2010F2010F2010F2010F	2011/22011/22011/22011/22011/22011/22011/22011/2
2 ->	Submit RFP	1 day Tu	e 10/8/24	Fue 10/8/24											
3 🖈	Notice of Award (90-day Proposal Period)	1 day Mo	on 1/6/25	Mon 1/6/25 2											
4 🖈	**Trout In-Water Restriction**	66 davs Tu	e 10/1/24	Fue 12/31/24											
5	**Rald Fade Work Pestriction**	66 days Su	n 12/1/24	ri 2/28/25	_										
6	Marguette Lake Dam Behabilitation (720 Day Duration)	E49 dovr. Tu	01/21/25	Sup 3/39/37	_										
7	Desired Advis	549 days 10	e 1/21/25	Sun 2/28/27	_										
	Project Admin	51 days Tu	e 1/21/25	lue 4/1/25											
8 ->	Notice to Proceed	1 day Tu	e 1/21/25	Fue 1/21/25 3FS+10 days											
9 🛼	Initial Job Conference	1 day Tu	e 2/18/25	Tue 2/18/25 3FS+30 days	<u>`</u>	7									
10 🔜	Material Procurement/Submittals	30 days We	ed 2/19/25	Fue 4/1/25 9											
11 🔜	Preliminary Construction - Job Setup	20 days Wo	ed 3/5/25	Fue 4/1/25		·1									
12 📑	Mobilization - *Milestone*	5 days We	ed 3/5/25	Tue 3/11/25 9FS+10 days		1									
13 📑	Survey Layout	3 days We	ed 3/12/25	Fri 3/14/25 12											
14 🛋	Preliminary E&S Controls *Milestone*	5 days We	ed 3/12/25	Fue 3/18/25 12	_	_									
15 🛋	Install Access Road & Laydown/Staging Areas	5 days We	ed 3/19/25	Tue 3/25/25 14	_	_									
16 🛋	Clearing & Grubbing *Milestone*	5 days We	ed 3/26/25	Tue 4/1/25 15		⊢									
17 🔜	Auxiliary Spillway & Channel Improvements	410 days Th	u 3/6/25	Wed 9/30/26											
18 🖦	Lake Lowering - In Coordination with Agency	18 days Th	u 3/6/25 I	Mon 3/31/25 12FS-4 days		} _									
19 🛋	Install Temporary Construction Access & Crossings	5 days Th	u 3/20/25	Wed 3/26/25 18FS-8 days	-										
20 🛋	Install Diversion of Water Features - Vegetated Filter Strip &	2 days Tu	e 4/1/25	Wed 4/2/25 19,18	_	+									
	Rock Filters														
21 🔜	Demolition of Existing Spillway Bridge, Piers & Chute *Milestone*	10 days Tu	e 4/1/25 I	Mon 4/14/25 18		*									
22 🖏	Bulk Excavation and Subgrade Prep for New Spillway Incl Drainage System*Milestone*	40 days Tu	e 4/15/25 I	Mon 6/9/25 21	-	*									
23 🛋	Stage 1 Auxiliary Spillway Construction	120 days Tu	e 5/13/25	Mon 10/27/25	_		[P]								
24 🛋	Install Stage 1 Control of Water *Milestone*	5 days Tu	e 5/13/25	Mon 5/19/25 22FS-20 days	_		l →								
25 🛋	Demo Remaining East Aux Spillway Features	5 days Tu	e 5/20/25	Mon 5/26/25 24	_		1								
26 🖡	Spillway Approach& Foundation - Excavation & Prep, Underdrain Installation *Milestone*	45 days Tu	e 5/27/25 I	Mon 7/28/25 25	-										
27 🛋	Rock Anchors	15 days Tu	e 7/1/25	Mon 7/21/25 26SS+25 days	_										
28 🛋	CIP Concrete - Stage 1 Spillway Slab & Training Wall	75 days Tu	e 7/8/25	Mon 10/20/25 26SS+30 days	_)						
29	Complete Wall Drainage System and Backfill New Left Training Wall *Milstone*	20 days Tu	e 9/30/25 I	Mon 10/27/25 28FS-15 days	-			\$							
30 🖈	**Trout In-Water Restriction**	65 days We	ed 10/1/25	Tue 12/30/25	_			-							
31 🖈	**Bale Eagle Work Restriction**	66 days Mo	on 12/1/25	Sat 2/28/26	_						η				
32 🛋	Stage 2 Auxiliary Spillway Construction	153 days Mo	on 3/2/26	Wed 9/30/26	-										
33 🖏	Remove Stage 1 and Install Stage 2 Control of Water *Milestone*	10 days Mo	on 3/2/26 I	Fri 3/13/26 31,76	-										
34 🛋	Demo Remaining Aux Spillway Features	5 days Mo	on 3/16/26	Fri 3/20/26 33											
35	Spillway Foundation Excavation & Prep, Underdrain Installation	45 days Mo	on 3/23/26 I	Fri 5/22/26 34	-						*				
36 📑	Rock Anchors	15 days Mo	on 4/27/26	Fri 5/15/26 35SS+25 days							│				
37 🔜	CIP Concrete - Stage 2 Spillway Slab & Training Wall	75 days Mo	on 5/4/26	Fri 8/14/26 3555+30 days											
38	Complete Wall Drainage System and Backfill New Right Training Wall *Milestone*	20 days Mo	on 8/17/26 I	Fri 9/11/26 37								-			
39 🛋	Topsoil and stabilize disturbed areas	5 days Th	u 9/24/26	Wed 9/30/26 38,42									₩		
40 -	Stage 3 Auxiliary Spillway Construction (Weir)	33 days Mo	on 8/17/26	Wed 9/30/26											
41	Remove Stage 2 Control of Water and Install Weir Wall Controls	3 days Mo	on 8/17/26	Wed 8/19/26 37								1			
42	CIP Concrete - Weir Walls	25 days Th	u 8/20/26	Wed 9/23/26 41											
Project: Marqu Date: Mon 10/	vette Lake Dam P Task Milestone 77/24 Split Summary	*	Project Inactive	Summary I	Inactive Milestone Manual Task Inactive Summary Duration-only	Manual Summary Rollup	Start-only C Finish-only 3	External Tasks External Milestone	Deadline + Progress	Manual Progress					
	1						Page 1								



ID Task Mode	Task Name	Duration	Start	Finish	Predecessors	2ct Oct Oct Not Not Not Not Not Not Not Not Ded Ded Ded Ded Ian Jan Jan Jan Jan Jan Jan Jan Jan Jan J
43	Final Grading of East & West Approach Channels *Milestone*	5 days	Thu 9/24/26	Wed 9/30/26	42	
44 🛋	Downstream Channel Construction	112 days	Mon 3/16/26	Tue 8/18/26		
45	Bulk Excavation and Rock Removal	30 days	Mon 3/16/26	Fri 4/24/26	33	
46 🛋	Subgrade Prep (Retaining Walls & RipRap Slopes)	10 days	Mon 4/27/26	Fri 5/8/26	45	
47 -	Channel CIP Conc Retaining Walls	30 days	Mon 5/11/26	Fri 6/19/26	46	
48 ➡	Install RipRap Scour Protection *Milestone*	40 days	Mon 6/22/26	Fri 8/14/26	47	
49 -	Remove Upstream/Downstrea Cofferdams	2 days	Mon 8/17/26	Tue 8/18/26	48	
50 -	Additional Downstream Channel Construction (BB2)	52 days	Mon 7/13/26	Tue 9/22/26		
51	Clearing and Grubbing	5 days	Mon 7/13/26	Fri 7/17/26	47FS+15 days	
52 →	Bulk Excavation	15 days	Mon 7/20/26	Fri 8/7/26	51	
53 -	Subgrade Prep	5 days	Mon 8/10/26	Fri 8/14/26	52	
54 ➡	Install RipRap Scour Protection *Milestone*	25 days	Mon 8/17/26	Fri 9/18/26	53	
55 =	Remove Temporary Cofferdams	2 days	Mon 9/21/26	Tue 9/22/26	54	
56 -	17th Street Bridge (BB3)	56 days	Mon 7/13/26	Mon 9/28/26		
57 🖈	Clearing and Grubbing	3 davs	Mon 7/13/26	Wed 7/15/26		
58 ->	F&S Controls	2 days	Thu 7/16/26	Fri 7/17/26	57	
59	Control of Water - Flume Pipe	3 days	Mon 7/20/26	Wed 7/22/26	58	
60	Demolition of Existing Bridge	5 days	Thu 7/23/26	Wed 7/29/26	50	
61	Pulk Execution 9: Subgrade Prop	15 days	Thu 7/20/26	Wod 8/10/26	60	
62	Buik Excavation & Subgrade Frep	10 days	Thu 8/20/20	Wed 0/2/20	60	
		10 days	Thu 8/20/20	wed 9/2/20	61	
63	Backhil New Structure	8 days	Thu 9/3/26	Mon 9/14/26	62	
64 →	RipRap Amoring R-6	/ days	Tue 9/15/26	Wed 9/23/26	63	
65 →	Asphalt Paving Restoration *Milestone*	2 days	Thu 9/24/26	Fri 9/25/26	64	
66	Bridge Barrier (Guiderail)	1 day	Mon 9/28/26	Mon 9/28/26	65	
67	Downstream East Embankment Improvements	126 days	Wed 4/2/25	Wed 9/24/25		
68 -	Install E&S Controls	5 days	Wed 4/2/25	Tue 4/8/25	16	
69 🤜	Demo Pavement, Utility Poles, Guiderail on Embankment Cres	at 2 days	Wed 4/9/25	Thu 4/10/25	68	
70 -	Fast Embankment Tonsoil Strin, Bulk Evravation, Salvage Rock	15 days	Wed 4/9/25	Tue 4/29/25	68	
	Slope Protection	10 0075	1100 11 57 25	100 4725725		
71 -	Excavate/Subgrade Internal Drain	5 days	Wed 4/30/25	Tue 5/6/25	70	
72 -	Construct Internal Drain (Incl Pipe, Drainfill, Earthfill)	80 days	Wed 5/7/25	Tue 8/26/25	71	
	Milestone					
73 🖈	Install Upstream RipRap Protection *Milestone*	5 days	Thu 9/11/25	Wed 9/17/25	72	↓
74	Finish Grading & Topsoil Respread	5 days	Thu 9/18/25	Wed 9/24/25	73	
75 🖈	**Trout In-Water Restriction**	65 days	Wed 10/1/25	Tue 12/30/25		
76 🖈	**Bale Eagle Work Restriction**	66 days	Mon 12/1/25	Sat 2/28/26		
77 -	Downstream West Embankment Improvements	110 days	Mon 3/30/26	Fri 8/28/26		+
78	West Embankment Topsoil Strip, Bulk Excavation, Salvage Roc	k 15 days	Mon 3/30/26	Fri 4/17/26	76FS+20 days	
	Slope Protection					
79 📑	Excavate/Subgrade Internal Drain	5 days	Mon 4/20/26	Fri 4/24/26	78	
80	Construct Internal Drain (Incl Pipe, Drainfill, Earthfill)	80 days	Mon 4/27/26	Fri 8/14/26	79	
	· WIIIESTONE*					
81 ➡	Install Upstream RipRap Protection *Milestone*	5 days	Mon 8/17/26	Fri 8/21/26	80	
82	Finish Grading & Topsoil Respread	5 days	Mon 8/24/26	Fri 8/28/26	81	
83 🖈	**Trout In-Water Restriction**	65 days	Thu 10/1/26	Wed 12/30/26		
84 🖈	**Bald Eagle Work Restriction**	65 days	Tue 12/1/26	Sun 2/28/27		
85	Site Restoration	28 days	Mon 8/31/26	Wed 10/7/26		
86	Topsoil, Seed Stabilize Remaining Site Areas	5 days	Mon 8/31/26	Fri 9/4/26	82	
Project: Marqu Date: Mon 10/	vette Lake Dam P Task Milestone 7/24 Split Summary	*	Proje	ect Summary tive Task	I	Inactive Milestone 🗄 Manual Task I Manual Summary Rollup Start-only E External Tasks Deadline 🖶 Manual Progress
						Page 2



ID	Task Mode	Task Name	Duration	Start	Finish	Predecessors	be do
87		Restore Access Roads & Gravel Parking Areas, and Other Misc Improvements	5 days	Thu 10/1/26	Wed 10/7/26	82,43	
88		Project Closeout	14 days	Thu 10/8/26	Tue 10/27/26		
89) =	Punch List Work	10 days	Thu 10/8/26	Wed 10/21/26	87	
90) =,	O&M Manuals & Training	1 day	Thu 10/22/26	Thu 10/22/26	89	
91	-	Remove Remaining E&S Controls and Complete Final Restoration *Milestone*	1 2 days	Thu 10/22/26	Fri 10/23/26	89,87	
92		Demobilize Site	2 days	Mon 10/26/26	Tue 10/27/26	91	
93	*	***Final Completion***	1 day	Thu 1/21/27	Thu 1/21/27	87	
94							
95	*?						
96	i 📌						

Project: Marquette Lake Dam P Date: Mon 10/7/24	Task Split	Milestone Summary	*	Project Summary Inactive Task	1	Inactive Milestone Inactive Summary	۰ ۱	Manual Task Duration-only	Manual Summary Rol Manual Summary	llup I	Start-only Finish-only	с э	External Tasks External Milestone	\$ Deadline Progress	+	Manual Progress	
												Page 3					



Marquette Lake Dam Rehabilitation

Project No. DGS C-0960-0086 Phase 1

TECHNICAL SUBMITTAL

Section 2. Project Management Plan

T-2B.b Critical Items Work Plan

MARQUETTE LAKE DAM REHABILITATION PROJECT NO. DGS C-0960-0086 PHASE 1

TECHNICAL SUBMITTAL

T-2B.b Critical Items Work Plan

• CONTROL/DIVERSION OF WATER

- Self-Performed with Support from GEI Consultants
- <u>General Lake Drawdown and Diversion Requirements</u> The lake is currently at normal pool but will be lowered for construction operations.
 - 1. The base streamflow will be managed utilizing the existing outlet works during construction of the new spillway.
 - 2. Initial lowering will be conducted in coordination with Client Agency personnel. Maximum drawdown is 1-foot per day, so this may take a few weeks depending on weather. Access for agency personnel will be provided to perform fish salvage operations as desired.
 - 3. The capacity of the existing outlet conduit is limited but it is understood that the level of protection for this project shall represent the peak reservoir stage for the 100-year flood event for the embankment and 10-year flood event for work zones.
 - 4. It is the contractor's responsibility to evaluate risk and progress the project in a manner that mitigates those risk levels. The contractor shall protect the existing embankment/abutment soils and work zone during water control activities and will be responsible for all damage caused by flooding events or system failures including dewatering and cleaning of affected area.
 - 5. The contractor shall further prepare a contingency plan for non-performing diversion works or the need for additional capacity.
 - 6. A surveillance plan will be developed to monitor storm and lake conditions during significant events including notification to state agencies of rising pool elevations and subsequent hourly updates.
- <u>Spillway Construction</u> It is KC's intent to generally follow the sequence of construction provided on the Construction Sequence Plan (C-3)
 - 1. Stage 1 Construction
 - i. After installing the E&S controls for this site, KC will begin establishing access roads to initial work areas. Demolition of the existing structures will commence as detailed in the suggested sequence including excavation of soils and weathered rock.
 - ii. As mentioned above, base flows will be passed through the Principal Spillway Intake and Low-Level Outlet conduit.
 - iii. KC intends to install a sandbag or bin block cofferdam (with geomembrane liner) which will be approx. 500 LF and isolate the left half of the Auxiliary Spillway, tying into the upstream and downstream side of the West Embankment. Material can be generated from the channel widening. Minimum cofferdam elevation will be calculated by our control of water engineer representing the computed peak reservoir stage during a 10-yr flood including 1-foot of freeboard. It is assumed bypass channel will be excavated to weathered bedrock. If bedrock is not encountered, the channel will be lined to prevent erosion.

- iv. Additionally, riprap will be installed on the exposed dam embankment slopes up to the computed peak reservoir stage during a 100-yr flood. Riprap will be sized by our engineer based on anticipated flow velocity.
- v. See Figure 1. for conceptual plan.



- vi. Rock Filter Outlet Prior to any earth disturbance within this work zone, rock filter outlets will be installed and vegetated filter strips planted.
- vii. Channel Crossing A temporary channel/stream crossing will be installed to provide construction traffic access from the staging areas to our work zones.
 - 1. The temp crossings will remain in place for the duration of the project to service construction vehicle access. The crossing will be designed to meet and pass base/low flow requirements and be capable of overtopping during major storm events.
- 2. Stage 2 Construction
 - i. Upon completion of Stage 1 construction (including backfill of new abutment training walls and other required improvements to protect embankment), Stage 1 cofferdam will be transferred over to establish the new work zone for the right side of the spillway.
 - ii. Bypass flow will now travel over the newly completed spillway slabs and the East embankment will be protected by the new training wall. Riprap embankment

armoring will remain on the West embankment to protect from a 100-yr event until the right training wall is established and backfilled.

- iii. Any remaining demolition will be completed, and construction of right side of the auxiliary spillway structure will be completed.
- iv. See Figure 2 for conceptual plan



- 3. Stage 3 Construction (Weir Walls & Channel Improvements)
 - i. Upon completion and backfill of Stage 2 construction, the Stage 2 cofferdam will be removed.
 - ii. Minimal cofferdams will be temporarily installed on the spillway slabs to protect weir wall construction as needed. The final weir cycle will be formed and poured within a weather window (to the best of our ability) to limit potential risk of damage to work.
 - iii. Similarly to the weir walls, the downstream channel retaining walls will be protected by temporary sandbag cofferdams as needed. These walls will generally be founded on rock, so the risk of erosion is minimal.
 - iv. After completion of the labyrinth weir walls and channel retaining walls, final riprap scour protection will be installed downstream.

• DEWATERING

- Self-Performed with Design Support from GEI Consultants
- Based on the data presented in the geotechnical report, it is difficult to anticipate how much water may be encountered in the proposed deep excavations for the new spillway and toe drain collection systems because the reservoir was at normal pool at the time of the observations. As stated, it should be anticipated that water levels will fluctuate in the hydrostatic water table depending on variations in the reservoir level, precipitation events, surface runoff, and performance of diversion structures.
 - 1. Surface Water
 - i. Excavations and interim embankment grading will utilize best practices to divert water away from work zones (trenches, diversion berms, etc.) as well as sealing disturbed surfaces daily and temporary stabilization (seeding/mulch) applied until permanent grades are achieved.
 - 2. Excavation Dewatering
 - i. Typically, KC will excavate some investigative test pits to identify and delineate potential areas of concern to assist with the development of our dewatering plan.
 - ii. It is anticipated that the deep excavations at the toe of embankments and spillway subgrade will be serviced by local sumps as needed. All pumped water will pass through BMPS (temporary sediment trap, pump filter bags, etc.) to eliminate sediment from moving downstream.
 - iii. If conditions beyond those anticipated are encountered, we will consult with our dewatering consultant to modify our plan and implement appropriate control measures.
 - iv. The new toe drain collection systems will be constructed from the low point discharge location and work upslope which will also serve as a dewatering facility as installation progresses.
 - 3. Cofferdam Dewatering
 - i. To address leaks through cofferdams, KC will install dewatering facilities between our cofferdams and excavation zones to manage the anticipated seepage.
 - 1. Dewatering facilities may be a combination of interceptor trenches with filter material and local sumps.
 - 2. For overtopping, submersible pumps will be used to dewater the work zone.
 - 4. System Operation and Maintenance
 - i. KC will establish a set of procedures to test dewatering systems upon installation, operate and maintain systems, repair, and perform scheduled maintenance on equipment and facilities, setup contingency plans (power, fuel), and conduct daily observations of system.
 - 5. System Removal
 - i. All dewatering systems will be removed after operations are discontinued. Any damage caused by the systems will be repaired and restored following removal.
 - ii. As-built locations and depths of any decommissioned dewatering elements left in place will be recorded and any interaction with permanent drainage improvements will be detailed.

• CAST-IN-PLACE CONCRETE

- Performance Construction Company
- Performance Construction Company specializes in structural cast in place concrete installation. We have successfully completed many dam and treatment plant projects that require watertight concrete construction.
- While developing a strategy of approach for the construction of this project, the team at Performance Construction Company pulled from our years of experience on similar projects. This experience will give us a first-hand perspective on some of the processes that we found to be successful, as well as insight into how to avoid possible setbacks.
- Performance Construction has thoroughly reviewed the specifications in detail Section 03300 Cast In Place Concrete. We understand the requirements and will provide all project submittals per Section 1.5 A special focus will be placed per section 1.7 Quality Requirements, All Testing, Qualifications for Personnel.
- The requirements for the vinyl water stop will also be met. We will provide the names of our employees who are trained to properly install and field weld butt splices. All intersecting changes of direction will be fabricated and provided by the manufacturer.
- Performance Construction Company has extensive experience in dam construction, and we
 understand the importance of meeting and exceeding all specified requirements and tolerances. Our
 approach to performing the construction of the spillway, along with the downstream training walls
 will be as follows.
- We will begin by placing the right-side slabs including associated turndown walls in a checkerboard pattern. The first pour will be Slab F4. The next pour will be Slab F3 and E4, followed by D4 and ES. At this point we will start an additional crew to install the first section of wall on the F4 slab. The walls will be built in two lifts as shown on the documents. We will continue to pour two sections of slabs at a time with the spillway walls sections following closely behind. Once complete we will install the weir walls and finish with the wing walls. In the Spring of 2026, we will construct the left side of the dam in the same manner. We anticipate the construction of one half of the spillway in three months.

• DRAINAGE FILTER & SEEPAGE COLLECTION SYSTEM AND ZONED EMBANKMENT CONSTRUCTION

✤ Self-Performed

- As much as possible we plan to maximize production by minimizing material handling. We expect that the earthen material required for embankment construction will be available on-site (excavated from the existing embankments and will be suitable for the zoned backfill (as indicated in Geotech report) with some anticipated drying and screening.
- As presented in our construction schedule, it is our intent to follow the proposed construction sequence with some minor alterations to remedy control of water and dewatering issues.
- Zoned Earthfill Materials during subgrade excavation operations, every effort will be made to identify and class earth materials so they can be stockpiled and separated appropriately. It is important that we determine sufficient quantities are available to be used for embankment fill zones.
 - Placement of embankment will strictly follow specification guidelines as they relate to lift thicknesses, placement around structures, compaction, and moisture content.
 - Collection System The toe drain subgrade area will be excavated beginning at the low point and progressing upslope. The chimney and blanket drain will then be installed following specification guidelines
 - All subgrade to up against aggregate fill shall be rolled smooth and not be scarified.

- The blanket and chimney drain construction will be installed in uniform horizontal lifts concurrently with embankment fill to support compaction of the varying fill zones.
- Control of moisture content and compaction requirements associated to earthfill, coarse aggregates and fine aggregates (sand) shall be executed in strict compliance with the specifications.
- It is understood that moisture content and compaction of all zoned materials is critical to the performance of the embankment and collection systems related to dam construction.
- As mentioned earlier, KC has worked on a wide variety of dam embankment scenarios and multiple variations drainage filter/seepage collection systems designed by several different engineers. This is a system we have installed many times before. We understand the design goal and the expectations of the governing agency.

• EXCAVATED MATERIAL SCREENING

✤ Self-Performed

- As noted above, we plan to maximize production by minimizing material handling. We expect that the earthen material required for embankment construction will be available on-site (excavated from the existing embankments and spillway channel and will be suitable for the zoned backfill (as indicated in Geotech report) with some anticipated drying and screening.
 - KC owns screening equipment but also supplements with specialty equipment from rental companies as needed. Depending on timing and volume of material requiring screening, KC may elect to bring in a subcontractor to support this effort.
 - To meet the earthfill specifications in section 31 23 23, oversized screening of soils will most likely be required.
 - Soil Screening
 - KC will mobilize the appropriately sized portable screening plant to process onsite soils to meet required gradations.
 - Excavated materials that have been classified and stockpiled for reuse in the different zones of embankment fill will be processed by a dedicated screening crew.
 - Processed materials will be separated into appropriate stockpiles for future use and sealed to maintain desired moisture content. If moisture conditioning is required, the soils processing crew will conduct those activities (applying water to stockpile lifts for dry material or spreading and disking lifts to dry wet material).

• PIEZOMETER INSTALLATION

Eichelbergers, Inc.

- The site currently includes several existing piezometers as part of the dam instrumentation system used for monitoring. Proposed construction scope will impact these locations. KC will protect and raise piezometers accordingly based on the final grades.
- New piezometers will be installed by Eichelbergers, Inc. who is a long-standing partner of KC and has worked on many of our dam rehabilitation projects. They are also a on a short list of drillers used by dam design professionals for investigative work, so they are well versed on drilling in dam environments.
- Piezometers exist on just about every dam project KC works on, so we are extremely familiar with this type of instrumentation device. There are multiple ways to protect them, but we have found that dropping a concrete MH section around the riser acts as an excellent deterrent.

- Additionally, walk behind compaction equipment will be used in the immediate vicinity so as not to disturb them.
- Piezometer pipe will be extended in kind.

Marquette Lake Dam Rehabilitation

Project No. DGS C-0960-0086 Phase 1

TECHNICAL SUBMITTAL

Section 2. Project Management Plan

T-2C Safety Plan

MARQUETTE LAKE DAM REHABILITATION PROJECT NO. DGS C-0960-0086 PHASE 1

TECHNICAL SUBMITTAL

T-2C Safety Plan

All employees are ultimately responsible for their own safety and share the responsibility for the safety of their co-workers, our client's employees, and their property and equipment. All employees must comply with: KC Construction Company Health and Safety Program; all Federal and State requirements; craft specific safety practices; established Safety, Health and Environmental Policies and Procedures of our clients; and posted safety instructions such as posted signs, barricades, barriers, and permit instructions.

All new employees are given physicals and are drug tested in accordance with our Drug and Alcohol Abuse Policy/Program. Furthermore, all employees are subject to mandatory post-accident drug and alcohol screening.

All Supervisors are required to have OSHA 30 training and CPR/First Aid Training. Other OSHA training such as OSHA-10, Fall Protection, Forklift, Signal Person, Confined Space, Competent Person, etc... are given to all employees as required. All training is performed by Med-Tex Services of Philadelphia, PA.

Upon award of the contract, a Site-Specific Health and Safety Plan (SSHASP) will be prepared and submitted to include, at a minimum, the following items:

- **The scope of work** This provides information on the work KC Construction has been contracted for and will provide the guide for writing the specific approaches to safety on the job.
- Contacts will be listed with e-mail and phone numbers to contact responsible site personnel.
- The plan will, at a minimum, include general safety topics such as:

General Safety Rules	Safe Operation of Motor Vehicles
Personal Protective Equipment	Fire Prevention and Protection
Emergency Procedures	Incident Reporting and Investigation
STOP Work Program	Hand and Power Tool Safety
Ladders	Scaffolds
Asbestos Awareness	Silica Awareness

- The plan will include, at a minimum, the following **topics specific** to the work to be performed:
 - o Fall Protection/Prevention
 - Confined Space Entry
 - Excavation Safety
 - o Crane and Mobile Equipment Safety
 - o Rigging
 - Working over or near water

- All employees assigned to the job will be trained, qualified and/or certified for the task they will perform. Complete course descriptions including hours and training outlines, certifications and training sign-in sheets will be included. Such training will be:
 - OSHA 10-hour Construction Outreach (general employees)
 - OSHA 30-hour Construction Outreach (forepersons and higher)
 - Fall protection (including competent person)
 - Excavation Safety (including competent person)
 - Confined Space Entry/Rescue
 - Asbestos and Silica Awareness.
- Safety meetings will be conducted and documented at least weekly or per contract.
- Job Hazard Analysis will be used to assure the hazards have been identified and the safest possible way to perform the task is being utilized
- **Subcontractor management** will be addressed, and subcontractor safety plans reviewed to assure the safety of the specific tasks they will be performing.

This outline is not totally inclusive of all aspects of the SSHASP. KC Construction has acquired the services of a professional safety consultant to write the plan, train the employees and assure compliance with all Federal (OSHA), State, local and client rules and regulations.

Performance Construction: Standard Safety Policy

Performance Construction Company has a written Safety Program Manual (copy available upon request) that is created and updated yearly by Quandel Enterprises Inc. (our parent company). Performance's operations employees are required to review the manual and openly discuss in a number of training sessions. When complete, all employees are required to sign an acknowledgment that they have, in fact, read the manual and will adhere to the required policies and procedures.

Performance has mandatory annual safety training workshops led by Greg Quandel, President & CEO. Employees are also required to have updated OSHA certificates, which require recertification every five years. Everyone on Performance's staff is responsible for project safety, but the Project Superintendent is the main person responsible for safety on site.

"Toolbox Meetings" are held weekly by the Site Superintendent and the trade foremen. During the meeting, the Quandel/Performance "Toolbox" newsletter is discussed, project safety is reviewed, concerns are noted, suggestions are made and next steps are laid out.

Safety Training Programs / Certifications

Performance Construction employs Union Labor for all self-performed work. The Unions provide substantial training opportunities through various training facilities throughout the Commonwealth of Pennsylvania. Performance also provides project specific training as required through Union and/or Independent training facilities/companies such as SMRS.

Performance Committee

Performance has a Safety Committee that meets monthly and Quandel Enterprises has a Safety Committee that also meets monthly to review project safety. Topics discussed include: safety training, equipment, jobsite
inspections, accidents, incidents and near misses. The committee is comprised of members from each branch of the organization, including Greg Quandel and SMRS as representatives from Performance.

Procedure

Performance has a firm commitment to provide and maintain a safe working environment on all of our projects. It is the policy of our management that all practical efforts are made to provide a safe and healthy workplace, and to do everything reasonable to protect jobsite personnel, owner's personnel, the public and property from accident or harm.

Accidents interfere with the orderly progress of the work and are indications of an inefficient operation. We expect everyone on the project to perform their job in a safe manner and in accordance with the procedures outlined in our safety program.

To be effective, the safety program requires full effort and attention from all members of the project team. Listed below are the major responsibilities assigned to each member of the team:

The Project Manager:

- Has full responsibility for Performance's safety program and the results that are achieved.
- Assigns authority for the implementation of the safety program.
- Holds supervisory personnel accountable for a high level of performance.
- Measures results of performance.
- Authorizes the budget and expenditures for safety.
- Approves safety policies.
- Participates in the safety program to show commitment.
- Sets the proper example in safety for all employees.
- Regularly discusses and reviews safety with the supervisory staff to emphasize and reinforce the importance of safety.

The Superintendent and Foremen:

- Regularly inspect the work areas and equipment for compliance with work rules and safety standards.
- Instruct workers on the (1) hazards of the job, (2) how to operate tools and equipment, (3) how to work safely and according to operating procedures, and (4) on applicable safety and health regulations.
- Take responsibility for maintaining a safe and healthy workplace, proper housekeeping, proper ventilation and illumination, safe equipment operation and the use of personal protective equipment as required by each job.
- Ensures that all injuries are promptly and properly treated.
- Analyze all processes, operations and facilities for hazards and eliminate the hazards or provide for proper protection.
- o Investigate the causes of all accidents and injuries and complete reports as required.
- Conduct weekly toolbox safety meetings and new worker orientations.
- Make all trade contractors aware the safety violations will result in warnings, citations and possible replacement of workers or the trade contractor.
- Compliment safe workers in the presence of co-workers: counsel unsafe workers when no one else is present.
- Cet a proper example for safety by complying with the safety program and displaying a positive attitude toward safety.

- Arrange for professional medical facilities and first aid. (All supervisory personnel have First Aid and CPR training.)
- Stay informed in the latest safety standards.

Workers:

- Perform only tasks and jobs that they have been trained to do. Use only machinery, equipment or tools that they have been trained to operate.
- Work in accordance with safe practices and comply the safety rules.
- Use required personal protective equipment.
- Report unsafe conditions or practices to supervisory personnel.
- Make safety suggestions.
- Cooperate during the investigation of any accidents that occur.
- Take an active part and participate in safety meeting.
- Performance Construction Services is proud of its safety record. Reflective of Performance's commitment to its successful safety program, our OSHA Experience Modification Factor is .771.

Written Safety Program

- All of our project managers, field managers and on-site team members are required to follow Performance's Safety Program (a voluminous three-ring binder)
- We ensure that all our programs coordinate with those required by Pennsylvania Department of General Services, the Department of Conservation & Natural Resources, and OSHA
- Our on-site staff members are required to have 10-hour OSHA certification; however many of our superintendents and field managers have 30-hour certifications
- The project superintendent or field manager serves as the daily on-site safety officer Brian Mickatavage, Senior Superintendent, will visit the site on a regular basis to focus on safety, quality and
- schedule adherence
- We have created a handbook of site-specific safety issues broken down by construction division that our team will utilize on site.

Safety Walk-Through's

In order to ensure that all parties involved with the project understand the safety program, we implement the following strategies:

- Daily safety walk-thru's of the project site and results recorded
- Weekly site safety meetings
- Hazard Analysis form is required for each task
- Monthly Audit

Emergency Response Area

We will work with the local officials to identify an Emergency Response Area. If there is a safety incident on site, all officials, including those on site, will meet at a pre-determined location so actions can be taken swiftly and effectively.

Worker Management System

- Every person that works on a project is assigned a Hard Hat Tag which includes a unique number and corresponding color
- We copy each subcontractor's driver's license for use with this system.
- If at any time anyone is noticed out of an area where they should be, all we need is the color and number of their Hard Hat Tag, and we can identify the person and take appropriate action.
- If required, we will implement and manage employee background checks to adhere to your policy.

Incident and Accident-Avoidance Program

Performance Construction utilizes the "Near Miss" program to recognize potential incidents that occur on the site. The near miss is immediately addressed and logged as a potential incident. These are then reviewed on a weekly basis with the project team to ensure like incidents are avoided. Disciplinary action process is specified in our Safety Manual for instances, reoccurring instances, and life safety instances.

In addition, all employees are subject to initial "substance abuse testing" and in accordance with our safety manual and employment policies "substance abuse testing' could occur on a random, incident, and as defined in our policy. Subjects testing positive are immediately removed from the job site.

On this project, to ensure a safe project environment, our Project Superintendent will be on site full-time during construction to ensure that all DGS, OSHA and local safety regulations are met. Our goal is to maintain a clean, quiet site with no safety issues or surprises for site visitors during construction.

Marquette Lake Dam Rehabilitation

Project No. DGS C-0960-0086 Phase 1

TECHNICAL SUBMITTAL

Section 2. Project Management Plan

T-2D Quality Control Plan

MARQUETTE LAKE DAM REHABILITATION PROJECT NO. DGS C-0960-0086 PHASE 1

TECHNICAL SUBMITTAL

T-2D Quality Control Plan

KC Construction Company utilizes a few key components for maintaining project tracking and reporting. The foremost software currently used is ComputerEase, Heavy Job, Microsoft Project, Microsoft Excel, and E-Builder.

• <u>E-Builder</u>

While KC has its own forms and processes established as shown below, the Departments implementation of E-Builder over the past few years has completely evolved how these projects are managed and controlled. E-Builder EnterpriseTM is a cloud-based, construction Program Management Information Solution (PMIS) for capital projects that delivers trusted insight into performance across the entire project lifecycle, reducing risk and improving performance. All communications and documentation are transmitted through this system.

KC was one of the first contractors to use the system and has now completed several projects utilizing this technology. Not only do we now feel as though we are expert users of the program, but we have also embraced it and believe it has a positive impact on job performance for both the owner and the contractor.

• <u>SUBMITTALS</u>

The first step in a successful project setup is a complete and accurate submittal log. KC Construction develops this log based upon the contract documents and drawings. This log contains item numbers for each submittal item along with transmittal numbers for ease of tracking. Other key information contain within the log is date submitted to KC Construction from Subcontractors/Vendors, date submitted to Engineer, date returned from Engineer, and date returned to Subcontractor/Vendor along with review status. This log and each submittal is uploaded to our FTP site for the Engineer and all subcontractors to access. Our submittal log also contains the necessary material certifications required for the project so a detailed tracking effort can be obtained.

Once the log has been developed, we create a submittal schedule which is incorporated within the overall project schedule. This information allows the Project Team to plan accordingly for when they can expect submittals from KC Construction for review and when an anticipated review date is required by the engineer. With having this information incorporated in the overall project schedule it is immediately evident how the submittals effect the work which are associated to them. A sample submittal log is attached for your reference.

Prior to sending submittals into the engineer for review, KC Construction's project management team takes great pride in viewing the submittals for accuracy and pertinent information as required by the project specifications in order to streamline the review process and cut down the need for returned submittals from the engineer requiring resubmission.

• REQUEST FOR INFORMATION (RFIs)

During the project KC Construction along with their subcontracts may have the need to request from the engineer clarification of the drawings or specifications. At that point KC will use a request of information (RFI) system to identify site changes, inconsistencies/clarifications of the specifications, items affecting usability of lifecycle cost, etc. When generating a RFI we typically offer suggested resolutions to the issues. This proactive approach in

many instances aid the Project Team in resolving issues at a faster rate than normal. In additional if there is a cost or a scheduling impact that too will be noted within the RFI. RFIs are tracked via a log containing date submitted and date responded. This log along with the submitted and reviewed responses from the engineer are uploaded onto our FTP site so the Project Team has real time access to this information.

<u>CHANGE ORDERS</u>

Change Orders are handled via our ComputerEase software. Once a request for change is initiated, we open up a new change order request which are numbered consecutively. This change order request would be supplied to the owner with all necessary information including but not limited to pricing for labor, materials, equipment, and subcontractors and also most importantly an estimated review impact. Some change order requests are critical to review in order to not incur project delays. This information would be noted within the request. Once a request is approved our software would generate a formal contract change order along with a change order number which runs independently of the request numbering. Throughout these steps ComputerEase generates reports for the request along with change orders that detail the current status (reviewing, approved, denied, etc.). These reports are shared at the job progress meetings to ensure the Project Team is fully aware of the current status.

• <u>PUNCHLIST & CLOSEOUT</u>

During project closeout once the punch list walk thru is completed between the engineer, owner, and KC Construction we would generate a punch list log. The punch list items would be listed with a required solution, an estimated completion date, and actual date completed. In addition to the punch list items any necessary closeout documents would be listed such as lien releases, O&M manuals, and warranty documents. Once this log is generated it would be shared with the Project Team via our FTP site and updated constantly.

QUALITY CONTROL & DAILY REPORTING

Our self-performed and subcontracted work performance would be monitored onsite by our site superintendent and our third-party QC Testing agency. All work would be monitored to be in accordance with the contract documents and drawings. If any items are noted to be in non-conformance, the subcontractor along with the owner/engineer would be immediately made aware of the issue. The subcontractor would be required to make the necessary corrective action prior to moving forward. Once corrected the engineer would be notified of the completed corrective action so they could verify compliance if required.

Our site superintendents utilize our field tracking software HeavyJob (HCSS) which is an industry leading data capture application. This program serves as a one stop shop for all project information to be captured and reported in one location. This software allows the superintendent to quickly and easily complete daily reports containing pertinent information such as weather, daily productions and activities, labor and equipment hours, issues and corrective actions, photo documentation and safety related items. Along with daily reports the software allows for tracking of delivered items and materials. Our reports are uploaded daily to the HeavyJob Manager system so the Project Team has real time access to the current project status.

KC has been fortunate to work on several PA DGS projects in recent years and now has multiple staff members who are fluent users of E-Builder, the Department's proprietary project management software. It is a powerful program that definitely includes a learning curve. KC believes in the system and understands the benefit of the project document organization, reporting capabilities and ability to expedite information processing.

• <u>PAYMENT PROCEDURES</u>

KC Construction has a strong standing relationship with our subcontractor and suppliers. This is due in part by providing prompt payment to all our subcontractors and suppliers. Our core company goal is to have all

subcontractors paid within 1 week of receiving payment from the owner for their work completed. Our Project Manager and Accounting team ensue this is in compliance with the use of ComputerEase which handles our accounts receivable and accounts payable for subcontractors.

Attached are samples of the reports generated by the multiple software we currently utilize.

KC Construction Company - 1737 Stout Drive, ivyland, PA 18974 - (215) 443-5553 ph (215) 443-0354 fx SUBMITTAL LOG

> Project: NJAW Raritan Millstone Long Term Flood Protection Project Owner: New Jersey American Water Commany

Owner: Engineer: Contractor:	New Jersey AECOM KC Construe	American M ction Comp	Vater Company any										
Item No.	Transmittal No.	Spec	Specification	Paragraph No.	Submittal Description	Submittal Type	Contractor, Subcontractor, Vendor	Date KC Recvd	Date Da Submitted fro	te Recvd	A TROVA PA A PAVO PA A B PAVO PA A B PAVO PA A PAVO PA A PAVO PAO A PAVO PAO	Date NEORIMATION From KC	Comments:
	14	01 53 00:01	Temporary Fload Protection	3.1	Temporary Flood Protection Plan	SD-01 Preconstruction Submittals						0	
		01 53 00:02	Temporary Retaining Structures	1.5.1	Temporary Rebaining Structures - Shop Drawings	SD-02 Shop Drawings							
		01 53 00.02	Temporary Retaining Structures	1.5	Temporary Retaining Structures - Design Data	SD-05 Design Data							1
		01 56 00	Dust Control	3.1	Dust Control Plan	SD-01 Preconstruction Submittals				4		5 8 5 8 5 8	4 A
		01 57 20	Environmental Protection	1.6	Environmental Protection Plan	SD-08 Manufacture's Instructions			1	>			
		01 57 20	Environmental Protection	1.7	Site Safety & Health Plan	SD-08 Manufacture's Instructions			5				
		01 57 20	Environmental Protection	1.7.2	Safety & Health Manager	SID-08 Manufacture's Instructions						s :	
		01 57 20	Environmental Protection	1.9.2	Persons Certified in First Aid & CPR	SD-08 Manufacture's Instructions		1		1 10			
		01 57 20	Environmental Protection	1.14	Emergency Response Plan	SD-08 Manufacture's Instructions							<i>2</i> 4
		01 57 20	Environmental Protection	1.17	Excavation & Handling Work Plan	SD-01 Preconstruction Submittals						9 0 9 0	
		01 57 20	Environmental Protection	3.8	Quality Control Plan	SID-01 Preconstruction Submittals				5.6	8		
		02 41 00	Selective Demoltion	1.7	Existing Conditions Survey	SD-01 Preconstruction Submittals	2						
		02 41 00	Selective Demolfton	1.7	Preconstruction Video Documentation	SD-01 Preconstruction Submittals	6						
		02 41 00	Selective Demolition	1.8	Demotition Ptan	SD-01 Preconstruction Submittals							
		02 41 00	Selective Demoltion	1.6.2	Waste Disposal Receipts	SD-07 Certificates				-			
		03 11 14	Formwork for Concrete	13	Form Work - Shop Drawings	SD-Dr. Strup Drawing							
		03 11 14	Formwork for Concrete	2.1	Form Work Accessories - Product Data	Strug Booled Date				2			
		03 11 14	Formwork for Concrete	1.9	Field Inspection Reports - Formwork	SD-06 T and Reports			·				
	2	03 15 13	Joints & Waterstop	3.1	Waterstop Layout - Shop Drawings	SD-02 Shop Drawings		33		×.			
	0 14	03 15 13	Joints & Waterstop	2.1.1	Preformed Expansion Joint Filler Strep. Product Data	So 03 Product Data	a 6	<u>10.</u> 10.				9 0 9 0	
		03 15 13	Joints & Waterstop	2.1.2.1	Field Molded Sealants & Phoner - Product Data	SD-03 Product Data	<u></u>					9 0 9 0 8 0	
		03 15 13	Joints & Waterstop	2.1.2.2	Compression Seals & Lubricant - Product Data	SD-03 Product Data							
		03 15 13	Joints & Waterstop	2.1.2.3	Concrete Slope Paving Joints Sealers - Product Data	SD-03 Product Data						10 U	
		03 15 13	Joints & Waterstop	22.1	Non-Metalic Weterstaps - Product Data	SD-03 Product Data							
		03 15 13	Joints & Waterstop	2.1.1	Preformed Expansion Joint Filer Strips - Sampro	SD-04 Samples							
		03 15 13	Joints & Waterstop		Field Worded Sealants & Primer - Sample	SD-04 Samples							
		03 15 13	Joints & Waterstop	21.2	Compression Seals & Lubricant - Sample	SD-04 Samples		5		0			
		03 15 13	Joints & Waterstop	2123	Concrete Stope Paving Joints Sealers - Sample	SD-04 Samples		2	Ť	÷			
		03 15 13	Joints & Waterstop	221	Non-Metalic Waterstops - Sample	SD-04 Samples	57 	23					
	0.0	03 15 13	Joints & Waterstop	23.12	Non-Metalic Field Spiced Waterstop - Sample	SD-04 Samples	9 R	10. 10.	<u></u>			ସ ତ ସ ତ ସ ତ	
	0	03 21 00	Reinforcing Steel	3.1	Reinforcement Bar - Shop Drawings	SD-02 Shop Drawings						9 9 9 9 9 9	
		03 21 00	Reinforcing Steel	2.1.1	Reinforcement Bar - Product Data	SD-03 Product Data							

00 - Submittal Log - Raritan Millstone LT Flood Protection.xis

1 of 7

1/30/2017 3:53 PM

DELAWARE DEPARTMENT OF TRANSPORTATION

23697 Dupont Boulevard, Georgetown, Delaware 19947

REQUEST FOR INFORMATION

TO: (Area Engineer)	
George Pierce, PE	DATE 1/10/17 RFI NO. 21
Group 3 Construction	CONTRACT NO. T201207603
	FAP No.
FROM: Derek Fuller – KC Construction Company	PROJECT NAME: Hearns Pond Dam Improvements
SUBJECT: Joint Details, Waterstop, & Keyway	ANSWER REQUIRED BY:
Clarifications	
(Department Line Only)	
Forwarded to: (name and date)	Returned from: (name and date)
Forwarded to(2 nd): (name and date)	Returned from(2 nd): (name and date)
Description of the Request for Information (RFI) Please find attached sketch. Review and commo	ent if our understanding/darifications are correct.
COPIES TO:	SIGNATURE Derek Fuller – KC Construction
ANSWER	DATE January 11, 2017
1. Slab to Slab - Agreed, no comment.	
2. Slab to Culvert Use Speed Dowel by	Sika 1 1/2" diameter smooth round dowel 20" long
(DCD10) and a 20" open control of	such a the second developed into a second developed in the second developed developed in the second developed in the second developed deve
(PSDIO), spaced at 30°, epoxy coated do	owers. Epoxy grout exposed dower end into existing
precisi cultert pile cap. Dowers shot	nd be rocated at mid-depth of spiriway stab. Ensure
douel an perpendicular to joint fac	e in all directions.
3. Ogee t asl ab - Agreed, no comment.	
4. Ogee to Ogee - Agreed, bituminous coat	ting for bond break is typical; between ogee to ogee, and
ogee to walls A & B.	
5. Slab to Walls - Agreed, no comment.	Sug
(Note any attachmente)	SIGNATURE
(Note any attachments)	
COPIES TO	







KC Construction Company - 1737 Stout Drive, Ivyland, PA 18974 - (215) 443-5553 ph (215) 443-0354 fx <u>RFI LOG</u>

NJAW Raritan Millstone Long Term Flood Protection Project New Jersey American Water Company AECOM KC Construction Company

Project: Owner: Engineer: Contractor: P

P			_	_	_	_				_	_	_	_	_	_	-	_	_	_	_	_	_		_	-	_
NOTES																										
DATE RETURNED			•						•			s - 6					6 D				98 - 41 54 - 13		6 10 5 10			
DATE SUBMITTED	1/31/2017	1/31/2017	1/31/2017	1/31/2017	1/31/2017																					
DESCRIPTION	Vibration Monitoring	Utility Location	Utility Grouting Low Lift Pump Station	Project Sign Location	Profile View Clarification	Welded Wire Reinforcement																				S
RFI#	01	02	03	04	05	90	07	08	60										0				~			

Page 1 of 2

8286 RFI Log.xls

2/13/201710:41 AM

KC CONSTRUCTION Co.

KC CONSTRUCTION COMPANY 1737 Stout Drive, Ivyland PA 18974 Ph: (215) 443-5553 Fax: (215) 443-0354



DAILY CONSTRUCTION REPORT

	Raritan Millstone LT Flood Control	DAY:	Thursday	DATE:	8/1	0/201	7
	GC8286	CONTRAC	T TIME:	1	70 of	465/	678
ATION:	Bridgewater, NJ	WEATHER	CONDITIONS:	Sunny	/		
	Mieszko Strozek	TEMP (°F)	: AM-	61	PM-	86	5
	KC CONSTRUCTION PROGRES	s			Personnel	No.	Hr.
	TASK NARRATIVE		PERSONNEL	HOURS	Office	2	
_	TASK NAMATIVE		COUNT	noons	Surveyor	1	10
Combi-	Wall Support		1	8	Operator	3	8
				~	Foreman	1	8
Wester	n Drying Bed fill		1	8	Laborer	2	8
		9	2	-		2	
Prep Fle	oodwall and Bonding Cable Install, Northeas	t	3	8		de la	
		î			N.	h	
					P. P.	1	
			1		4 4		
			- W	the star	TOTAL		_
				V ľ			
		39		The second			
	Combi- Wester Prep Fl	ATION: ATION:	Raritan Millstone LT Flood Control DAY: CONTRAC GC8286 Bridgewater, NJ Mieszko Strozek WEATHER TEMP (°F) KC CONSTRUCTION PROGRESS TASK NARRATIVE Combi-Wall Support Western Drying Bed fill Prep Floodwall and Bonding Cable Install, Northeast	Raritan Millstone LT Flood Control DAY: Thursday GC8286 CONTRACT TIME: WEATHER CONDITIONS: Mieszko Strozek TEMP (°F): AM- KC CONSTRUCTION PROGRESS TASK NARRATIVE PERSONNEL COUNT Combi-Wall Support 1 Western Drying Bed fill 1 Prep Floodwall and Bonding Cable Install, Northeast 3	Raritan Millstone LT Flood Control DAY: Thursday DATE: GC8286 CONTRACT TIME: 1 Bridgewater, NJ WEATHER CONDITIONS: 5unny Mieszko Strozek TEMP (°F): AM- 61 COUNT 61 KC CONSTRUCTION PROGRESS TASK NARRATIVE PERSONNEL COUNT HOURS Combi-Wall Support 1 8 Western Drying Bed fill 1 8 Prep Floodwall and Bonding Cable Install, Northeast 3 8	Raritan Millstone LT Flood Control DAY: Thursday DATE: 8/10 GC8286 CONTRACT TIME: 170 of Bridgewater, NJ WEATHER CONDITIONS: Sunny 61 PM- Mieszko Strozek TEMP (°F): AM- 61 PM- KC CONSTRUCTION PROGRESS TASK NARRATIVE PERSONNEL COUNT HOURS Operator Combi-Wall Support 1 8 Foreman Laborer. Western Drying Bed fill 1 8 Torman ToTAL Prep Floodwall and Bonding Cable Install, Northeast 3 8 ToTAL	Raritan Millstone LT Flood Control DAY: Thursday DATE: 8/10/201 GC8286 CONTRACT TIME: 170 of 465, Bridgewater, NJ WEATHER CONDITIONS: Sunny 61 PM- 80 Mieszko Strozek TEMP (°F): AM- 61 PM- 80 KC CONSTRUCTION PROGRESS TASK NARRATIVE PERSONNEL COUNT HOURS Office 2 Surveyor 1 8 Foreman 1 Western Drying Bed fill 1 8 Foreman 1 Prep Floodwall and Bonding Cable Install, Northeast 3 8 TOTAL TOTAL

	SUBCONTRACTOR PROGRESS	
SUBCONTRACTOR	PROGRESS	WORKFORCE
McCrossin	Combi-Wall: Grouted Pipe Piles P81, P82, P83.	9
Consolidated Fence	Continued work on final fence run connecting Northwest and Southwest runs.	2
R&W Concrete	Poured footings in the Southeast for Monolith's SE-4, SE-6, SE-8. Planned pour for Northeast Valve Vault was postponed to tomorrow	6

GENERAL DISCUSSION, NOTES ON PROJECT, UPCOMING ISSUES, DELIVERIES, ETC.	
-Continued filling Western Drying Bed from STA 705+00 to STA 703+00	
-Continued installing bonding cables to sheets in the Northeast.	
-Placed pumps for dewatering the Northeast Basin in preparation for fill	

MATERIALS RECEIVED	SUPPLIER	TOTAL	COMMENTS
4" Minus Fill (Western Drying Bed)	Stavola Bound Brook Quarry	2103.99 Tons	82 Loads
A A A			
Wannes W			
The American	-	· ·	
A	ACCIDENTS / INJURIES & HAZARI	DOUS ACTIVITIES CONDUCTED	1
None			

VISITORS TO SITE	COMPANY	PURPOSE	
Jeff Bevacqua	French & Parello	Soil testing, Concrete Testing, Grout Testing	
0 200			

Page 1 of 4



DAILY CONSTRUCTION REPORT

PROJECT: Raritan Millstone LT Flood Control DATE: 8/10/2017



Western Drying Bed (Showing STA 705+00 to STA 703+00)

Page 2 of 4

KC CONSTRUCTION COMPANY 1737 Stout Drive, Ivyland PA 18974 Ph: (215) 443-5553 Fax: (215) 443-0354



DAILY CONSTRUCTION REPORT

PROJECT: Raritan Millstone LT Flood Control DATE: 8/10/2017



Western Drying Bed (Photo Taken from top of existing Levee near STA 703+00, looking North)

Page **3** of **4**

KC CONSTRUCTION COMPANY 1737 Stout Drive, Ivyland PA 18974 Ph: (215) 443-5553 Fax: (215) 443-0354



DAILY CONSTRUCTION REPORT

PROJECT: Raritan Millstone LT Flood Control DATE: 8/10/2017



Footing poured for Monolith SE-8

Page 4 of 4

1354 fx	×	NOTES	KCC revised trench to 200LF x 2' and corrected burden rate	ABPROVED	APPROVED				2				Approved orally by Manoj on 8/31	Approved orally by Manoj			9/18: Manoj is okay with KCC procurring them, per AECOM	No longer desired by NJAW	Approved orally by Manoj											
ph (215) 443-0		APPROVED CO COST	S (11,767.00)	\$ 11,304.96	\$ 36,072.11	\$ 7664 38	\$ 85,349.00	\$ 3,392.83	\$(104,737.48)	\$ 4,267.78	S (11,810.50)	\$ 119,467.25	\$ 98,328.62	\$ 13,398.34	\$ 72,629.92 * 052.70	\$ 8.625.00.	\$ 6,785.00	\$	\$ 17,028.00	\$ 130,594.75			, S			- -	•	20100		\$ 484,364.09
215) 443-5553		COST	\$ (11,767.00)	\$ 33,153.67	\$ 36,072.11	\$ 2 664 38	\$ 85,349.00	\$ 3,392,83	\$(104,737.48)	5 4,267.78	\$ 133.785.00	\$ 119,467.25	\$ 98,328.62	\$ 13,398.34	\$ 72,629.92 * 052.72	\$ 8.625.00	\$ 6.785.00	\$ 37,358.00	\$ 17,028.00	\$ 130,594.75	\$ 75 567 54	\$ 61,303.00	\$ 72,709.35	\$ 8,428.75	\$ 55,287.00	\$ 67.533.00	\$ 36,080.00			
d, PA 18974 - (DER LOG		DATE RETURNED	5/4/2017	11/15/2017	11/15/2017	5/0/2017	5/26/2017	11/15/2017	11/15/2017	5/26/2017	11/15/2017	11/15/2017	11/15/2017	11/15/2017	11/15/2017	11/15/2017	11/15/2017		11/15/2017	11/15/2017				-						
ut Drive, Ivylan CHANGE OR		DATE	5/4/2017	8/3/2017	8/3/2017	4/24/2017	5/16/2017	5/12/2017	9/6/2017	5/26/2017	6/23/2017 10/26/2017	8/23/2017	8/16/2017	7/12/2017	10/30/2017	8/7/2017	8/7/2017	8/7/2017	9/20/2017	10/30/2017	10/25/2017	417/2017	2/21/2018	11/7/2017	11/1/2017	1/30/2018	2/21/2018			1
KC Construction Company - 1737 Stor	g Tarm Flood Protection Project Company	DESCRIPTION	Relocation of 2" Sanitary Forcemain to High Road	Jet Grouting 6* Gas Main Northeast Levee 2 - 6*	Jet Grouting 48" Water Main Northeast Levee 4-8"	High Road Aerial Communication Line Demo High Road Flactrical Orientation Confirmation	Cedar Hill Access Roadway Widening	Additional Underground Electrical Duct Bank Trenct	Revisions to Jet Grouting Scope as per RFI No. 31 Response	RFI 34 Sludge Line Removal	U-Culvert Joint Revisions Toe Drain Revisions - REV 1	Western Drying Bed	High Road Electrical Pole B Modification	60" Flow Meter Temporary Electric Service	Combi Wall Down Time - REV 2	50 Samping Line Fix - Noruleast Flood Gates - Equipment Side Change	Flood Gates - Protective Shields	Flood Gates Spare Air Bladder Tubes	Admin. Building Storm Drainage	Northwest Embankment Unsuitable Materials - REV 2	Combi-Wall Clean Un	Southwest Sampling Vault	Southwest Sampling Vault	Presray Flood Gates Inspection	RFI 60 Gate 5 Utility Lowering North Gate DSE&G Gas Line Encasion	Northeast Drain Line Extension	Basin 3 & 4 Electrical Reconnection			20
	Millstone Lon merican Water on Company	NJAW ISSUED CO #	CO#1	C0#2	CO#2	1#00	CO#1	CO#2	CO#2	CO#1	CO#Z	C0#2	CO#2	C0#2	CO#2	CO#2	C0#2	100000	C0#2	CO#2										0.
	NJAW Raritan New Jersey Au AECOM KC Constructi	ACTION	APPROVED	APPROVED	APPROVED	APPROVED	APPROVED	APPROVED	APPROVED	APPROVED	PENDING	APPROVED	APPROVED	APPROVED	APPROVED	APPROVED	APPROVED	REJECTED	APPROVED	PENDING	PENDING	DENDING	PENDING	PENDING	PENDING	PENDING	PENDING			
	Project: Owner: Engineer: Contractor:	PCO#	COR 01.A	COR 02.A1	COR 03.A	COP OF	COR 06.B	COR 07	COR 08.2	COR 09.A	COR 10.A	COR 12.1	COR 13.1	COR 14	COR 15.2	COR 17	COR 18	COR 18	COR 20.1	COR 21.2	COR 23	COR 24	COR 24.A	COR 25	COR 26	COR 28	COR 29			

3/21/201811:32 AM

KC CONSTRUCTION CO.

8286 Change Order Log.xls

Page 1 of 2



Marquette Lake Dam - Rehabilitation

Project No. DGS C-0960-0086 Phase 1

SECTION 3. Staffing Plan

KC CONSTRUCTION CO.

1737 Stout Drive, Ivyland, PA 18974 | 215-443-5553

127

Marquette Lake Dam Rehabilitation

Project No. DGS C-0960-0086 Phase 1

TECHNICAL SUBMITTAL

Section 3. Staffing Plan

T-3A Staffing Resources

MARQUETTE LAKE DAM REHABILITATION PROJECT NO. DGS C-0960-0086 PHASE 1

TECHNICAL SUBMITTAL

T-3A Staffing Resources

We anticipate requiring a combination of heavy equipment operators, skilled and unskilled laborers, carpenters and articulated off road truck drivers for much of the project. The scope of services includes but is not limited to selective demolition, excavation, drainage pipe installation, embankment fill, and site restoration. As mentioned in our work plan, we will have multiple crews on-site working on several different work areas concurrently seeing as many as 10-15 workers at a given time. We currently have a pool of skilled employees well in excess to meet project requirements.

KC Construction Co. is signatory to local trade unions, such as the International Union of Operating Engineers Local 542 and the Laborers International Union of North America Local 158. Should the need arise, we will request skilled operators and laborers from these unions to fill needed positions.

It is the policy of KC Construction Company to take affirmative action to assure equal employment opportunity to all qualified persons, without regard to race, color, religion, sex, national origin, age, disability, or veteran status. This includes, but is not limited to the following: hiring, placement, upgrading, transfer, demotion or promotion recruitment, advertising or solicitation for employment treatment during employment rates of pay or other forms of compensation selection for training layoff or termination

It is the policy of KC Construction Company to achieve and maintain full compliance with all applicable statutes, regulations and executive orders on equal employment opportunity and affirmative action. The Equal Employment Opportunity Officer for KC is Doreen Fortnum. 215-443-5553.

KC Construction Company is committed to nondiscrimination in employment. Any person who applies for a job with this company will not be discriminated against because of race, color, religion, sex, age, national origin, disability or veteran status. All qualified applicants are welcome to apply for jobs with this company. In particular, present minority and female employees are encouraged to refer qualified minorities and females to the company.

All Subcontractors shall submit verification that they can properly man the work with skilled labor prior to the start of their work.

Performance Staffing Resources

As addressed in Sections T-1A and T-2A, we have assigned a veteran team of construction professionals. This team will have the support they need to meet your project schedule while meeting your expectations.

Performance is also a signatory with the carpenters, laborers and operating engineer's unions in Pennsylvania. We have a core group of personnel that we can choose from and will supplement with workers from the local unions. We can also bring in workers from locals outside of the immediate area surrounding the project if need be. The carpenter's union has an exceptional training program for carpentry skills as well as certifications for the safe operation of various equipment that will be utilized throughout projects in our industry. This ensures that workers recruited from them will be well qualified.

With the ability to tap into these many resources, our team remains poised to lead this construction project to a successful completion. We will provide full-time, onsite supervision, as well as any necessary office support, throughout construction. We have the resources, know-how, and the veteran team to meet the priorities, overcome the construction challenges, and bring the Dam Improvements at the Lower Woods Pond project that you envision. Our team has a plan and is ready to work for you.

Marquette Lake Dam Rehabilitation

Project No. DGS C-0960-0086 Phase 1

TECHNICAL SUBMITTAL

Section 3. Staffing Plan

T-3B Skill Training

MARQUETTE LAKE DAM REHABILITATION PROJECT NO. DGS C-0960-0086 PHASE 1

TECHNICAL SUBMITTAL

T-3B Skill Training

KC Construction participates federally registered Apprenticeship Program through local unions we are signatory to. However, we also have our own in-house training program. All newly hired skilled personnel (operators / truck drivers / laborers) participate in an in-house on the job site training assessment to determine their eligibility to perform the tasks assigned to them. Some key elements of training are: training on operating and maintenance by manufacturer's reps, off road truck driving skills, large diameter riprap placement, embankment toe drain excavation of drainage material placement, blanket drainage material placement, and operating excavators on side slopes. Determining that our personnel have these, and other key proficiencies is critical in providing an exceptional project on time and budget to the owner.

KC Construction is also a signatory with the operating engineer's unions in Pennsylvania and New Jersey. The union members are trained in real-world facilities on the latest models of equipment, including those with the newest technology and GPS systems. They offer comprehensive programs so apprentices, mechanics, field engineers, journeymen and women and members can perfect their skills, cross train to learn new ones, and stay ahead of changes in equipment and technology.

Full-time instructors provide everything from heavy equipment operator training, training in emergency response, hazardous waste operations and OSHA requirements to keep contractors supplied year-round with safe, skilled, and efficient operators. Numerous pieces of equipment, simulators and instrumentation are available for training. Equipment includes a variety of cranes, new millers and pavers, backhoes, dozers, side booms, pile drivers and more.

Marquette Lake Dam Rehabilitation

Project No. DGS C-0960-0086 Phase 1

TECHNICAL SUBMITTAL

Section 3. Staffing Plan

T-3C Workforce Safety

MARQUETTE LAKE DAM REHABILITATION PROJECT NO. DGS C-0960-0086 PHASE 1

TECHNICAL SUBMITTAL

T-3C Workforce Safety

All employees are ultimately responsible for their own safety and share the responsibility for the safety of their co-workers, our client's employees, and their property and equipment. All employees must comply with: KC Construction Company Health and Safety Program; all Federal and State requirements; craft specific safety practices; established Safety, Health and Environmental Policies and Procedures of our clients; and posted safety instructions such as posted signs, barricades, barriers, and permit instructions.

All new employees are given physicals and are drug tested in accordance with our Drug and Alcohol Abuse Policy/Program. Furthermore, all employees are subject to mandatory post-accident drug and alcohol screening.

All Supervisors are required to have OSHA 30 training and CPR/First Aid Training. Other OSHA training such as OSHA-10, Fall Protection, Forklift, Signal Person, Confined Space, Competent Person, etc... are given to all employees as required. All training is performed by Med-Tex Services, Philadelphia, PA.

A copy of our Company Health and Safety Policy and Procedures Manual will be kept on-site at all times. Prior to a project beginning, a site and work hazard assessment will be performed by the Project Manager and a Site-Specific Health and Safety Plan will be produced. All Subcontractors will be required to submit their own Site-Specific Health and Safety Plan. Our outside Safety Consultant will review and approve these plans for OSHA and Company compliance and determine if additional training will be required. During the project, weekly safety toolbox talks will be given by our project superintendent. Topics shall include potential hazards for the work being performed that week. Weekly site safety audits are to be performed by the site Superintendent with monthly audits to be performed by the company Operations Manager or Vice President. An outside safety professional will be brought in to perform a quarterly audit.



Marguette Lake Dam - Rehabilitation

Project No. DGS C-0960-0086 Phase 1

PART 4.

Supporting Documentation

KC CONSTRUCTION CO.

1737 Stout Drive, Ivyland, PA 18974 | 215-443-5553

Marquette Lake Dam Rehabilitation

Project No. DGS C-0960-0086 Phase 1

TECHNICAL SUBMITTAL

Section 4. Supporting Documents

T-4A Proposal Signature Page (COPY)

APPENDIX A

PROPOSAL SIGNATURE PAGE

APPENDIX A PROPOSAL SIGNATURE PAGE

Proposer's Representations and Authorizations. Proposer by signing this Proposal Signature page and submitting its proposal understands, represents, acknowledges and certifies that:

- a. All information provided by, and representations made by, the Proposer in the proposal are material and important and will be relied upon by the Proposal Evaluation Committee in reviewing the Proposal and by DGS in awarding the contract. Any misrepresentation of a material fact or omission of material fact by the entity submitting the proposal shall be treated as fraudulent concealment from the Commonwealth of the true facts relating to the submission of the proposal. If the misrepresentation and/or omission of material fact is discovered during the review of the proposal, the proposal will be automatically disqualified. Discovery of the misrepresentation and/or omission of material fact after contract award constitutes grounds for defaulting the contractor and may lead to debarment procedures being instituted against the contractor. A misrepresentation shall be punishable under 18 Pa. C.S. § 4904.
- b. Proposer acknowledges that they have received, read and understood all Addenda issued for the Project.
- c. The price and amount of this proposal have been arrived at independently and without consultation, communication or agreement with any other Proposer or potential Proposer.
- d. Neither the price nor the amount of the proposal, and neither the approximate price nor the approximate amount of this proposal, have been disclosed to any other firm or person who is a Proposer or potential Proposer, and they will not be disclosed on or before the proposal submission deadline specified in the Notice to Proposers and the Calendar of Events.
- e. No attempt has been made or will be made to induce any firm or person to refrain from submitting a proposal on this contract, or to submit a proposal higher than this proposal, or to submit any intentionally high or noncompetitive proposal or other form of complementary proposal.
- f. The proposal is made in good faith and not pursuant to any agreement or discussion with, or inducement from, any firm or person to submit a complementary or other noncompetitive proposal.
- g. To the best knowledge of the person signing the proposal for the Proposer, the Proposer, its affiliates, subsidiaries, officers, directors, and employees are not currently under investigation by any local, state or federal governmental agency and have not in

the last four (4) years been convicted or found liable for any act prohibited by State or Federal law in any jurisdiction, involving conspiracy or collusion with respect to bidding or proposing on any public contract, except as disclosed by the Proposer in its proposal.

- h. To the best of knowledge of the person signing the proposal for the Proposer and except as otherwise disclosed by the Proposer in its proposal, the Proposer has no outstanding, delinquent obligations to Commonwealth including, but not limited to, any state tax liability not being contested on appeal or other obligation of the Proposer that is owed to Commonwealth.
- i. The Proposer is not currently under suspension or debarment by Commonwealth, or any other local, state, or the federal government. If the Proposer cannot so certify, then it shall submit along with its proposal a written explanation of why it cannot make such certification.
- j. The Proposer has not, under separate contract with the DGS made any recommendations to DGS concerning the need for the services described in the proposal or the specifications for the services described in the proposal.
- k. Each Proposer, by submitting its proposal, authorizes all Commonwealth agencies to release to Commonwealth information related to liabilities to Commonwealth of Pennsylvania including, but not limited to, taxes, unemployment compensation, workers' compensation liabilities and Prevailing Wage Act.
- 1. Until the selected Proposer receives a fully executed and approved written contract from the DGS, there is no legal and valid contract in law or in equity, and the Proposer should not begin to perform work. If a Letter of Intent has been issued, the Proposer may proceed in accordance with the terms of the Letter.
- m. Proposer is not currently engaged, and will not during the duration of the contract engage, in a boycott of a person or an entity based in or doing business with a jurisdiction which the Commonwealth is not prohibited by Congressional statute from engaging in trade or commerce; and is eligible to contract with the Commonwealth under Section 3604 of the Procurement Code.
- n. Proposer agrees and certifies to abide by, but not be limited to, the Commonwealth of Pennsylvania Acts, Provisions, Clauses, and Statements stated in the Contract Documents.

I am authorized to sign this proposal on behalf of the Proposer and I agree and state that <u>CCConstruction</u> (Name of Firm) understands and acknowledges that the above representations are material and important, and will be relied upon by the Proposal Evaluation Committee and the Department of General Services in awarding the contract(s) for which this proposal is submitted. I understand and my firm understands that any misstatement shall be treated as fraudulent concealment from the Department of General Services of the true facts relating to the submission of this proposal.

PROPOSER IS A CONTRACTOR/INDIVIDUAL: By: Witness: Contractor / Individual PROPOSER IS A LIMITED LIABILITY COMPANY (LLC) OR PARTNERSHIP: By: Witness: General Partner / Authorized LLC Member By: Limited Partnership PROPOSER IS A CORPORATION: President Vice-President reast elarv Gino Yannuzzelli John V. Lima PROPOSER IS A JOINT VENTURE Attest: By: President Secretary By: Attest: President Secretary

Marquette Lake Dam Rehabilitation

Project No. DGS C-0960-0086 Phase 1

TECHNICAL SUBMITTAL

Section 4. Supporting Documents

T-4B Non-Collusion Affidavit (COPY)

APPENDIX B

Non-Collusion Affidavit

Appendix B NON-COLLUSION AFFIDAVIT

INSTRUCTIONS FOR NON-COLLUSION AFFIDAVIT

- 1. This Non-collusion Affidavit is material to any contract awarded pursuant to this proposal. According to §4507 of the Commonwealth Procurement Code, 62 Pa. C.S. §4507, governmental agencies may require Non-collusion Affidavits to be submitted with proposals.
- 2. This Non-collusion Affidavit must be executed by the member, officer, or employee of the Proposer who makes the final decision on prices and the amount quoted in the proposal.
- 3. Bid rigging and other efforts to restrain competition, and the making of false sworn statements in connection with the submission of proposals are unlawful and may be subject to criminal prosecution. The person who signs the affidavit should examine it carefully before signing and assure himself or herself that each statement is true and accurate, making diligent inquiry, as necessary, of all other persons employed by or associated with the Proposer with responsibilities for the preparation, approval or submission of the proposal.
- 4. In the case of a proposal submitted by a joint venture, each party to the venture must be identified in the proposal documents and an affidavit must be submitted separately on behalf of each party to the joint venture.
- 5. The term "complementary proposal" as used in the affidavit has the meaning commonly associated with that term in the proposal process, and includes the knowing submission of proposals higher than the proposal of another firm, any intentionally high or noncompetitive proposal, and any other form of proposal submitted for the purpose of giving a false appearance of competition.
- 6. Failure to submit a Non-collusion affidavit with the Proposal in compliance with these instructions may result in disqualification of the proposal.

NONCOLLUSION AFFIDAVIT

State of	Pennsylvania	
County of	Bucks	

DGS Project Number: C-0960-0086.1

KC Construction Co. (Name of I state that I am the Vice President (Title) of Firm) and that I am authorized to make this affidavit on behalf of my firm, and its owners, directors, and officers. I am the person responsible in my firm for the prices(s) and the amount of this proposal.

I state that:

- 1. The price(s) and amount of this proposal have been arrived at independently and without consultation, communication or agreement with any other contractor, proposer, or potential proposer.
- Neither the price(s) nor the amount of this proposal, and neither the approximate price(s) nor 2. approximate amount of this proposal, have been disclosed to any other firm or person who is a proposer or potential proposer, and they will not be disclosed before the proposal submission date.
- No attempt has been made or will be made to induce any firm or person to refrain from 3. proposing on this contract, or to submit a proposal higher than this proposal, or to submit any intentionally high or noncompetitive proposal or other form of complementary proposal.
- The proposal of my firm is made in good faith and not pursuant to any agreement or 4. discussion with, or inducement from, any firm or person to submit a complementary or other noncompetitive proposal.
- (Name of Firm) its affiliates, subsidiaries, officers, 5. KC Construction Co. directors, and employees are not currently under investigation by any governmental agency and have not in the last three years been convicted or found liable for any act prohibited by state or federal law in any jurisdiction, involving conspiracy or collusion with respect to proposing and/or bidding on any public contract, except as follows:

N/A

(Name of Firm) understands and acknowledges that the KC Construction Co. I state that above representations are material and important, and will be relied upon by the Department of General Services in awarding the contract(s) for which this proposal is submitted. I understand and my firm understands that any misstatement in this affidavit is and shall be treated as fraudulent concealment from the Department of General Services of the true facts relating to the submission

of this proposal. (Signature

Gino Yannuzzelli (Signatory's Printed Name)

Vice President

(Signatory's Title)

SWORN TO AND SI

otary Public

My Commission Expires

