

**Attention: All certification candidates are required to have an established and up to date user portal account in the PA State Fire Academy 's Acadis Learning Management System prior to participating in <u>ANY</u> certification testing opportunity. Please log in to your Acadis portal account and update all personal information before submitting your certification application. (Access can be gained through the OSFC website – <u>Training and Certification Portal</u>).

Firefighter II Skill Stations

NFPA 1001 – Chapter 5 (2019 Edition)

Station A	Fire Ground Communications & Operations / Interior Attack Coordination	Mandatory
Station B	Gas Cylinder Fire Control *	Mandatory
Station C	Combustible Liquid Fire Control *	Mandatory
Station D	Sprinkler Drain / Pressures	Random
Station E	Fire Safety Presentation	Random
Station F	Inspection / Maintenance: Generator, Power Tools, & Lighting Equipment	Random
Station G	Hose Service Test	Random
Station H	Fire Scene Preservation	Random

^{*} NOTE: Either Station B or Station C MUST be tested. The station not used as a mandatory station may be used as a random station.



Test	Operations / Interior Attack Coordination Mandatory Station: JPRs 5.1.2, 5.2.2, 5.3.2 Test Site Test Date Candidate # Check the Test Type						
LCSC	Site	Test Date	Candidate #	Check the Test Type			
				Initial	F	Retest	
			gned in the scenario. As a two-posts as the Incident Commander for		ach cand	idate i	
_		y - Hose Line Officer - Rescue Team Officer	Engine Company - Bac Truck Company - Vent			er	
sem r th entile omn ondite entile	ble a team and coordinate e conditions present; ass ation, entry and search need and is advised of changing ion present (e.g., attic, gra attion procedures, evaluation and its advised of changing ion present (e.g., attic, gra attion procedures, evaluation	an interior attack to accompliance the techniques are commeds are demonstrated and cooring hazards. You are evaluated ade/upper levels, basement), for on/forecast developing fire gray questions?	ommunications equipment, and which an assignment at a structure fire nunicated to the attack team; team dinated; fire growth and developm on your ability to: assemble a team or cible entry tools selected, use of sowth and development and communicated to the attack team; team or cible entry tools selected, use of sowth and development and communicated to the attack team.	e; select approp m coordination nent are monito m, attack techn search & rescu- unicate hazardo	oriate techn is main ored and I nique for technique	hniquentained nciden the firues and	
No.		Tasks	;		Yes	No	
1	Demonstrates ability to	communicates to all levels					
2			appropriate communications proc				
_	1 Toperty utilizes commit	inications equipment and uses	appropriate communications proc	cedures			
3	Coordinates and transn	nit to the teams an appropria	te plan of action for the assignment				
3	Coordinates and transn Executes the established	nit to the teams an appropriated goals and objectives for the	te plan of action for the assignme e assignment	ent			
3	Coordinates and transn Executes the establishe Checks & insure person	nit to the teams an appropriated goals and objectives for the al and team's PPE/SCBA are	te plan of action for the assignment	ent			
3 4 5	Coordinates and transn Executes the established Checks & insure person Selects proper tools/eq	nit to the teams an appropriated goals and objectives for the al and team's PPE/SCBA are uipment for the assignment	te plan of action for the assignme e assignment properly worn and monitors durin	ent			
3 4 5 6	Coordinates and transn Executes the established Checks & insure person Selects proper tools/eq Monitors fire growth, a	nit to the teams an appropriated goals and objectives for the al and team's PPE/SCBA are uipment for the assignment	te plan of action for the assignme e assignment properly worn and monitors durin unicates changes to command	ent			
3 4 5 6 7	Coordinates and transn Executes the established Checks & insure person Selects proper tools/eq Monitors fire growth, a Demonstrates appropri	nit to the teams an appropriated goals and objectives for the all and team's PPE/SCBA are uipment for the assignment and development and communication.	te plan of action for the assignme e assignment properly worn and monitors durin unicates changes to command	ent			
3 4 5 6 7 8	Coordinates and transm Executes the established Checks & insure person Selects proper tools/eq Monitors fire growth, a Demonstrates appropri	nit to the teams an appropriated goals and objectives for the all and team's PPE/SCBA are uipment for the assignment and development and commutate search and rescue technical	te plan of action for the assignme e assignment properly worn and monitors during unicates changes to command ques	ent			
3 4 5 6 7 8 9	Coordinates and transm Executes the established Checks & insure person Selects proper tools/eq Monitors fire growth, a Demonstrates appropri Demonstrates appropri Demonstrates acceptab	nit to the teams an appropriated goals and objectives for the all and team's PPE/SCBA are uipment for the assignment and development and commutate search and rescue techniques are ventilation techniques are used in confidence of the techniques are used in the techniques are us	te plan of action for the assignme e assignment properly worn and monitors during unicates changes to command ques	g use			
3 4 5 6 7 8 9	Coordinates and transm Executes the established Checks & insure person Selects proper tools/eq Monitors fire growth, a Demonstrates appropri Demonstrates appropri Demonstrates acceptab Monitors tactics to deter	nit to the teams an appropriated goals and objectives for the all and team's PPE/SCBA are uipment for the assignment and development and commutate search and rescue techniques are ventilation techniques are used in confidence of the techniques are used in the techniques are us	te plan of action for the assignment e assignment properly worn and monitors during unicates changes to command ques	g use			
3 4 5 6 7 8 9 10	Coordinates and transm Executes the established Checks & insure person Selects proper tools/eq Monitors fire growth, and Demonstrates appropriate Demonstrates appropriate Demonstrates acceptable Monitors tactics to determine the second seco	nit to the teams an appropriated goals and objectives for the all and team's PPE/SCBA are uipment for the assignment and development and commutate search and rescue technicate ventilation techniques are used in concermine if outcomes are met a	te plan of action for the assignment e assignment properly worn and monitors during unicates changes to command ques appleting the assignments and makes necessary tactical revi	g use			
3 4 5 6 7 8 9 10 11	Coordinates and transm Executes the established Checks & insure person Selects proper tools/eq Monitors fire growth, and Demonstrates appropriate Demonstrates appropriate Demonstrates acceptable Monitors tactics to determine the second seco	nit to the teams an appropriated goals and objectives for the all and team's PPE/SCBA are uipment for the assignment and development and commutate search and rescue techniques are ventilation techniques are used in concermine if outcomes are met a within an established ICS	te plan of action for the assignment e assignment properly worn and monitors during unicates changes to command ques appleting the assignments and makes necessary tactical revi	g use	PASS	FAII	
3 4 5 6 7 8 9 10 11 12 13	Coordinates and transm Executes the established Checks & insure person Selects proper tools/eq Monitors fire growth, a Demonstrates appropri Demonstrates appropri Demonstrates acceptab Monitors tactics to deta Utilizes and operates w Completes all tasks with	nit to the teams an appropriated goals and objectives for the all and team's PPE/SCBA are uipment for the assignment and development and commutate search and rescue technicate ventilation techniques are used in concernine if outcomes are met a within an established ICS thout compromising persona	te plan of action for the assignment e assignment properly worn and monitors during unicates changes to command ques appleting the assignments and makes necessary tactical revial or team safety	g use sions		FAII	
3 4 5 6 7 8 9 10 11 12 13	Coordinates and transm Executes the established Checks & insure person Selects proper tools/eq Monitors fire growth, a Demonstrates appropri Demonstrates appropri Demonstrates acceptab Monitors tactics to deta Utilizes and operates w Completes all tasks with	nit to the teams an appropriated goals and objectives for the all and team's PPE/SCBA are uipment for the assignment and development and commutate search and rescue technicate ventilation techniques are used in concernine if outcomes are met a within an established ICS thout compromising persona	te plan of action for the assignment e assignment properly worn and monitors during unicates changes to command ques mpleting the assignments and makes necessary tactical revial or team safety Please circle the final s	g use sions		FAII	



STATION B: Gas Cylinde	r Fire Control	Reference NFPA 1001 (201 Mandatory/Random Statio	, <u> </u>
Test Site	Test Date	Candidate #	Check the Test Type
			Retest

Directions: As a team, select the appropriate hose line to cool and approach a burning propane cylinder, shut the valve, and extinguish the fire. Change the nozzle operator and repeat the evolution. Do you have any questions?

Performance Outcome: Pass / Fail is determined by **14 of 14** tasks being correctly performed.

Evaluator Signature:

Vo.	Tasks	Yes	No
1	Crew selects no larger than 13/4" attack line with combination nozzle		
2	A safe haven is identified prior to advancing a hose line		
3	Contents are identified		
4	Crew initiates advancement of hose line utilizing a straight stream to cool cylinder		
5	Cylinder is cooled, and cylinder integrity is evaluated		
6	Crew widens stream pattern to fog as they approach the cylinder		
7	Nozzle operator protects crew with a fog pattern		
8	Back up person handles hose to facilitate nozzle operator's movements and control		
9	Crew successfully prevents flame from bypassing fog pattern		
10	Back-up person shuts off the cylinder valve		
11	Crew backs out using fog pattern for protection		
12	Team maintains control of the hose line at all times		
13	Candidates faced cylinder(s) during approach and retreat		
	CANDIDATES SWITCH POSITIONS AND REPEAT TASKS 4 THRU 13		
14	Completes all tasks without compromising personal or team safety		
	Please circle final skill outcome	PASS	FAI
Eva	luator Comments:		

Evaluator #



Test Site Test Date Candidate # Check the Test T Initial Calluator Note: Please indicate the type of foam system used Eductor ProPak Apparatus S rections: As a team, select and assemble the proper appliances to create a 1½" or 1¾" foam line. Using sembled, attack a combustible liquids fire, and achieve knockdown/extinguishment. Upon achieving known as afe haven, switch positions, and complete a second attack and extinguish the fire. Do you sestions? Performance Outcome: Pass / Fail is determined by 12 of 12 tasks being correctly performed. No.	ratus System Using the line ing knockdown,
Aluator Note: Please indicate the type of foam system used Eductor ProPak Apparatus Strections: As a team, select and assemble the proper appliances to create a 1½" or 1¾" foam line. Using embled, attack a combustible liquids fire, and achieve knockdown/extinguishment. Upon achieving known as afe haven, switch positions, and complete a second attack and extinguish the fire. Do you sistions? **Tormance Outcome: Pass / Fail is determined by 12 of 12 tasks being correctly performed. **No.	Using the line ing knockdown, o you have any
rections: As a team, select and assemble the proper appliances to create a 1½" or 1¾" foam line. Using embled, attack a combustible liquids fire, and achieve knockdown/extinguishment. Upon achieving knoceat to a safe haven, switch positions, and complete a second attack and extinguish the fire. Do you estions? **Tormance Outcome: Pass / Fail is determined by 12 of 12 tasks being correctly performed. **No.** Tasks** Ye* Team selects and connects proper foam eductor or foam proportioning device Team selects and connects the proper nozzle for foam application Team creates a workable foam line; tests line for foam operation prior to an attack A safe haven is identified prior to advancing a hose line Eductor/foam proportioning device is properly set for the foam being used on the given fire Attack is made from upwind direction (where possible) Foam applied using a proper foam application technique (rain down, roll-over, bank down) Knockdown/Extinguishment is achieved in a timely fashion Team properly retreats/backs away from the fire, prevents re-flash, and safe haven reached **CANDIDATES SWITCH POSITIONS AND REPEAT TASKS 5 THRU 13* Team properly flushes foam eductor/foam proportioning device, and nozzle Team disassembles foam eductor/ foam proportioning device and nozzle and returns same to storage	Using the line ing knockdown, o you have any
Tasks Team selects and connects proper foam eductor or foam proportioning device Team selects and connects the proper nozzle for foam application Team creates a workable foam line; tests line for foam operation prior to an attack A safe haven is identified prior to advancing a hose line Eductor/foam proportioning device is properly set for the foam being used on the given fire Attack is made from upwind direction (where possible) Foam applied using a proper foam application technique (rain down, roll-over, bank down) Knockdown/Extinguishment is achieved in a timely fashion Team properly retreats/backs away from the fire, prevents re-flash, and safe haven reached CANDIDATES SWITCH POSITIONS AND REPEAT TASKS 5 THRU 13 Team properly flushes foam educator/foam proportioning device, and nozzle Team disassembles foam eductor/ foam proportioning device and nozzle and returns same to storage	Yes No
Team selects and connects proper foam eductor or foam proportioning device Team selects and connects the proper nozzle for foam application Team creates a workable foam line; tests line for foam operation prior to an attack A safe haven is identified prior to advancing a hose line Eductor/foam proportioning device is properly set for the foam being used on the given fire Attack is made from upwind direction (where possible) Foam applied using a proper foam application technique (rain down, roll-over, bank down) Knockdown/Extinguishment is achieved in a timely fashion Team properly retreats/backs away from the fire, prevents re-flash, and safe haven reached CANDIDATES SWITCH POSITIONS AND REPEAT TASKS 5 THRU 13 Team properly flushes foam educator/foam proportioning device, and nozzle Team disassembles foam eductor/ foam proportioning device and nozzle and returns same to storage	
Team selects and connects the proper nozzle for foam application Team creates a workable foam line; tests line for foam operation prior to an attack A safe haven is identified prior to advancing a hose line Eductor/foam proportioning device is properly set for the foam being used on the given fire Attack is made from upwind direction (where possible) Foam applied using a proper foam application technique (rain down, roll-over, bank down) Knockdown/Extinguishment is achieved in a timely fashion Team properly retreats/backs away from the fire, prevents re-flash, and safe haven reached CANDIDATES SWITCH POSITIONS AND REPEAT TASKS 5 THRU 13 Team properly flushes foam educator/foam proportioning device, and nozzle Team disassembles foam eductor/ foam proportioning device and returns same to storage	
Team creates a workable foam line; tests line for foam operation prior to an attack A safe haven is identified prior to advancing a hose line Eductor/foam proportioning device is properly set for the foam being used on the given fire Attack is made from upwind direction (where possible) Foam applied using a proper foam application technique (rain down, roll-over, bank down) Knockdown/Extinguishment is achieved in a timely fashion Team properly retreats/backs away from the fire, prevents re-flash, and safe haven reached CANDIDATES SWITCH POSITIONS AND REPEAT TASKS 5 THRU 13 Team properly flushes foam educator/foam proportioning device, and nozzle Team disassembles foam eductor/ foam proportioning device and nozzle and returns same to storage	
A safe haven is identified prior to advancing a hose line Eductor/foam proportioning device is properly set for the foam being used on the given fire Attack is made from upwind direction (where possible) Foam applied using a proper foam application technique (rain down, roll-over, bank down) Knockdown/Extinguishment is achieved in a timely fashion Team properly retreats/backs away from the fire, prevents re-flash, and safe haven reached CANDIDATES SWITCH POSITIONS AND REPEAT TASKS 5 THRU 13 Team properly flushes foam educator/foam proportioning device, and nozzle Team disassembles foam eductor/ foam proportioning device and returns same to storage	
Eductor/foam proportioning device is properly set for the foam being used on the given fire Attack is made from upwind direction (where possible) Foam applied using a proper foam application technique (rain down, roll-over, bank down) Knockdown/Extinguishment is achieved in a timely fashion Team properly retreats/backs away from the fire, prevents re-flash, and safe haven reached CANDIDATES SWITCH POSITIONS AND REPEAT TASKS 5 THRU 13 Team properly flushes foam educator/foam proportioning device, and nozzle Team disassembles foam eductor/ foam proportioning device and nozzle and returns same to storage	
Attack is made from upwind direction (where possible) Foam applied using a proper foam application technique (rain down, roll-over, bank down) Knockdown/Extinguishment is achieved in a timely fashion Team properly retreats/backs away from the fire, prevents re-flash, and safe haven reached CANDIDATES SWITCH POSITIONS AND REPEAT TASKS 5 THRU 13 Team properly flushes foam educator/foam proportioning device, and nozzle Team disassembles foam eductor/ foam proportioning device and returns same to storage	
Foam applied using a proper foam application technique (rain down, roll-over, bank down) Knockdown/Extinguishment is achieved in a timely fashion Team properly retreats/backs away from the fire, prevents re-flash, and safe haven reached CANDIDATES SWITCH POSITIONS AND REPEAT TASKS 5 THRU 13 Team properly flushes foam educator/foam proportioning device, and nozzle Team disassembles foam eductor/ foam proportioning device and nozzle and returns same to storage	
8 Knockdown/Extinguishment is achieved in a timely fashion 9 Team properly retreats/backs away from the fire, prevents re-flash, and safe haven reached **CANDIDATES SWITCH POSITIONS AND REPEAT TASKS 5 THRU 13** 10 Team properly flushes foam educator/foam proportioning device, and nozzle 11 Team disassembles foam eductor/ foam proportioning device and returns same to storage	
Team properly retreats/backs away from the fire, prevents re-flash, and safe haven reached **CANDIDATES SWITCH POSITIONS AND REPEAT TASKS 5 THRU 13** Team properly flushes foam educator/foam proportioning device, and nozzle Team disassembles foam eductor/ foam proportioning device and nozzle and returns same to storage	+
CANDIDATES SWITCH POSITIONS AND REPEAT TASKS 5 THRU 13 10 Team properly flushes foam educator/foam proportioning device, and nozzle 11 Team disassembles foam eductor/ foam proportioning device and nozzle and returns same to storage	
10 Team properly flushes foam educator/foam proportioning device, and nozzle 11 Team disassembles foam eductor/ foam proportioning device and nozzle and returns same to storage	
11 Team disassembles foam eductor/ foam proportioning device and nozzle and returns same to storage	
12 Completes an tasks without compromising personal of team safety	
Please circle final skill outcome PAS	e PASS FAI
Evaluator Comments:	



STATION D: Sprinkler D	rain / Pressures	Reference NFPA 1001 (201) Random Station: JPR 5.5.3	, <u>=</u>
Test Site	Test Date	Candidate #	Check the Test Type
			InitialRetest

Evaluator Note: Provide the candidate with the pressure recording form. Review the candidate's documented pressure reading to evaluate Tasks #5, 9, and 10.

Directions: Locate and identify the sprinkler components for both a wet and dry pipe sprinkler system; then identify the procedure to / open and close the main drain valve on the wet pipe system. Next, read and record the appropriate pressures (system, air, and water) for both sprinkler systems on the sheet provided. Do you have any questions?

Performance Outcome: Pass/ Fail is determined by 8 of 11 tasks being correctly performed.

No.	Tasks	Yes	No
	WET-PIPE SYSTEM		
1	Identifies the main water control valve		
2	Identifies the main drain valve.		
3	Describes the procedure used to close / open the main water control valve		
4	Describes the procedure used to open / closes the main drain valve		
5	Documents the "system pressure" (PSI)		
	DRY-PIPE SYSTEM		
6	Identifies the main water control valve		
7	Identifies the dry-pipe valve		
8	Identifies the main drain valve.		
9	Documents the systems "water pressure" (PSI)		
10	Documents the systems "air pressure" (PSI)		
11	Completes all tasks without compromising personal team safety and wearing appropriate PPE (Mandatory to PASS)		
	Please circle final skill outcome	PASS	FAIL
Eva	luator Comments:		
Eva	luator Signature: Evaluator #		



STATION D: Sprinkler D	rain / Pressures	Reference NFPA 1001 (201 Random Station: JPR 5.5.3	
Test Site	Test Date	Candidate #	Check the Test Type
			InitialRetest

Pressure Recording Form

System Pressure Gauge:	
Water Pressure Gauge:	
Air Pressure Gauge:	

NOTE: All pressure readings **MUST** be recorded in Pounds Per Square Inch.



STATION E: Fire Safety Presentation		Reference NFPA 10 Random Station: JI	001 (2019 Edition) Chapter 5 PR 5.5.2
Test Site	Test Date	Candidate #	Check the Test Type
			InitialRetest
Evaluator Noto: Provide t	he candidate with the fi	re safety presentation/station t	tour log form Review the candidate's

Evaluator Note: Provide the candidate with the fire safety presentation/station tour log form. Review the candidate's documented presentation log form to ensure accuracy based on the topic/scenario given.

Directions: Given a fire safety presentation assignment, present a fire safety program to a **small** group or station visitors. The presentation should be brief (i.e., 5-10 minutes) yet informative and accurate. Answer all questions posed. Then document your fire safety presentation. Do you have any questions?

Performance Outcome: Pass / Fail is determined by 6 of 8 tasks being correctly performed.

No.	Tasks	Yes	No
1	Identifies self and organization		
2	Defines the topic		
3	Selects and explains the importance of the topic		
4	Uses informative and accurate information		
5	Demonstrates the ability to summarizes information		
6	Checks for and addresses questions appropriately		
7	Documents delivery of the presentation according to SOPs		
8	Completes the task in a professional manner		
	Please circle final skill outcome	PASS	FAIL
Eva	luator Signature: Evaluator #		



STATION E: Fire Safety P	resentation	Reference NFPA 1001 (201) Random Station: JPR 5.5.2	
Test Site	Test Date	Candidate #	Check the Test Type
			InitialRetest

Fire Safety Presentation / Station Tour Log

Date: _		Time:	:
Location: _			
			Range:
Contact:		Phon	ne:
Торіс:			
Iaterials Used	:		
	Computer/Projector	Brochures/Handouts	Telephone
	Audio/Visual Aids	Smoke Detector(s)	PPE
	Puppets/Costumes	Fire Extinguisher(s)	SCBA
	Other Training Aid(s):		
<u>Narrative</u> :			
Presenter:			Date:



STATION F: Inspection / I Power Tools	Maintenance – Generator, and Lighting Equipment	Reference NFPA 1001 (201) Random Station: JPR 5.5.4	
Test Site Test Date		Candidate #	Check the Test Type
			InitialRetest

Directions: Demonstrate your ability to maintain power plants (generator/inverter), power tools, and lighting equipment by performing a routine inspection of each unit provided. Describe what you are checking, and the conditions found during each inspection. Explain to the evaluator the necessary maintenance that would occur for each piece of equipment after use. Document your inspection and notify the evaluator if the equipment is in the ready state or needs repairs. Do you have any questions?

Performance Outcome: Pass / Fail is determined by **12 of 16** tasks being correctly performed.

No.	Task Steps	Yes	No
	POWER SOURCE: GENERATOR / INVERTER (Portable or Vehicle Mounted)		
	Evaluator indicates the type of power source:		
1	Checks all fluids in of power plant to assure acceptable level (i.e., fuel, oil) (Mandatory to PASS)		
2	Checks all applicable components (e.g., spark plug & wire, belts, hoses, cords, connections, etc.)		
3	Checks entire unit for visible damage		
4	Turns on and operates the power plant (Mandatory to PASS)		
5	Turns off the power plant (Automatic Failure if turned off under load)		
6	Describes the necessary maintenance that would occur after use to be placed in a ready state		
	LIGHTING EQUIPMENT		
	Evaluator indicates the type of lighting equipment:		
7	Checks electrical cords for damage		
8	Checks entire unit for visible damage		
9	Sets-up and operates the lighting equipment (Mandatory to PASS)		
10	Describes the necessary maintenance that would occur after use to be placed in a ready state		
	POWER TOOL (Evaluator, please indicate the tool to inspect)		
	Power Tool Inspected:		
11	Checks all power tool components and accessories (i.e., chains/blades)		
12	Checks to determine guards and safety devices are in place and operable (Mandatory to PASS)		
13	Describes the necessary maintenance that would occur after use to be placed in a ready state		
14	Checks operating status of power tool while the generator is running (Mandatory to PASS)		
15	Operates tool safely and as intended (Mandatory to PASS)		
16	Completes all tasks without compromising personal team safety and wearing appropriate PPE (Mandatory to PASS)		
	Please circle final skill outcome	PASS	FAIL
Eva	luator Comments:		
Eva	luator Signature: Evaluator #		
Febru	ary 2025		



STATION F: Inspection / I Power Tools	Maintenance – Generator, and Lighting Equipment	Reference NFPA 1001 (2019 Edition) Chapter 5 Random Station: JPR 5.5.4		
Test Site	Test Date	Candidate #	Check the Test Type	
			Retest	

Directions: After inspecting each unit (i.e., power plant, lighting equipment, power tool), document your actions and findings; Indicate whether the unit is in a ready state for use, or out-of-service and in need of repair. If any item/component is not in a ready state, briefly document the issue.

POWER SOURCE: GENERATOR / INVERTER (Describe items in need of service in the space provided)	Operational	Service Needed
Unit Condition (i.e., damage)		
Fluids		
Unit Components (e.g., ignition system, exhaust system, etc.)		
Unit operational		
Is the power plant ready for use? Yes No (If no, explain)		
LIGHTING EQUIPMENT		
Unit Condition (i.e., damage)		
Electrical cords		
Unit operational		
Is the lighting equipment ready for use? Yes No (If no, explain)		
POWER TOOL		
Unit Condition (e.g., damage, all parts present, etc.)		
Fluids (if applicable)		
Unit operational		
Is the power tool ready for use? Yes No (If no, explain)		
Candidate Signature:		



STATION G: Hose - Service Testing		Reference NFPA 1001 (2019 Edition) Chapter 5 Random Station: JPR 5.5.5		
Test Site	Test Date	Candidate # Check the Test Type		
			InitialRetest	

Evaluator Note: For efficiency in skill testing, a full three (3) minutes need not be maintained once pressure is reached.

Directions: Using the equipment provided, conduct an annual service test on a 50-foot section of hose. Instruct the pump operator when you need the valves opened/closed and pressures increased/decreased. When done, document your test. Do you have any questions?

Performance Outcome: Pass / Fail is determined by 15 of 21 tasks being correctly performed.

No.	Tasks	Yes	No
1	Performs inspection of the hose and couplings (free of debris and/or signs of damage)		
2	Extends hose so that it is laid out straight without kinks or twists		
3	Checks hose gaskets were checked prior to making any connection		
4	Demonstrates ability to properly connect couplings and connections are spanner wrench tight		
5	Assembles configuration so the test gate valve is attached to pumper discharge, the hose is connected to the test gate valve, and the hose is anchored to the pumper at the test gate valve		
7	Secures rope hose tool/rope/strap 10" to 15" from the test gate valve. (Mandatory to PASS)		
8	Utilizes and connects an appropriate nozzle to the end of the test hose.		
9	Demonstrates ability to bleed off air in the hose line (Mandatory to PASS)		
10	Raises nozzle above the level of the pump discharge while bleeding the hose-line.		
11	Applies marks at hose couplings to check for creep (Mandatory to PASS)		
12	Secures leaking couplings to mitigate water loss (tightened, gasket changed)		
13	Checks to assure hose test gate valve is completely closed (Mandatory to PASS)		
14	Notifies pump operator of test pressure based on NFPA 1962 (2013 Ed.)		
	 Any fire hose marked must be service tested to the pressure stamped/marked on the hose. Attack fire hose not marked must be tested to a minimum of 300 psi. Supply fire hose not marked must be tested to a minimum of 200 psi 		
15	Notifies pump operator to increase pressure at an acceptable rate (i.e., 15 PSI per second) until desired pressure is attained <i>(Mandatory to PASS)</i>		
16	Three (3) minute timeframe is ordered for maintaining pressure		
17	Notifies pump operator to slowly reduce pressure and close the discharge valve		
18	Performs pressure bleed-off at the nozzle and dismantles hose and nozzle and drains the hose		
19	Checks marks made at the hose couplings to determine if any coupling creep occurred		
20	Documents test results and reports same to the evaluator		
21	Completes all tasks without compromising personal team safety and wearing appropriate PPE (Mandatory to PASS)		
Eva	Please circle final skill outcome luator Comments:	PASS	FAIL
	luator Signature: Evaluator #		
Febru	ary 2025		



STATION G: Hose - Service Testing		Reference NFPA 1001 (201) Random Station: JPR 5.5.5	, <u> </u>
Test Site	Test Date	Candidate #	Check the Test Type
			Retest

Directions: Document the hose test information, condition of the hose, the results, and any remarks.

Test Date	Hose ID No.	Hose Size	Hose Length	Condition	Service Test Pressure	Pass/Fail	Remarks



STATION H: Fire Scene Preservation		Reference NFPA 1001 (2019 Edition) Chapter 5 Random Station: JPR 5.3.4		
Test Site	Test Date	Candidate #	Check the Test Type	
			Retest	

Evaluator Note: An additional sheet is provided for the candidate to document the scene. Please review the candidate's notes and information to evaluate Tasks 2, 3, 4, and 9.

Directions: Using the equipment and tools provided, examine the fire scene, secure the area from further disturbance, note any possible evidence of cause/origin, notify (through your evaluator) any investigative or legal authorities needed, and take any other measures appropriate to conditions found. Do you have any questions?

Performance Outcome: Pass / Fail is determined by 7 of 10 tasks being correctly performed.

No.	Tasks	Yes	No
1	Candidate physically secures site, denies entry through the use of barrier tape, barricades, or		
	posting a guard.		
	Candidate records the following data on the clipboard provided		
2	What evidence was noted?		
3	Was any evidence disturbed? If so, how?		
4	Was evidence moved? If moved, where, how, and why?		
	Candidate deals appropriately with loss of life issues		
5	Candidate calls for coroner / medical examiner.		
6	Candidate calls for fire marshal investigative team.		
7	Candidate calls for law enforcement investigative team.		
8	Candidate preserves the dignity of deceased; covers remains from public view.		
9	If remains were moved, records position and location where initially found, and why moved?		
10	Completes all tasks in a professional manner and without compromising personal safety (Mandatory to PASS)		
	Please circle final skill outcome	PASS	FAIL
Eva	luator Comments:		
	luator Signature: Evaluator #ary 2025		



STATION H: Fire Scene Preservation		Reference NFPA 1001 (2019 Edition) Chapter 5 Random Station: JPR 5.3.4		
Test Site	Test Date	Candidate #	Check the Test Type	
			InitialRetest	

CANDIDATE'S NOTES AND DOCUMENTATION

