

Project Description

The project includes rehabilitation of the superstructure of the Route 741 bridge (Millersville Road) over Little Conestoga Creek in Manor Township, Lancaster County. The purpose of this project is to provide a continued safe and efficient crossing on Route 741 over Little Conestoga Creek.

The project includes rehabilitation of the existing superstructure. Superstructure repairs include replacement of the existing asphalt plug expansion with a neoprene strip seal dam (3" movement) joint and painting of the existing steel beams. The horizontal and vertical geometries will remain unchanged.

Environmental

The project is located in an urban setting. No bicycle or pedestrian facilities exist within project limits. Other environmental efforts for the project include investigating historical, archeological, and aquatic resources as well as threatened and endangered species.

Utilities

There are no anticipated utilities impacts within the project limits. No utilities are anticipated to be relocated prior to construction.

Right-of-way

Permanent and temporary right-of-way acquisitions are not anticipated for this project.

Maintenance and Protection of Traffic

Long-term staged temporary traffic control will be implemented for the duration of construction for Route 741. The use of the adjacent intersection of Wheaton Drive and Route 741 may be impacted during construction.

Schedule and Cost

Overall construction is anticipated to last approximately 4 months during the Fall of 2026 or Spring of 2027 at an estimated cost of \$250,000.